NI 43-101 Technical Report

Goldstrike Project, Utah, USA

Heliostar Metals Ltd.

Prepared by:

SLR Consulting (Canada) Ltd.

SLR Project No.: 201.089829.00001

Effective Date:

March 23, 2026

Signature Date:

May 6, 2026

Revision: A

Qualified Persons:
Lorraine Tam, P.Geo.
Gary L. Simmons, QP MMSA

NI 43-101 Technical Report, Goldstrike Project, Utah, USA

SLR Project No.: 675.073103.00001

Prepared by
SLR Consulting (Canada) Ltd.
55 University Ave., Suite 501
Toronto, ON M5J 2H7
for
Heliostar Metals Ltd.
Suite 1723, 595 Burrard Street
Vancouver, BC, Canada V7X 1J1

Effective Date - March 23, 2026
Signature Date - May 6, 2026

Prepared by:
Lorraine Tam, P.Geo.
Gary L. Simmons, QP MMSA.

Peer Reviewed by:
Valerie Wilson, M.Sc., P.Geo.

Approved by:

Project Manager
Valerie Wilson, M.Sc., P.Geo.

Table of Contents

1.0 Summary 1-1
1.1 Executive Summary 1-1
1.2 Technical Summary 1-5
2.0 Introduction 2-1
2.1 Site Visits 2-1
2.2 Sources of Information 2-2
2.3 Acknowledgements 2-3
2.4 List of Abbreviations 2-3
3.0 Reliance on Other Experts 3-1
4.0 Property Description and Location 4-1
4.1 Property Location 4-1
4.2 Mineral Tenure 4-1
4.3 Underlying Agreements and Encumbrances 4-7
4.4 Permits and Authorization 4-8
4.5 Environmental Considerations 4-8
4.6 Mining Rights of the Goldstrike Project 4-10
4.7 Environmental Liabilities, Permitting, and Other Significant Factors or Risks 4-11
5.0 Accessibility, Climate, Local Resources, Infrastructure and Physiography 5-1
5.1 Accessibility 5-1
5.2 Local Resources and Infrastructure 5-1
5.3 Climate 5-1
5.4 Physiography and Vegetation 5-1
6.0 History 6-1
6.1 Early Historical Prospecting and Mining 6-1
6.2 Modern Historical Exploration Campaigns 6-1
6.3 Surface Exploration 6-5
6.4 Historical Estimates 6-11
6.5 Past Production 6-12
7.0 Geological Setting and Mineralization 7-1
7.1 Regional Geology 7-1
7.2 Property Geology 7-3
7.3 Alteration 7-14
7.4 Mineralization 7-16

8.0 Deposit Types 8-1
9.0 Exploration 9-1
9.1 Liberty Gold Compilation 9-1
9.2 Liberty Gold Geologic Mapping 9-1
9.3 Liberty Gold Soil Sampling 9-2
9.4 Liberty Gold Rock Sampling 9-4
9.5 Liberty Gold Three-Dimensional Modelling 9-7
9.6 Liberty Gold Induced Polarity Geophysics 9-7
9.7 Summary Statement on Surface Exploration by Liberty Gold 9-13
10.0 Drilling 10-1
10.1 Historical Drilling 10-1
10.2 Liberty Gold Drilling, 2015 to 2022 10-5
10.3 SLR Comments 10-17
11.0 Sample Preparation, Analyses, and Security 11-1
11.1 Historical Drilling Programs 11-1
11.2 Specific Gravity Data 11-5
11.3 Quality Assurance and Quality Control Programs 11-5
12.0 Data Verification 12-1
12.1 Verifications by Liberty Gold – Drill Hole Database 12-1
12.2 Verifications by GL Simmons Consulting, LLC 12-2
12.3 Verifications by SLR 12-2
13.0 Mineral Processing and Metallurgical Testing 13-1
13.1 Historical Metallurgical Testing 13-1
13.2 Phase 1 - Liberty Gold Metallurgical Test Program 13-1
13.3 Phase 2 - Liberty Gold Metallurgical Test Program 13-7
13.4 Phase 3 - Liberty Gold Metallurgical Test Program 13-13
13.5 Phase 4 – Head Assays and Bottle Roll Leach Testing (KCA) 13-24
13.6 Comments on Metallurgical Sampling and Testing 13-28
13.7 Gold and Silver Recovery Models 13-28
14.0 Mineral Resource Estimates 14-1
14.1 Summary 14-1
14.2 Comparison to Previous Resources 14-2
14.3 Mineral Resource Cut-off Grades 14-2
14.4 Resource Database 14-3

14.5 Geological Interpretation 14-6
14.6 Resource Assays 14-15
14.7 Compositing 14-19
14.8 Trend Analysis 14-20
14.9 Search Strategy and Grade Interpolation Parameters 14-22
14.10 Bulk Density 14-25
14.11 Block Models 14-26
14.12 Cut-off Grade and Whittle Parameters 14-26
14.13 Classification 14-27
14.14 Block Model Validation 14-30
14.15 Grade Tonnage Sensitivity 14-35
14.16 Mineral Resource Reporting 14-36
15.0 Mineral Reserve Estimates 15-1
16.0 Mining Methods 16-1
17.0 Recovery Methods 17-1
18.0 Project Infrastructure 18-1
19.0 Market Studies and Contracts 19-1
20.0 Environmental Studies, Permitting, and Social or Community Impact 20-1
21.0 Capital and Operating Costs 21-1
22.0 Economic Analysis 22-1
23.0 Adjacent Properties 23-1
24.0 Other Relevant Data and Information 24-1
25.0 Interpretation and Conclusions 25-1
26.0 Recommendations 26-1
27.0 References 27-1
28.0 Date and Signature Date 28-1
29.0 Certificate of Qualified Person 29-1
29.1 Lorraine Tam 29-1
29.2 Gary L. Simmons 29-3
30.0 Appendix 1 30-1
30.1 Land Tenure 30-1

Tables

Table 1-1: Summary of Mineral Resources as of March 23, 2026 1-1

Table 1-2: Estimated Cost for the Advanced Exploration Program Proposed for the Goldstrike Project 1-4
Table 4-1: Annual Claim Maintenance Fees for the Goldstrike Property 4-5
Table 6-1: Summary 1912 to 1942 Gold–Silver Production of the Goldstrike District 6-12
Table 6-2: Summary of Goldstrike 1988 to 1996 Gold Production by Pit 6-13
Table 6-3: Annual Gold and Silver Production 1988 to 1996 (Willden 2006) 6-14
Table 10-1: Summary of Historical Drilling in Heliostar's Database 10-1
Table 10-2: Summary of 2015 to 2022 Liberty Gold Drilling 10-5
Table 11-1: Liberty Gold Certificate Standards 11-12
Table 12-1: Verification of Drill Hole Collar Locations During Site Visit 12-4
Table 13-1: Goldstrike Phase Comminution Testing 13-4
Table 13-2: Abrasion Index Test Results 13-5
Table 13-3: Summary Phase-1 Goldstrike Bottle Roll and Column Leach Test Results 13-6
Table 13-4: Summary Phase-2 Goldstrike Bottle Roll and Column Leach Test Results 13-11
Table 13-5: Bulk Sample Location Areas 13-14
Table 13-6: Sonic Master Composite Assays 13-17
Table 13-7: Bulk Sample Head Assays 13-18
Table 13-8: Summary of Sonic Leach Pad, Pad Backfill and Mine Waste Dump Composites, Bottle Roll and Column Leach Test Results 13-19
Table 13-9: Sonic Drill Column Leach Crush Size and Charge Weight Data 13-20
Table 13-10: Summary of Load Permeability Test Results for Sonic Drill Composites 13-21
Table 13-11: Summary of Bulk Sample Bottle Roll and Column Leach Test Results 13-22
Table 13-12: Bulk Sample Column Leach Crush Size and Charge Weight Data 13-22
Table 13-13: Summary of Load Permeability Test Results for Sonic Drill Composites 13-23
Table 13-14: Phase 4 Bottle Roll Test Results 13-27
Table 13-15: Goldstrike – Coarse Crush/Agglomeration Gold Recovery Equations 13-32
Table 13-16: Goldstrike – Coarse Crush/Agglomeration Silver Recovery Equations 13-32
Table 13-17: Goldstrike Leach Pad 1 and 2, Agglomeration Gold Recovery Equations 13-33
Table 13-18: Goldstrike Leach Pad 1 and 2, Agglomeration Silver Recovery Equations 13-33
Table 14-1: Summary of Mineral Resources – March 23, 2026 14-1
Table 14-2: Comparison of Previous and Current Mineral Resource Estimates 14-2
Table 14-3: Goldstrike Resource Cut-off Grade Summary 14-3
Table 14-4: Summary of Drill Holes Supporting the Block Model Estimation 14-4
Table 14-5: Goldstrike Mineralization Domain Wireframes 14-8
Table 14-6: Gold Capped and Uncapped Assay Statistics 14-15

Table 14-7: Silver Uncapped Assay Statistics 14-18
Table 14-8: Gold Composite Statistics 14-19
Table 14-9: Silver Composite Statistics 14-20
Table 14-10: Search and Grade Interpolation Parameters 14-23
Table 14-11: Block Model Densities by Lithology 14-25
Table 14-12: Goldstrike Block Model Parameters 14-26
Table 14-13: Goldstrike Whittle Pit Optimization Parameters 14-26
Table 14-14: Block Model Validation Statistical Checks 14-33
Table 14-15: Summary of Mineral Resources by Area – Effective Date March 23, 2026 14-36
Table 26-1: Estimated Cost for the Advanced Exploration Program Proposed for the Goldstrike Project 26-2

Figures

Figure 4-1: Location of the Goldstrike Project 4-3
Figure 4-2: Land Tenure Map of the Goldstrike Property 4-4
Figure 4-3: Patented Claims, Placer Claims and Historical Workings Located in Beaverdam Wash 4-6
Figure 4-4: Aerial View Showing the Reclaimed Goldstrike Mine Area, and Typical Landscape of the Project Area, Looking East 4-10
Figure 6-1: Map of Goldstrike Production Areas Mined 1988 to 1996 6-2
Figure 6-2: Map of Historical Exploration and Drilling Areas, Goldstrike Project 6-3
Figure 6-3: Reduced to Pole Magnetic Map of the Goldstrike Property 6-7
Figure 6-4: Total Count Radiometrics Map of the Goldstrike Property 6-8
Figure 6-5: Gradient Array Apparent Resistivity Map of the Goldstrike Property 6-9
Figure 7-1: Generalized Geological Map of the Goldstrike Property 7-2
Figure 7-2: Geological Map of the Goldstrike Mine Trend 7-4
Figure 7-3: Stratigraphic Column for Paleozoic Rocks in the Goldstrike Project Area 7-5
Figure 7-4: Stratigraphic Column for Cenozoic Rocks of the Goldstrike Project Area 7-6
Figure 7-5: Relative Positions of the Major Structures and Pits from the 1988 to 1996 Mining 7-13
Figure 7-6: Examples of Alteration and Mineralization at Goldstrike 7-16
Figure 7-7: View of the Syn-Mineral Hamburg Fault, Hamburg Pit 7-17
Figure 7-8: Generalized Target Concept for Mineralization at Goldstrike 7-18
Figure 7-9: Altered Intrusive Rock along a Fault in the Upper Hamburg Mine Area 7-19
Figure 7-10: High-Grade Antimony Mineralization in Outcrop 7-21

Figure 8-1: Cross-Section of a Hypothetical Carlin-style Sediment-hosted Gold Deposit 8-2
Figure 9-1: All Historical and Liberty Gold Soil Samples at Goldstrike 9-3
Figure 9-2: All Historical and Liberty Gold Rock Samples at Goldstrike 9-5
Figure 9-3: Plan Map of Goldstrike Area Showing Select Antimony Values in Rock Samples 9-6
Figure 9-4: Map Showing Induced Polarity Lines, Goldstrike 2017 Program 9-8
Figure 9-5: IP Chargeability 2D Inversion Sections, Goldstrike 2017 Program 9-10
Figure 9-6: Resistivity 2D Inversion Sections, Goldstrike 2017 Program 9-12
Figure 9-7: Interpreted Geology on Resistivity – Line 4300E, Goldstrike 2017 Program ...9-13
Figure 10-1: General Map of Historical and Liberty Gold Drilling Sites.....10-3
Figure 10-2: Drilling by Company and Year.....10-4
Figure 10-3: Vertical Section Locations, Main Area and Peg Leg to Dip Slope Zone.....10-9
Figure 10-4: Hassayampa-Hamburg Pit Section, View to the East 10-10
Figure 10-5: Dip Slope - Aggie - Peg Leg Cross Section, View to the East.....10-11
Figure 10-6: Moosehead Pit Section, View to the Northeast 10-15
Figure 11-1: Hunter Assays of Duplicates Relative to Original Hunter Analyses.....11-8
Figure 11-2: Talco Check Assays Relative to Original Hunter Analyses 11-9
Figure 11-3: Cone Assays of Duplicates Relative to Original Rocky Mountain Analyses ...11-10
Figure 11-4: Rocky Mountain Assays of Cuttings Duplicates Relative to Original Rocky Mountain Analyses 11-11
Figure 11-5: Chart of Standard Performance for Goldstrike Standard Au19.09 11-14
Figure 11-6: Chart of Standard Performance for Goldstrike Standard Au19.10 11-14
Figure 11-7: Chart of Standard Performance for Goldstrike Standard CDN-GS-P6A 11-15
Figure 11-8: Chart of Standard Performance for Goldstrike Standard FGS2011A.....11-15
Figure 11-9: Chart of Standard Performance for Goldstrike Standard LG21.01 11-15
Figure 11-10: Chart of Standard Performance for Goldstrike Standard LG21.02.....11-16
Figure 11-11: Chart of Standard Performance for Goldstrike Standard LG19001 11-16
Figure 11-12: Chart of Standard Performance for Goldstrike Standard OxA71.....11-16
Figure 11-13: Chart of Standard Performance for Goldstrike Standard OxD57 11-17
Figure 11-14: Chart of Standard Performance for Goldstrike Standard OxD87 11-17
Figure 11-15: Chart of Standard Performance for Goldstrike Standard OxF65.....11-17
Figure 11-16: Chart of Standard Performance for Goldstrike Standard OxF85.....11-18
Figure 11-17: Chart of Standard Performance for Goldstrike Standard OxJ68 11-18
Figure 11-18: Chart of Standard Performance for Goldstrike Standard Oxi54 11-18
Figure 11-19: Chart of Standard Performance for Goldstrike Standard PG13001X.....11-19

Figure 11-20: Chart of Standard Performance for Goldstrike Standard PG13002X 11-19
Figure 11-21: Chart of Standard Performance for Goldstrike Standard PG14001X 11-19
Figure 11-22: Chart of Standard Performance for Goldstrike Standard SE58 11-20
Figure 11-23: Chart of Standard Performance for Goldstrike Standard SG40 11-20
Figure 11-24: Chart of Standard Performance for Goldstrike Standard Si54 11-20
Figure 11-25: 2015 to 2022 Blank Performance, Goldstrike Drill Program 11-21
Figure 11-26: Liberty Gold Field Duplicate Data 11-22
Figure 11-27: 2015 – 2022 Liberty Gold Preparation Duplicate Data 11-23
Figure 11-28: 2015 – 2025 Liberty Gold Analytical Duplicate Data 11-24
Figure 11-29: Comparison of ALS Primary and BV Check Assays 11-25
Figure 11-30: Percent Difference Graph of BV Check Assays versus ALS Assays 11-26
Figure 12-1: Liberty Gold Drill Hole Collar Location (PGS741) 12-4
Figure 13-1: Phase 1 - Goldstrike Project Metallurgical Core Plan Map 13-2
Figure 13-2: Phase 2 - Project Metallurgical Core Map 13-8
Figure 13-3: Phase 3 – Sonic Drill Hole and Bulk Sample Location Map 13-16
Figure 13-4: Cross-Section Through the Main Zone Looking East 13-30
Figure 14-1: Goldstrike Project Areas Included in the Mineral Resource Estimate 14-5
Figure 14-2: Example Cross-Section Through the Main Zone Geological Model (Section 244,450E) 14-7
Figure 14-3: Plan View of Goldstrike Gold Mineralization Domains 14-9
Figure 14-4: Cross-Section View of Goldstrike Gold Mineralization Domains in the Main Zone 14-10
Figure 14-5: Plan View Showing Locations of Backfill, Waste Dumps, and Heap-Leach Pads 14-12
Figure 14-6: Vertical-Section Through Main Zone Sulphide Model Showing Zones of AuCN < 40% 14-14
Figure 14-7: Histogram for Main Zone Raw Assays (Zoomed in on the axes) 14-17
Figure 14-8: Log Probability Plot for Main Zone Raw Assays 14-17
Figure 14-9: Grade Contours Showing the Mineralized Trends in the Main Zone 14-21
Figure 14-10: Variogram Model – Main Area Domain 206 14-22
Figure 14-11: Section Through Main Zone Domain 206 Showing Variable Orientation Directions 14-24
Figure 14-12: Plan View of the Classified Open Pit Resource – All Deposit Areas 14-28
Figure 14-13: Cross-Section Through the Classified Open-Pit Resource Blocks in the Main Zone 14-29
Figure 14-14: Plan and Cross-Section Views Through Main Zone Domain 206 14-31

Figure 14-15: Section and Planar Views Through Beavertail Domains 4100 and 4208 14-32
Figure 14-16: Main Zone Swath Plots 14-34
Figure 14-17: Indicated and Inferred Gold Mineral Resource Grade Tonnage Curves 14-35

Appendix Tables

Table 30-1: List of Unpatented Mining Claims, Goldstrike Property, Washington Country, Utah 30-1
Table 30-2: Claims and Lease Payments Effective 23 March 2026 30-21
Table 30-3: List of Unpatented Placer Mining Claims, Goldstrike Property, Washington County, Utah 30-23
Table 30-4: List of Patented Mining Claims, Goldstrike Property, Washington County, Utah 30-24
Table 30-5: Jennings and Goldstrike Thiriot, LLC Property Lease 30-26
Table 30-6: Utah State Institutional Trust Lands Administration Lease, Washington County, Utah 30-26

1.0 Summary

1.1 Executive Summary

SLR Consulting (Canada) Ltd. (SLR) was retained by Heliostar Metals Ltd. (Heliostar) to prepare an independent Technical Report on the Goldstrike Project (Goldstrike, the Project, or the Property), located in Washington County, Utah, USA. The purpose of this report is to disclose the results of an updated Mineral Resource estimate, following the acquisition of the Project by Heliostar from Liberty Gold Corp (Liberty Gold). This report, with an effective date of March 23, 2026 (the Effective Date), conforms to National Instrument 43-101 Standards of Disclosure for Mineral Projects (NI 43-101). SLR's Qualified Person (QP) visited the Property on March 5, 2025. The GL Simmons Consulting, LLC (GL Simmons) QP, responsible for the metallurgical sections of this report, visited the site on multiple occasions, with the most recent site visit on May 16, 2022.

The Mineral Resource estimate presented in this Technical Report supersedes all prior resource estimates for the Project as well as the 2018 Preliminary Economic Assessment (PEA) prepared by SRK Consulting (Canada) Inc. (SRK), which is no longer current and should not be relied upon.

Heliostar is an emerging mid-tier gold producer with two operating mines in Mexico, La Colorada in Sonora and San Agustin in Durango. The company also has a strong portfolio of development projects in Mexico and the USA, including its flagship Ana Paula projects in Guerrero, the Cerro del Gallo project in Guanajuato, the San Antonio project in Baja Sur, and the Unga project in Alaska, USA. Heliostar is listed on the TSX Venture Exchange (TSX-V:HSTR) and holds its interest in the Project through its wholly owned subsidiary, Helio Five Resources Ltd.

Heliostar is the 100% owner of federal lode claims and patented claim leases hosting the Mineral Resource at the Goldstrike property, having acquired the Property in March 2026 through the purchase of Specialty American Metals Inc., a wholly owned British Columbia-based subsidiary of Liberty Gold Corp. (Heliostar, 2026).

The Goldstrike Project was the site of open-pit mining and cyanide heap-leach processing from 1988 to 1996.

The total estimated Mineral Resources at the Project are presented in Table 1-1. The Mineral Resources comprise approximately 65.8 million tonnes (Mt) at an average grade of 0.46 g/t Au containing approximately 975 thousand ounces (koz) in the Indicated category and approximately 8.9 Mt at an average grade of 0.31 g/t Au containing approximately 90 koz Au in the Inferred Mineral Resources category. There are no Measured Mineral Resources. Canadian Institute of Mining, Metallurgy and Petroleum (CIM) Definition Standards for Mineral Resources and Mineral Reserves (CIM (2014) definitions) were followed for Mineral Resource classification.

Table 1-1: Summary of Mineral Resources as of March 23, 2026

Classification	Tonnage (000 t)	Grade (g/t Au)	Contained Metal (000 oz Au)
Indicated	65,804	0.46	975
Inferred	8,860	0.31	90
Notes:			

1. CIM (2014) definitions were followed for Mineral Resources.
2. Mineral Resources are estimated at a gold cut-off grade of 0.10 g/t and using a long-term gold price of US$2,000 per ounce.
3. Mineral Resources are estimated using a variable recovery derived from metallurgical studies.
4. Bulk density is variable by rock type.
5. There are no Mineral Reserves currently estimated at the Goldstrike Project.
6. Mineral Resources that are not Mineral Reserves do not have demonstrated economic viability.
7. Mineral Resources are reported within conceptual open-pit shells.
8. Rounding as required by reporting guidelines may result in apparent discrepancies between tonnes, grades, and contained gold content.
9. The effective date of the Mineral Resource estimate is March 23, 2026.

Recent surface exploration activities in the southeastern portion of the Property have discovered extensive zones of antimony mineralization, resulting in staking of additional claims.

The QPs are not aware of any environmental, permitting, legal, title, taxation, socio-economic, marketing, political, or other relevant factors not discussed in this report that could materially affect the potential development of the Goldstrike Mineral Resources as of the Effective Date of the report.

1.1.1 Conclusions

SLR has reviewed the Goldstrike 2015–2024 project data, examined the drill data in the context of the property geology and mineralization, provided an updated resource estimate, and visited the Project site. SLR is unaware of any significant risks or uncertainties that could be expected to affect the reliability of the exploration information presented in this report, and the data provided to SLR by Heliostar are believed to be reasonably representative of the Goldstrike project geology and gold mineralization.

The Goldstrike property includes a past-producing heap-leach gold mine that was operated by Tenneco Mineral Co., a subsidiary of Tenneco Inc. (Tenneco) and United States Mineral Company (USMX) from late 1988 to 1996. A total of approximately 209,000 ounces of gold and 198,000 ounces of silver were produced during these operations from approximately 8 million tons (7.26 million tonnes) of ore mined from 12 open pits. The average grade was approximately 1.2 g/t Au (0.035 oz/ton Au). A total of 19 million short tons (17.24 million tonnes) of waste was also mined.

Liberty Gold acquired the Project in August 2014. Heliostar acquired the property in March 2026 through its wholly owned subsidiary, Helio Five Resources Ltd. In an agreement dated March 20, 2026, it agreed to purchase Specialty American Metals Inc., a wholly owned British Columbia subsidiary of Liberty Gold, which is the sole owner of Pilot Goldstrike Inc., a Nevada company that holds the Goldstrike Project. Based on a letter from the Utah Division of Oil, Gas, and Mining (UDOGM), dated August 12, 2012, Heliostar believes that there are no outstanding reclamation liabilities.

The Goldstrike mineralization shares many of the characteristics of Carlin-type gold deposits. The mineralization is hosted primarily in conglomerate and limestone of the basal Claron Formation of Tertiary age, as well as with underlying Paleozoic units. The principal controls on mineralization include the generally shallow-dipping unconformity at the base of the Claron Formation, which is extensively mineralized, and high-angle structures of various orientations that appear to be the conduits through which mineralizing fluids circulated. These structural zones can also lead to significant mineralization in the Paleozoic silty limestone of the Pennsylvanian Callville Limestone and Mississippian Redwall Limestone, important hosts of mineralization.

The Project drill hole database includes 1,391 holes (87,175 m) drilled by historical operators and 984 holes for 130,218 m drilled by Liberty Gold in late 2015 through 2022. The data includes 39 core holes and 23 sonic holes, with the remainder being RC holes. Heliostar has not completed any drilling or exploration activities as of the effective date of this report.

SLR reviewed the Project database, and the QP is of the opinion that the data are acceptable as used in this report, although the locations of many of the historical drill holes are uncertain. During its time as operator, Liberty Gold completed work to validate drill hole locations by using historical data (e.g., drill logs and surface location maps and aerial imagery), as well as by surveying the relatively small percentage of historical drill collars that can still be identified in the field.

While a large number of historical holes have been drilled at the Goldstrike property, most are shallow (the average of the downhole drill lengths is 64 m) and were drilled within and immediately adjacent to areas that were subsequently mined. Historical holes drilled outside of the limits of the open pits suggest that the mined mineralization extends beyond pit limits and remains open along the seven-kilometre-long mine trend, and this has been confirmed by Liberty Gold's drilling program and Heliostar's resource estimate.

The Goldstrike oxide resources appear to be readily amenable to crush and/or ROM conventional heap leaching practice. Cyanide and lime consumptions are low to moderate. Deleterious elements such as copper, zinc, mercury, nickel, etc., are low and will have minimum impact upon cyanide consumption. Power required for crushing and abrasion wear characteristics are low to moderate and represent minimal risk. Oxide gold recoveries are considered to be good to excellent, depending upon resource location, cyanide solubility, and particle size.

1.1.2 Recommendations

In the SLR QP's opinion, this property has merit, warranting additional exploration expenditures. Finding additional mineralization of economic interest within the Goldstrike property is possible through drill testing of prioritized targets, both known and conceptual. Work to advance engineering, economic, and hydrological modelling and studies is also justified.

Heliostar has outlined an approximately US$7,550,400 2026 work program of 22,500 m of RC and core drilling in the resource area and Antimony Ridge. The program includes a district-wide field exploration program that includes geophysics, remote sensing, and surface work. The SLR QP supports this work program.

It is recommended that additional transition metallurgical samples be obtained for testing and that the 3D geology/mine block model be updated to cover the oxide, transition, and waste gold cyanide solubility ranges proposed by GL Simmons.

If silver is to be included in future Mineral Resource estimation, the SLR QP recommends that samples be analyzed using four-acid digestion instead of two-acid aqua regia, which is not a total digestion for silver. Remodelling of the silver domains should follow once the controls on the silver mineralization are better understood.

Engineering work, including site evaluation and economic modelling, is recommended, culminating in a revised Technical Report and update to the 2018 PEA, which is no longer current. An application for a Notice of Intent (NOI) to address drilling in the Antimony Ridge was submitted in June 2025 and approved. Additional work to find a viable water source suitable for a mining operation should be progressed.

Details of the costs of the recommended program are tabulated in Table 1-2.

Table 1-2: Estimated Cost for the Advanced Exploration Program Proposed for the Goldstrike Project

Category	US$	Comments
Drilling	4,923,000	Goldstrike Main & Antimony Ridge & water 15,000 m RC averaging ~$90/m, 7,500 m core averaging ~$400/m, assays @ $60/sample
Technical Report Update	750,000	PEA and mineral resource update
District Field Exploration	785,000	Mapping, prospecting, IP geophysics, soil and rock sampling, assays, remote sensing, field support and compilation
Metallurgy	150,000	Final work on remaining and proposed composites
Re-assaying	101,600	Re-assaying (gold assay verification and silver using four acid digestion)
Geotechnical Consulting	200,000	Work separate from the PEA including engineering, reporting, etc.
Hydrological Consulting	150,000	Work separate from the PEA including water exploration and water rights
Environmental	80,000	Monitoring and surveys
Property	529,051	Claim fees and lease holding costs
5% Contingency	359,353	
Total	**7,546,404**	

The QPs are unaware of any significant factors and risks that may affect access, title, or the right or ability to perform the exploration work recommended for the Goldstrike Project.

1.1.3 Risks

The previous operator, Liberty Gold, undertook considerable work to de-risk the Property pursuant to mining, including several phases of closely-spaced drilling, several phases of metallurgical testing, ongoing permitting, hydrological studies, and engagement with stakeholders.

The QPs note the following risks:

- Access to water sufficient to carry out mining activities has not been procured as of the Effective Date of this report.
- Further engineering and economic studies are needed to assess the feasibility of a mining operation at Goldstrike.

In the QPs' opinion, there are no other significant risks and uncertainties that could reasonably be expected to affect the reliability or confidence in the exploration information presented in this Technical Report or the data provided to SLR by Heliostar. The SLR QP considers the exploration information presented in this Technical Report to be reasonably representative of the Project geology and gold mineralization.

1.2 Technical Summary

1.2.1 Property Description

The Goldstrike Project is located in the Bull Valley Mountains in Washington County, approximately 50 kilometres (km) northwest of St. George, southwestern Utah, USA. It is accessible year-round via paved and all-weather roads. The approximate geographic centre of the Goldstrike Project is 37.386°N latitude and 113.88°W longitude.

The Property is made up of a central block of patented claims that are surrounded by a contiguous block of unpatented claims and land leased from the State of Utah, all within Washington County, Utah. The combined mineral property at Goldstrike controlled by Heliostar totals 5,514 ha (13,627 acres) as of the Effective Date of this report.

The climate in the Project area is semi-arid, with cool, dry winters and hot summers. Most precipitation falls during brief thunderstorms during the summer and as winter rain and snow.

Elevations within the Project area range from 1,200 m to 2,000 m. The topography is moderately steep throughout much of the area.

1.2.2 Land Tenure

Heliostar holds its interest in the Goldstrike Project through its wholly-owned subsidiary, Helio Five Resources Ltd., a British Columbia, Canada-based Corporation.

The Goldstrike property consists of a semi-contiguous block of 621 unpatented federal mining claims totalling 4,819 ha, a lease of Utah State Institutional Trust Lands Administration mineral rights consisting of two parcels and totalling 926 ha, 41 private mineral patents held in four separate lease agreements totalling 256 ha, and two parcels of leased fee land totalling 65 ha.. All are located in the State of Utah in Washington County and occupy a combined area of 5,514 ha (13,627 acres). Annual claim maintenance fees are the only federal payments related to unpatented mining claims, and these fees have been paid in full through September 1, 2026. County recording fees are also required annually, as well as a lease payment to the State of Utah. Lease payments also apply to the patents. Heliostar's annual claim holding costs, in total, are estimated to be US$529,051 in 2026.

Heliostar controls 100% of all unpatented federal claims and patented claim leases, having acquired the property through acquisition of Specialty American Metals Inc., a wholly owned British Columbia subsidiary of Liberty Gold, in an agreement dated March 2026.

1.2.3 Existing Infrastructure

Services are readily available in St. George, Utah. Skilled labour and experienced contractors, if not available in St. George, can be sourced from Las Vegas, Nevada or Salt Lake City, Utah. Grid electrical power extends to a point 8 km to the southeast of the Project. Year-round water for exploration drilling is available from a ranch located immediately southwest of the Project and is available from a sump on private property in the east fork of the Beaverdam Wash seasonal stream during the spring run-off period. The historical mining project was fully reclaimed and there is no infrastructure on site.

1.2.4 Mining History

Prospecting in the Goldstrike mining district commenced as early as the 1870s, with minor exploration activity and gold production between 1895 and 1920. Approximately 40 lode claims and one placer claim were brought to patent during this period. Coarse gold was recovered, and

a three-stamp mill operated briefly. The total recorded production from 1912 through 1942 was approximately 813 gold ounces, most of which was recovered from the Hamburg underground mine, located on the southwest high wall of the later Hamburg Pit, and from the Bull Run underground mine, located approximately 0.5 km west-northwest of the (present day) Goldtown Pit. Exploration in the district was largely dormant until the 1960s.

Modern exploration began in the late 1960s with the Padre Mining Company (Padre Mining) staking 53 claims on the east side of Heliostar's patented claim block. Exploration for "Carlin-style" sediment-hosted gold deposits began in earnest in the early 1970s. Reportedly, 14 companies explored the Property between 1975 and 2012.

Exploration in the 1970s and 1980s culminated in the development of the Goldstrike mine by Tenneco. From 1988 to 1996, Tenneco and USMX produced a total of approximately 209,000 ounces of gold and 198,000 ounces of silver from the heap-leach operation at Goldstrike. Approximately 8 million tons (7.26 million tonnes) of sediment-hosted disseminated gold ore from sandstone and conglomerate members of the Tertiary Claron Formation and from silty limestone members of the Pennsylvanian Callville Limestone and Mississippian Redwall Limestone was mined from 11 open pits. The average grade of the ore was 1.2 g/t Au (0.035 oz/ton Au). Some of the ore was crushed to minus 2 in. (51 mm) and the rest was processed as run-of-mine (ROM) material. The reported ore cut-off grade was approximately 0.617 g/t Au (0.018 oz/ton Au) over the life of mine. A total of 19 million short tons (17 million tonnes) of waste was also mined.

1.2.5 Geology and Mineralization

The Goldstrike Project occurs at the eastern edge of the Basin and Range Province, transitional to the Colorado Plateau. Devonian, Mississippian, Pennsylvanian, and Permian marine siliciclastic and carbonate sequences are unconformably overlain by Jurassic and Cretaceous sandstone and conglomerate and Cenozoic sedimentary and volcanic rocks. Rocks as young as Jurassic were strongly deformed during the Late Cretaceous Sevier orogeny, being folded and thrust-imbricated. Local Late Cretaceous to Paleocene basins developed with voluminous deposits of coarse clastic strata overlain by sandstone and conglomerate of Paleocene to Oligocene age, including the Claron Formation. Cenozoic ash-flow tuff, limestone, sandstone, conglomerate, and intermediate to felsic volcanic rocks overlie the older sedimentary rocks. Strongly altered mafic dikes of basalt or andesite composition locally intrude the sedimentary section.

The basal clastic member of the Eocene Claron Formation is the principal host rock for disseminated gold at Goldstrike, with gold mineralization also present in the underlying Paleozoic rocks, with the Pennsylvanian Callville Limestone and the middle member of the Pakoon Dolomite being the preferred hosts. Alteration and mineralization consist primarily of finely disseminated gold hosted in silicified or jasperoidized rocks. Silicification is accompanied by clay alteration, iron oxides, and decalcification of limy host rocks. Finely disseminated arsenical pyrite is noted in a few drill holes. Altered and mineralized zones are characterized by elevated arsenic, antimony, and mercury. Gold shows a strong spatial association with ENE- and NW-striking high angle faults. Overall, the alteration and geochemistry are typical of the sedimentary rock-hosted "Carlin-style" deposits of Nevada and western Utah.

1.2.6 Exploration

1.2.6.1 Drill Hole Database

The Goldstrike Project drill hole database comprises 2,375 holes for 217,393 m drilled on the Project by 11 previous operators, including Liberty Gold, from 1978 through 2022. Most of the historical holes drilled are vertical RC/rotary holes whereas the majority of Liberty Gold holes are angled holes. Most holes are RC or rotary (2,294 RC/rotary holes for 210,254 m), with limited core drilling (58 core holes for 6,338 m) and sonic drill testing of the historical heap-leach pad (23 sonic holes for 802 m).

1.2.6.2 Historical Exploration

Heliostar inherited substantial historical data from the previous operators, including a historical digital drill hole database. Original laboratory certificates are available for most of the drill hole samples, as are some surface geochemical and blasthole data for all the historical mine pits. Paper maps, cross-sections, drill logs, reports, and other miscellaneous information derived from the historical mining operation are also part of the historical data package. These data were digitized, verified, and assembled by Liberty Gold into a comprehensive digital database.

Included in the database are approximately 7,912 historical soil samples and 507 historical rock samples, with an additional 1,987 soil samples and 1,331 rock samples collected by Liberty Gold throughout the Property. Rock sample values range from below detection to a high of 26.3 g/t Au. Correlation matrices for all the rock samples show a strong Au-Ag-Sb-Te affinity and a lesser Au-Hg-Tl-Zn-Ni-As-Mo-Cu correlation. In combination with field observations, the sampling indicates that gold is associated with multi-phase jasperoid breccias with jarosite-limonite-hematite matrix.

1.2.6.3 Historical Drilling and Sampling, 1978 to 2012

The historical drill hole database includes 1,391 holes drilled by 10 previous operators during 1978 to 2012, totalling 87,175 m, including 1,372 RC/rotary holes for 85,202 m and 19 core holes for 1,974 m. Drill hole collar information has had several iterations of validation. The historical database contains 59,869 assay intervals, which average 1.57 m, with 97% of the sample intervals having a length of 1.524 m (5 ft).

There is limited information available for drilling and sampling methods and procedures employed by historical operators. There are no downhole survey data in the Project database for the historical holes. Almost 80% of the historical holes in the compiled database were drilled vertically, and only 44 of the 1,391 historical holes were drilled to depths exceeding 125 m.

It is difficult to assess the adequacy of historical sampling, sample preparation, and assaying due to a lack of sufficient quality assurance/quality control (QA/QC) data. However, some QA/QC analyses were completed by previous operators Inspiration Mines, Inc. (Inspiration), Tenneco, Midway Gold Corp. (Midway), and Cadillac Mining Corporation (Cadillac). Inspiration, Tenneco, and USMX drilled 93% of the holes in the Project database, and all were well-recognized and reputable mining companies at the time of their involvement at Goldstrike, which was prior to the implementation of NI 43-101 reporting requirements.

1.2.6.4 Liberty Gold Exploration, 2015 to 2024

Liberty Gold drilled a total of 984 holes for 130,218 m from 2015 through 2022 at the Goldstrike property, including 922 RC holes for 125,053 m, 39 core holes for 4,364 m, and 23 sonic holes for 802 m.

Liberty Gold's 2015 to 2022 QA/QC program meets current industry standards. No significant issues are indicated from the available QA/QC data for Liberty Gold drilling at Goldstrike.

In addition to drilling, Liberty Gold carried out extensive soil and rock sampling and geological mapping throughout the Property from 2015 through 2024.

1.2.7 Sampling, Sample Preparation, Analysis, and Security

While documentation is not complete, all of the historical operators were reputable, well-known mining/exploration companies, and the independent laboratories used to analyze the drill samples of the historical operators prior to the historical open-pit mining operation at the Goldstrike project were generally widely known and commonly used by the exploration and mining industry at the time.

The sample preparation, analysis, and security protocols of Liberty Gold, as well as their QA/QC program, are consistent with current industry standards, and no material issues were identified through analysis of their QA/QC results.

1.2.8 Data Verification

The historical drill hole data have undergone extensive verification. This verification included checking of the database values using historical records, and statistical analyses. The resource estimation was guided to a significant extent by Liberty Gold's lithological and structural (geological) models. SLR is of the opinion that Liberty Gold's geological model is of high quality and provided critical geological support that is required to support the estimation of the Project Mineral Resources.

The QP is of the opinion that, overall, the Goldstrike data are acceptable for use in Mineral Resource estimation.

1.2.9 Site Reclamation

Reclamation of the site was completed in 1999. In 2012, the State of Utah Department of Natural Resources Division of Oil, Gas and Mining stated in a letter to Cadillac: *"The site is stable, and the post mining land uses of grazing and wildlife habitat have been re-established. It is a showcase of exemplary reclamation in arid areas of Utah"* and recommended that the file be closed (UDOGM, 2012). Heliostar believes that there are no outstanding reclamation liabilities.

1.2.10 Metallurgical Testing and Mineral Processing

1.2.10.1 Historical Metallurgical Testing

Historical metallurgical sampling and testing (i.e., pre-Liberty Gold) extends back to the 1980s, though meaningful results are limited. However, it was reported that in 1993, USMX retained Kappes, Cassiday and Associates (KCA) to carry out cyanide-soluble assaying and column-leach testing on bulk sample material from the Beavertail (BEV) and Moosehead (MOS) deposits. Material for two columns was crushed to 100% passing 4 in. (10.2 cm). The columns utilized 708 kg of material from BEV and 805 kg of material from MOS. The material from BEV averaged 0.079 oz/ton Au (2.71 ppm Au) and that from MOS averaged 0.032 oz/ton Au (1.10 ppm Au). The column tests were carried out on a portion of each sample over a total of 61 days. Gold recovery was reported to be 78% for the MOS sample and 80% for the BEV sample.

1.2.10.2 Liberty Gold Testing

Liberty Gold initiated metallurgical testing in 2016. Four metallurgical test programs have been completed. These programs include:

- 2016 large-diameter PQ (85 mm) metallurgical core drilling program (Phase 1). Liberty Gold drilled 10 PQ diamond drill core holes in the Main Zone that includes the Basin, Hamburg, and Dipslope areas in the eastern portion of the historical mine trend of mineralization. Metallurgy composites underwent geo-metallurgical characterization, bottle roll, and column leach testing at KCA in Sparks, Nevada.
- 2018 large-diameter PQ met core program (Phase 2). Liberty Gold drilled 14 PQ diamond drill core holes in the Main, Cariboo, Moosehead, and Beavertail areas in the south and western portions of the historical mine trend. Metallurgical composites were tested at KCA.
- 2022 Sonic Drill and Bulk Sample program (Phase 3). Phase 3 was a two-part program:
  - Part 1 involved sonic drilling of existing Leach Pads 1 and 2, pad under-liner backfills, and two nearby historical mine waste dumps. Sonic drill samples were sent to KCA for sample preparation, geochemical assaying, and Master Composite selection. Composites were subjected to bottle roll and “as is” particle size column leach testing.
  - Part 2 was a series of 11 backhoe bulk samples excavated in and around historical pits and unmined mineralized surface exposures. Eleven bulk samples were selected from known resource areas with limited previous metallurgical core drilling and testing. Samples were crushed to 100% minus 100 mm (4 in.) to represent potential future crush/agglomeration flowsheet envisioned for Goldstrike. Composite samples underwent geo-metallurgical characterization, bottle roll, and column leach testing at KCA.
- 2022 large-diameter PQ metallurgical core drilling program (Phase 4). Liberty Gold drilled eight large diameter PQ diamond drill core holes in the Hamburg, Basin, and Padre areas in the northwest and west portions of the historical mine trend. The testing started on 22 Phase 4 variability composites. A few weeks into the program Liberty Gold requested that the scope of work (SOW) be modified to exclude the column leach testing, load permeability testing, tails screen analysis, and environmental characterization. KCA completed the geo-metallurgical characterization and bottle roll portion of the work. Composites are still at KCA and Liberty Gold plans to complete the remaining Phase 4 SOW in the future.

Metallurgical testing from the above test programs identified significant gold and silver mineralization in the following lithologic units as potential unique metallurgical recovery domains.

- Claron Formation (TC)
- Callville (PC)
- Pakoon Dolomite (PP) and Pakoon Sandstone (Pps)
- Scotty Wash (MSW) or Redwall stratigraphic units

Gold and silver recovery equations have been developed for each of the following metallurgical domains.

- PC – Callville Limestone
- PC – Callville Limestone (Beavertail)
- PP – Pakoon Dolomite
- TC – Claron Formation
- MSW– Scotty Wash

To facilitate gold and silver recovery modelling of the various lithologic units, gold and silver recovery equations are based upon the metallurgical domains and gold cyanide solubility (AuCN %) ranges.

- Oxide: Mineralized oxide material with gold cyanide solubility >75%.
- Transition: Mineralized transition material with gold cyanide solubility >50%, <65%. There is only one transition material type, which is not enough to develop separate gold and silver recovery equations.
- Waste: Mineralized sulphide/waste material with gold cyanide solubility <50%.

The QP notes that there is a current disconnect between the geology/mine three-dimensional (3D) model for cyanide solubility and the gold cyanide solubility ranges described for the above metallurgical domains. The current state of the Goldstrike 3D geology/mine model is described below:

- Geological Model: The Goldstrike geological model was used to assign recovery equations to the various formations.
- Units such as the clay-rich/sulphide Tcpyclay, Chainman Shale (MC), and all volcanic units (TC1) were assigned a 0.001% recovery due to the sulphidic or carbonaceous nature of these units.
- A model for cyanide solubility to fire assay ratio (AuCN) of <40% was built and these volumes were assigned 0.001% recovery.
- No 3D cyanide solubility model has been developed for the transition material, AuCN% <75, >40% resource. The current resource transition material is assigned oxide gold and silver recovery equations.

The QP is of the opinion that the samples tested are sufficiently representative to support the Goldstrike Mineral Resource update. Additional metallurgical sampling, testing, and geology/mine 3D block modelling is needed in future studies.

1.2.11 Mineral Resource Estimates

An updated Mineral Resource estimate for the Goldstrike Project was prepared by Liberty Gold with oversight and auditing by the SLR QP. Following the acquisition of the Property by Heliostar, it was adopted by the SLR QP with an effective date of March 23, 2026.

CIM (2014) definitions were used for Mineral Resource classification.

A total of 75 estimation domains representing gold mineralization were generated using Leapfrog Geo software and estimation was completed using a multi-pass inverse distance cubed (ID^3) interpolation approach. Classification was based on drill hole spacing, and wireframes representing the classification boundaries were generated using Leapfrog Geo

software. Estimation and classification were completed on a sub-block model, which was reblocked in Vulcan software for pit optimization using Whittle software.

Validation procedures included comparison of wireframe volume to block volume, statistical comparisons between composite grades, nearest neighbour (NN) estimates, and ID^3 estimates, validation using swath plots, and visual validation in three dimensions, longitudinal sections, cross-sections, and plan sections.

A summary of the Goldstrike Project Mineral Resource estimate is presented in Table 1-1.

The QP is not aware of any environmental, permitting, legal, title, taxation, socio-economic, marketing, political, or other relevant factors that could materially affect the Mineral Resource estimate.

2.0 Introduction

SLR Consulting (Canada) Ltd. (SLR) was retained by Heliostar Metals Ltd. (Heliostar) to prepare an independent Technical Report on the Goldstrike Project (Goldstrike or the Project), located in Washington County, Utah, USA. The purpose of this report is to disclose the results of an updated Mineral Resource estimate with an effective date of March 23, 2026 (the Effective Date), following the acquisition of the Project by Heliostar from Liberty Gold. A summary of mineral processing and metallurgical testing was provided for this Technical Report by GL Simmons Consulting, LLC (GL Simmons).

This report conforms to National Instrument 43-101 Standards of Disclosure for Mineral Projects (NI 43-101). The Mineral Resource estimate presented in this Technical Report supersedes all prior Mineral Resource estimates for the Project.

Heliostar is an emerging mid-tier gold producer with two operating mines in Mexico, La Colorada in Sonora and San Agustin in Durango. The company also has a strong portfolio of development projects in Mexico and the USA, including its flagship Ana Paula projects in Guerrero, the Cerro del Gallo project in Guanajuato, the San Antonio project in Baja Sur, and the Unga project in Alaska, USA. Heliostar is listed on the TSX Venture Exchange (TSX-V:HSTR) and holds its interest in the Project through its wholly owned subsidiary, Helio Five Resources Ltd.

Heliostar is the 100% owner of federal lode claims and patented claim leases hosting the Mineral Resource at the Goldstrike property, having acquired the Property through the purchase of Specialty American Metals Inc. in March 2026 (Heliostar, 2026). American Specialty Metals was a wholly owned British Columbia subsidiary of Liberty Gold Corp., which was the sole owner of Pilot Goldstrike Inc., a Nevada company that held the Property.

The Goldstrike Project is an advanced-stage gold exploration project, located approximately 56 km northwest of St. George in Washington County, southwestern Utah, USA. Gold is associated with multi-phase jasperoid breccias with strong jarosite-limonite-hematite matrix, having a strong spatial association with high-angle faults, and alteration and geochemistry being typical of the sediment-hosted “Carlin-style” deposits of Nevada and western Utah.

The Goldstrike Project was the site of open-pit mining and cyanide heap-leach processing from 1988 to 1986.

Recent surface exploration activities in the southeastern portion of the Property have outlined extensive zones of antimony mineralization, resulting in staking of additional claims and preparations for drilling in 2025.

2.1 Site Visits

Lorraine Tam, Consultant Resource Geologist with SLR, conducted a site visit at the Goldstrike Project on March 5, 2025, accompanied by Ms. April Barrios, Senior Resource Geologist for Liberty Gold. This site visit included geologic overviews of the Project, detailed inspections of exposures in the historical open pits, and verification of drill hole locations. The visit also included detailed discussions of the evolving geologic understanding of the Project and associated mineralization. Topics of discussion at the site also included:

- Property geology, gold mineralization, alteration, and controlling structures;
- Geologic Model in Leapfrog Geo;
- Logging and reverse circulation (RC) sampling procedures;

- Chain of custody procedure for RC sample handling and transport to ALS in Elko, Nevada;
- Database management and data entry;
- Quality assurance and quality control (QA/QC) data verification program for project sampling;
- Specific gravity determination;
- Methodology for historical drill hole data collection, storage, and compilation into the electronic drill hole database; and
- Drill hole collar locations.

Gary L. Simmons, Consultant Metallurgist with GL Simmons, accompanied by Peter Shabestari, of Liberty Gold, visited the Goldstrike Project on a number of occasions, with the most recent visit on May 16, 2022. The purpose of his visits was to examine ore and waste in the field and in core, as well as the layout of the historical mines and pits. During the site visits, Mr. Simmons toured the Project and reviewed relevant geology, the historical pits, and historical Noranda metallurgical sample locations and discussed plans for all metallurgical aspects of the Project with the on-site geologists

SLR and GL Simmons were given full access to relevant data and conducted interviews of Liberty Gold personnel to obtain information on the past exploration work, to understand procedures used to collect, record, store, and analyze historical and current exploration data.

2.2 Sources of Information

Lorraine Tam, P.Geo., SLR Consultant Resource Geologist, is responsible for the overall preparation of the Technical Report apart from Sections 1.2.10, 13, and metallurgy related portions of Sections 1.1, 25, and 26 that were prepared by Consulting Metallurgist Gary L. Simmons, MMSA, a QP with respect to metallurgy.

Ms. Tam is a QP under NI 43-101 and has no affiliation with Heliostar or Liberty Gold except that of independent consultant/client relationship. Ms. Tam was assisted by April Barrios, Senior Resource Geologist for Liberty Gold, in the preparation of wireframe models and resource estimations.

Section 13 was prepared by Mr. Simmons, a QP with respect to metallurgy. Mr. Simmons has no affiliation with Heliostar or Liberty Gold except that of independent consultant/client relationship.

This report is based on information collected by SLR during a site visit performed on March 5, 2025 and on additional information provided by Liberty Gold and GL Simmons throughout the course of SLR's investigations, including:

- Discussions with Liberty Gold and GL Simmons personnel.
- Inspection of the Goldstrike Project area, including historical open-pit faces, outcrop, and drill hole collar locations.
- Review of exploration data collected or compiled by Liberty Gold.
- Additional information from public domain sources.

SLR has no reason to doubt the reliability of the information provided by Liberty Gold.

All sections of this report, with the exception of Sections 13 and 14, rely on descriptions and summaries in previous NI 43-101 Technical Reports by Gustin and Smith (2016) and SRK (2018A, 2018B).

2.3 Acknowledgements

SLR would like to acknowledge the support and collaboration provided by Heliostar and Liberty Gold personnel for this assignment. Their collaboration was greatly appreciated and instrumental to the success of this project.

2.4 List of Abbreviations

Units of measurement used in this Technical Report conform to the metric system unless otherwise indicated. All currency in this report is United States dollars (US$) unless otherwise indicated.

μ	micron
μg	microgram
a	annum
A	ampere
bbl	barrels
Btu	British thermal units
°C	degree Celsius
C$	Canadian dollars
cal	calorie
cfm	cubic feet per minute
cm	centimetre
cm^2	square centimetre
d	day
dia	diameter
dmt	dry metric tonne
dwt	dead-weight ton
°F	degree Fahrenheit
ft	foot
ft^2	square foot
ft^3	cubic foot
ft/s	foot per second
g	gram
G	giga (billion)
Gal	Imperial gallon
g/L	gram per litre
Gpm	Imperial gallons per minute
g/t	gram per tonne
gr/ft^3	grain per cubic foot
gr/m^3	grain per cubic metre
ha	hectare
hp	horsepower
hr	hour
Hz	hertz
in.	inch
in^2	square inch
J	joule
k	kilo (thousand)
kcal	kilocalorie
kg	kilogram
kVA	kilovolt-amperes
kW	kilowatt
kWh	kilowatt-hour
L	litre
lb	pound
L/s	litres per second
m	metre
M	mega (million); molar
m^2	square metre
m^3	cubic metre
MASL	metres above sea level
m^3/h	cubic metres per hour
mi	mile
min	minute
μm	micrometre
mm	millimetre
mph	miles per hour
MVA	megavolt-amperes
MW	megawatt
MWh	megawatt-hour
oz	Troy ounce (31.1035g)
oz/ton, opt	ounce per short ton
ppb	part per billion
ppm	part per million
psia	pound per square inch absolute
psig	pound per square inch gauge
RL	relative elevation
s	second
st	short ton
stpa	short ton per year
stpd	short ton per day
t	metric tonne
tpa	metric tonne per year
tpd	metric tonne per day
US$	United States dollar
USg	United States gallon
USgpm	US gallon per minute
V	volt
W	watt

km	kilometre	wmt	wet metric tonne
km^2	square kilometre	wt%	weight percent
km/h	kilometre per hour	yd^3	cubic yard
kPa	kilopascal	yr	year

3.0 Reliance on Other Experts

This Technical Report has been prepared by SLR and GL Simmons for Heliostar. The information, conclusions, opinions, and estimates contained herein are based on:

- Information available to SLR at the time of preparation of this Technical Report.
- Assumptions, conditions, and qualifications as set forth in this Technical Report.

SLR has relied on Heliostar and Liberty Gold for guidance on applicable taxes, royalties, and other government levies or interests, applicable to revenue or income from the Goldstrike Project.

For the purpose of this Technical Report, SLR has relied on ownership information provided by Heliostar and Liberty Gold.

SLR has not performed an independent verification of land title and tenure information as summarized in Section 4 of this report. SLR is not an expert in legal matters, such as the assessment of the validity of mining claims, mineral rights, and property agreements in the United States. SLR did not verify the legality of any underlying agreement(s) that may exist concerning the permits or other agreement(s) between third parties and have relied on a legal advisor to the client as expressed in legal opinions provided to Liberty Gold in 2014, 2016, 2017, 2018, 2019, and 2022. A copy of the title opinions is provided in Appendix 1, Table 30-1 to Table 30-6. The reliance applies solely to the legal status of the rights disclosed in Sections 4.1 and 4.2 below.

Furthermore, SLR did not conduct any investigations of the environmental or political issues associated with the Goldstrike Project and is not an expert with respect to these matters. SLR has therefore relied upon information and opinions provided by Heliostar, Liberty Gold, and its consultants about the following:

- Section 4.1, which pertains to land tenure, was prepared by Mr. Heston of Liberty Gold incorporating reports by Richard Moorhead, a Utah Landman who reviewed the legal status of the original claim block purchased from Cadillac (Moorhead 2014). Liberty Gold also received a report on the mineral status of unpatented claims from Erwin and Thompson LLP of Reno, Nevada (Erwin 2014; Erwin 2016; Erwin 2017; Erwin 2018a; Erwin 2018b; Erwin 2019) and updated by Parsons, Behle, and Latimer of Salt Lake City, Utah (Parsons 2022).
- Section 4.2, which pertains to legal agreements and encumbrances, was prepared by Mr. Heston, responsible for maintaining the Property in good standing, and includes Utah State Tax, Utah State Bill 216: High Cost Infrastructure Tax Credit effective date May 12, 2015, 12 p.; and Utah tax code for Severance tax reference, Utah Tax Code, Title 59, Chapter 5, Part 2, section 202.
- Section 4.3, which pertains to environmental permits and licences, was prepared by Mr. Heston, responsible for permitting at Goldstrike.
- Section 4.4, which pertains to environmental liabilities, was summarized by Liberty Gold from documents prepared by Environmental Resources Management Inc.

SLR has relied on Heliostar to provide full information concerning the legal status of Heliostar and its affiliates, as well as current legal title, the material terms of all agreements, and material environmental and permitting information that pertains to the Goldstrike Project. SLR was

informed by Heliostar that there are no known litigations potentially affecting the Goldstrike Project.

Except for the purposes legislated under provincial securities laws, any use of this Technical Report by any third party is at that party's sole risk.

4.0 Property Description and Location

4.1 Property Location

The Goldstrike Project is located in the Bull Valley Mountains in Washington County, approximately 50 km northwest of St. George, southwestern Utah, USA (Figure 4-1). The approximate geographic centre of the Goldstrike Project is 37.386°N latitude and 113.88°W longitude.

Heliostar is the 100% owner of federal lode claims and patented claim leases hosting the Mineral Resource at the Goldstrike property, having acquired the Property through the purchase of Specialty American Metals Inc., a wholly owned British Columbia-based subsidiary of Liberty Gold Corp.

Liberty Gold, under its previous name Pilot Gold Inc. (Pilot Gold), acquired the original Goldstrike Project, including mineral leases on 41 patented claims and direct ownership of 208 unpatented lode claims by acquisition of Cadillac pursuant to a Court-approved plan of arrangement in August 2014.

4.2 Mineral Tenure

4.2.1 Land Area

The Property is made up of a central block of patented claims that are surrounded by a contiguous block of unpatented claims and land leased from the State of Utah, all within Washington County, Utah. The combined mineral property at Goldstrike controlled by Heliostar totals 13,627 acres (5,514 ha) as of the Effective Date of this report.

4.2.2 Unpatented Lode Claims

The Property includes a total of 621 wholly-owned, unpatented federal lode mining claims for a total of approximately 11,907 acres (4,819 ha) (Appendix 1 Table 30-1 and Table 30-3). The unpatented lode claims lie in portions or all of the following sections (all in Salt Lake Base Line and Meridian, Washington County, Utah):

- Township 39 South, Range 17 West, Sections 30-31
- Township 39 South, Range 18 West, Sections 9-10, 15-23, 25-31, 34-36
- Township 39 South, Range 19 West, Sections 22-28, 33-36

The unpatented lode claims were staked in 2004, 2010, 2011, 2014, 2015, 2016, 2017, 2022, 2024, and 2025.

A total of 99 unpatented claims were leased from Oro Vista LLC in Township 39 South, Range 19 West, Sections 13-14, 22-24, Salt Lake Base Line & Meridian, between 2015 and 2025, covering approximately 2,046 acres (828 ha). This lease was terminated on July 10, 2025.

The unpatented claims were located in the field with 5 cm x 5 cm wooden posts and metal tags that meet Utah regulations. Heliostar states that the list of unpatented claims in Section 30.0 Appendix 1 30.0 is complete, accurate, and valid as of the Effective Date of this report. The status of the 208 original claims was reviewed by Richard Moorhead, a Utah Landman, and found to be in good standing (Moorhead 2014). Mineral status reports were prepared by Erwin and Thompson LLP of Reno, Nevada (Erwin 2014; Erwin 2016; Erwin 2017; Erwin 2018a; Erwin

2018b; Erwin 2019) and updated by Parsons, Behle, and Latimer of Salt Lake City, Utah (Parsons 2022). They indicate the presence of third-party claims in the vicinity of the Property, but no conflicts were identified.

Figure 4-1: Location of the Goldstrike Project



Source: Liberty Gold 2026.

Figure 4-2: Land Tenure Map of the Goldstrike Property



Source: Liberty Gold 2025. Please refer to Figure 4-3.

Ownership of unpatented mining claims is in the name of the holder (locator), subject to the paramount title of the United States of America, under the administration of the U.S. Bureau of Land Management (BLM). Currently, annual claim maintenance fees are the only federal payments related to unpatented mining claims, and these fees have been paid in full through September 1, 2026. All claims have an expiration date of September 1, 2026 unless annual claim maintenance fees are paid on or before September 1, 2026. Heliostar's annual holding costs for the Goldstrike unpatented land and placer mining claims, exclusive of lease fees, are estimated at $529,051 in 2026 (Table 4-1), and Heliostar has indicated to the BLM their intention to renew.

Table 4-1: Annual Claim Maintenance Fees for the Goldstrike Property

Annual Fee Type	Estimated 2026 Amount (US$)
Unpatented BLM Fees	128,800
Unpatented County Filing Fees	1,308
Patented Claims Taxes	1,831
Patented Claims Lease Fees	386,000
State Mineral Lease Fees	11,112
Total Annual Taxes and Fees	**529,051**

4.2.3 Unpatented Placer Claims

Sixteen unpatented placer claims are located along the East Fork of Beaver Dam Wash and were recorded with Washington County and the BLM in 2017 (Figure 4-3 and Appendix 1 Table 30-3). The placer claims are owned by Heliostar and overlap existing Heliostar and Oro Vista lode claims. The claims lie in all or portions of:

- Sections 24 and 25, Township 39 South, Range 19 West
- Sections 17, 18, and 19, Township 39 South, Range 18 West, Salt Lake Baseline & Meridian.

Figure 4-3: Patented Claims, Placer Claims and Historical Workings Located in Beaverdam Wash



4.2.4 Patented Mining Claims

Cadillac acquired leases on 41 patented mining claims (634.76 ac/256.2 ha) as four separate parcels in 2011. The claims cover approximately 40% of the historically mined area, including the Goldtown and Covington open pits and portions of the Basin and Hamburg pits (Figure 4-3). A list of the patented claims is presented in Appendix 1 Table 30-4. Patent ownership documents were reviewed in May 2014 by Richard Moorhead, Utah Landman, and found to be accurate (Moorhead 2014). Patents were further examined in a mineral status report prepared in June 2014 and updated in 2016, 2017, 2018, and 2019 by Erwin and Thompson LLP of Reno, Nevada, and in 2022 by Parsons, Behle, and Latimer, with no conflicts identified (Erwin 2014; Erwin 2016; Erwin 2017; Erwin 2018a, Erwin 2018b, Erwin 2019, Parsons 2022). The lease payments are current through the dates listed in Appendix 1 Table 30-2.

In July 2017, Liberty Gold leased an additional parcel of private land, Bracken Trust, consisting of two homestead patents, to the northeast of the 41 mining patents for an additional 159.77 acres (64.65 ha) (Figure 4-2 and Appendix 1 Table 30-5).

In February 2026, Liberty Gold and Bull Valley III LLC amended the Mining Lease to extend the term until 2041. The Annual Royalty Payments and Production Royalty increased (Table 4-1 and Section 4.3.3).

4.2.5 Utah State Mineral Lease

Two parcels of land are leased from the State of Utah under the School and Institutional Trust Lands Administration (SITLA) subject to an annual fee as summarized in Table 4-1 and a royalty as summarized in subsection 4.3.3. As shown in Figure 4-2 and Appendix 1 Table 30-6, these two parcels have the Utah State Mineral Lease number 52928. The Utah State Mineral Lease has been paid through November 1, 2026.

4.3 Underlying Agreements and Encumbrances

4.3.1 General Statement

Unless otherwise noted below, there are no back-in rights, payments, or other agreements or encumbrances to which the Property is subject.

4.3.2 Utah State Tax

Mineral production from Goldstrike would be subject to the Utah Mining Severance tax of 2.60%, subject to certain exemptions.

The Goldstrike Project may be eligible for a State of Utah High Cost Infrastructure Tax Credit, under which up to 30% of state revenues per year can be written off for up to 20 years, or until 50% of certain infrastructure investments are recovered.

4.3.3 Patented Claims and Utah State Lands Royalties

The original patented claims owned by Fraser Trust, Bauer Trust, and Marvil Investments LLC are subject to a 2.5% Net Smelter Return (NSR) royalty, payable to the individual claim owners. The Bracken Trust properties are subject to a 1% NSR. Land leased from the State of Utah is subject to a 4.0% gross value production royalty. The Bull Valley III LLC patents are subject to a 4.0% NSR royalty, payable to Bull Valley III LLC.

4.3.4 Unpatented Claims

The 76 GAP unpatented claims owned by Heliostar are subject to a 2.0% NSR royalty payable to Vista Gold U.S. Inc. While Liberty Gold was the operator, they abandoned 40 GAP claims in September 2025, with notice to the royalty payee.

4.4 Permits and Authorization

Exploration work on patented and unpatented claims is permitted by BLM under a Plan of Operations (POO). Permitting and bonding through the Utah Division of Oil, Gas, and Mining (UDOGM) for disturbance is also required.

Prior to the approval of the POO in August 2017, Pilot Goldstrike held UDOGM permit# E/053/0065 and Notice of Intent (NOI) UTU-091149 from the BLM. By September 22, 2016, after four amendments, total authorized and bonded disturbance was 9.76 acres (3.9 ha), of which 4.02 acres (1.6 ha) were on private land and 5.74 acres (2.3 ha) were on public land. A second NOI permit, UDOGM permit #E/053/0070 and BLM UTU-092291, authorizing up to 1.8 acres (0.7 ha) of disturbance, applied to the area around Mineral Mountain in the northwestern corner of the Property.

The POO (UDGOM Permit # E/053/0069 and BLM # UTUT105857100) was approved by the BLM and bonded by UDOGM in August 2017. Minor modifications were approved in February 2018, November 2018, and December 2024. Approximately 77 acres (31.2 ha) of disturbance, covering most of the known surface mineralization on the Property, are permitted. The files for the two NOIs were closed, with both projects wrapped into the current POO.

A new NOI for drilling at Antimony Ridge (UDOGM Permit # E/053/0312 and BLM # UTUT106719741) was approved in June 2025.

A reclamation bond in the amount of $489,235 for the POO and a bond in the amount of $44,400 for the Antimony Ridge NOI are in place with UDOGM.

4.5 Environmental Considerations

There is evidence of extensive previous mineral exploration and mining activities at the Property. Tenneco developed and operated the Goldstrike mine from 1988 to 1992, eventually selling it to United States Mineral Company (USMX). The mine produced oxidized, disseminated gold ore for heap-leach recovery from eight open pits. From east to west, these pits include the Padre, Main, Hassayampa, Goldtown, Basin, Hamburg, Moosehead, and Covington pits (see Figure 7-5). A crushing plant, two heap-leach pads, and recovery facility were located near the Main Pit. A haul road connected the operations. The site was fully reclaimed by late 1996, including removal of all facilities, partial backfilling of pits, recontouring and revegetating of all heap-leach pads, waste dumps, and roads (with the exception of the haul road and exploration drill roads located on private land).

During Liberty Gold’s time as the operator of the Project, they routinely reclaimed drill sites and access roads that were no longer required for drilling. Liberty Gold estimated that it has reclaimed approximately 69.8 acres (28.2 ha) on both public and private land as of the Effective Date of this report. Approximately 45.2 acres (18.3 ha) of fully reclaimed areas were released from the bond in 2022 and 2025. Approximately 24.6 acres (10.0 ha) are in “Phase 1” reclamation, waiting on successful vegetation growth. Approximately 25.7 acres (10.4 ha) are currently open and in use. An example of the reclaimed Goldstrike Mine area is shown in Figure 4-4.

In a letter dated August 12, 2012, personnel of the State of Utah Department of Natural Resources Division of Oil, Gas and Mining stated that reclamation of the site was completed in 1999 and recommended that the file be closed. They further stated: “Vegetation has established that exceeds the ground cover of the surrounding area. The site is stable, and the post mining land uses of grazing and wildlife habitat have been re-established. It is a showcase of exemplary reclamation in arid areas of Utah” (UDOGM, 2012). On this basis, Heliostar believes that the surface disturbance and reclamation liability that are related to the above-described operations are not transferable; thus, there are no outstanding reclamation liabilities that could or would be tied to successor companies as a result of holding the mining claims associated with the Property.

Meetings between Liberty Gold and the St. George, Utah office of the BLM have indicated no immediate concerns regarding historic or prehistoric cultural sites. No wildlife concerns have been identified.

A Phase I Environmental Site Assessment (ESA) report was prepared for Cadillac by Environmental Resources Management Inc. (ERM) (Environmental Resources Management Inc. 2014). ERM identified the following issues.

ERM advised Cadillac that at the time of their site visit (May 2013), water was observed seeping from the heap-leach pad drainage underground collection point north of the Hamburg Pit. Heap-leach pad effluent data from 2008 indicated that the effluent contained constituents in excess of groundwater quality standards. Current effluent water quality is not known. In May 2014, Liberty Gold geologists visited the site and did not see any water seepage.

Historically, cyanide was used and cyanide solutions were released on the Property. All spills were cleaned up under State approved programs.

Figure 4-4: Aerial View Showing the Reclaimed Goldstrike Mine Area, and Typical Landscape of the Project Area, Looking East



Source: Liberty Gold 2017.

4.6 Mining Rights of the Goldstrike Project

Mining rights are granted by the federal government. In the case of leases and patents, these rights, originating with the federal government, are assigned by the private owners and the State of Utah in the case of the state mineral leases.

All of the unpatented lode and placer mining claims are located on lands administered by the BLM, St. George Field Office.

Under the Mining Law of 1872, which governs the location of unpatented mining claims on Federal lands, the locator has the right to explore, develop, and mine minerals on unpatented mining claims without payments of production royalties to the U.S. government, subject to the surface management regulation of the BLM. In recent years, there have been efforts in the U.S. Congress to change the 1872 Mining Law to include, among other items, a provision of production royalties to the U.S. government.

For the patented claims, the leases grant Heliostar the right to *"… erect, construct, maintain, and operate, on and in the Property, buildings, structures, facilities, machinery, and equipment, and to use, occupy, excavate, and disturb so much of the surface and subsurface of the Property as Heliostar may determine to be useful, desirable, or convenient..."*

The Utah State Mineral Lease grants Heliostar the following "*Lessee may use such lands to the extent reasonably incident to the exploration and production of the Leased Substances by Lessee on the Property or production of Offsite Substances by Lessee or its Affiliates on nearby or adjacent lands that are developed in connection with production of the Leased Substances*

and operations on the Property, including but not limited to: (i) roads, pipelines, and production wells; (ii) conveying, storing, loading, hauling and otherwise transporting Leased Substances; (iii) excavating, removing, stockpiling, depositing and redepositing of surface materials; (iv) developing and utilizing mine portals and adjacent areas for access, staging and other purposes incident to mining; and (v) the subsidence, mitigation, restoration and reclamation of the surface."

4.7 Environmental Liabilities, Permitting, and Other Significant Factors or Risks

Other than that which is discussed above, Heliostar has not identified any other significant factors or risks that may affect access to title or the right or ability to perform work on the Property.

Heliostar has identified and initiated discussions with potential stakeholders at the community, city, county, State, and Federal levels. These introductory meetings have focused on meeting key personnel, their roles and engagement level, and entry level permitting strategies. Heliostar is not aware of any potential social or community related requirements that may materially affect the Goldstrike Project at this time.

The QP is not aware of any environmental liabilities on the Property. Heliostar has all required permits to conduct the proposed work on the Property. The QP is not aware of any other significant factors and risks that may affect access, title, or the right or ability to perform the proposed work program on the Property.

5.0 Accessibility, Climate, Local Resources, Infrastructure and Physiography

5.1 Accessibility

The Goldstrike Project is located approximately 50 km northwest of the city of St. George, Utah (Figure 4-1) and 13 km east of the Nevada state line. St. George is located on Interstate Highway 15, which connects Las Vegas to Salt Lake City. Year-round access to the Property is via paved Utah State Highway 8, which turns into Old US Highway 91 north of Ivins, and then on the Motoqua Road, an improved, all-weather gravel road, to the Goldstrike Road. An alternate route is via the Gunlock Road from Old US Highway 91. Mine haul roads provide excellent access to all the historically mined pits, with unimproved gravel roads providing access to most other areas of the Property.

5.2 Local Resources and Infrastructure

At present, there is no electrical power to the Property, although a regional power transmission line extends to a natural gas pipeline located 12 km to the southeast of the Property. The nearest major electrical transmission line is eight kilometres southeast of the Property. At least one perennial stream crosses the property. A large house and barn are located on a private ranch seven kilometres southwest of the Property and could be utilized for crew quarters and drill hole logging and storage needs.

Water for drilling is available from sources on the same ranch. During the spring, when water flows in Bull Valley Wash are high, water can be obtained from an impoundment in the wash on leased private property.

5.3 Climate

The climate is semi-arid. Daytime temperatures may drop below freezing briefly in the winter and may exceed 45°C in the summer. Annual precipitation in St. George is approximately 20 cm, with more precipitation received at Goldstrike due to its higher elevation and mountainous terrain. Most precipitation falls as winter rain and occasional snow and late summer thunderstorms. The climate and road access are such that, with the exception of significant snow or rain events, year-round access for drilling and other exploration activities is possible. Historical mining and processing occurred throughout the year.

5.4 Physiography and Vegetation

The Goldstrike Project lies on the eastern margin of the Basin and Range physiographic province of Nevada and western Utah. The Project site is characterized by moderate to steep terrain in the southern portion of the Bull Valley Mountains. Elevations range from approximately 1,200 m to 2,000 m. Sagebrush and other shrubs are the main vegetation in the lower elevation areas; pinion pine and juniper predominate at higher elevations. Stream courses contain cottonwood trees and other streamside vegetation. Overall, the Project area is considered to be within the “desert woodland and sagebrush grassland” vegetation zones of western Utah (Shultz and Shultz 1987).

6.0 History

6.1 Early Historical Prospecting and Mining

Prospecting in the Goldstrike mining district commenced as early as the 1870s, with minor exploration activity and gold production between 1895 and 1920. Approximately 40 lode claims and one placer claim were brought to patent during this period (Willden 2006). Coarse gold was recovered, and a three-stamp mill operated briefly. The total recorded production from 1912 through 1942 was approximately 813 ounces, most of which was recovered from the Hamburg underground mine, located on the southwest high wall of the later Hamburg Pit, and from the Bull Run underground mine, located approximately 0.5 km west-northwest of the (present day) Goldtown Pit (Figure 6-1). Exploration in the district was largely dormant until the 1960s.

6.2 Modern Historical Exploration Campaigns

Modern exploration began in the late 1960s with the Padre Mining Company (Padre Mining), which staked 53 claims on the east side of Heliostar's patented claim block. Exploration for "Carlin-style" sediment-hosted gold deposits began in earnest in the early 1970s. Reportedly, 14 companies explored the Property between 1975 and 2012, summarized below. Historical exploration and drilling areas are shown in Figure 6-2 and the historical drilling totals reported are summarized in Section 10.1.

Figure 6-1: Map of Goldstrike Production Areas Mined 1988 to 1996



Figure 6-2: Map of Historical Exploration and Drilling Areas, Goldstrike Project



- 1975 to 1976: Gold Resources Inc. (GRI) carried out reconnaissance mapping, soil and rock sampling, and identified gold mineralization over a 32 km^2 area, including most of the areas that were later mined, and the Padre Mining ground. Elevated gold concentrations were found in fault-controlled jasperoids and at the base of the Claron Formation.
- 1977: Lustre Gold Mines Inc. optioned the Gunlock-Bonanza patented claims and opened and sampled the historical Hamburg underground mine.
- 1978 to 1979: Occidental Minerals leased the ground previously explored by GRI and test drilled surface geochemical anomalies that were identified by GRI in the vicinity of what became the Main, Hassayampa, Hamburg, and Goldtown pits.
- 1979 to 1982: Houston International Minerals Company (Houston International) continued the drilling started by Occidental Minerals on the Padre Mining leases and conducted additional mapping and sampling programs. The drilling focused on areas around the same geochemical anomalies previously identified by Occidental Minerals, including the Hassayampa, Hamburg, Main, and Goldtown Pit areas, as well as the Arsenic Nose and Peg Leg target areas.
- 1982 to 1987: Permian Exploration Account (Permian) leased the Padre Mining properties from Houston International and conducted geological mapping, geochemical surveys, and drilling at the Hassayampa, Goldtown, Main, and Hamburg Pit areas, as well as the Big Red target.
- 1984: Bonanza Exploration collected surface rock samples from the Mineral Mountain and Potters Peak areas
- 1985 to 1987: Inspiration Mines, Inc. (Inspiration) subleased the Property from Permian and carried out exploration and development drilling over four main target areas in and around the existing Hamburg, Main, Hassayampa, and Goldtown mineralized areas, and discovered gold mineralization at the Basin and Padre targets. Some outlying targets were also drill tested. Inspiration sold their interests at Goldstrike to Tenneco in 1987.
- 1988 to 1989: Goldsil Resources (Goldsil) carried out exploration drilling in the Moosehead and Caribou areas.
- 1987 to 1992: Tenneco carried out aggressive exploration and development drilling in 10 target areas. Over the first few years, drilling focused mainly on the Main, Hassayampa, Goldtown, Hamburg, Basin, and Padre target areas. Expansion drilling then shifted westward with the discovery of mineralization in the Moosehead target area in late 1988, Caribou in 1989, Covington in 1990, and Beavertail in 1992, all of which were subject to definition drilling. Other significant targets that were drill tested by Tenneco include Peg Leg, Bogart, Arsenic Nose, Arsenic Gulch, Antimony Shafts, Bull Run, Picaroon, Big Red, Black Canyon, Butcher Knife, Mineral West – Fawcett, Potters Peak, Jedediah, and Cane Spring. In early 1992, Tenneco sold the Project to USMX.
- 1989 to 1990: Pegasus Gold Corp. (Pegasus) carried out exploration drilling in the Mineral West – Fawcett area, of which Liberty Gold has no assays for three holes.
- 1992 to 1993: USMX carried out very limited exploration drilling in the Goldstrike property and focused on definition drilling.
- 1996 to 1997: North Mining, Inc. (North Mining) leased patented claims from Bull Valley LLC, and drilled in the floors of the Hamburg, Padre, and Main pits, testing for what was

then considered deep, structurally controlled mineralization, and were largely unsuccessful.

- 1999: Bull Valley LLC (Bull Valley) drilled holes testing for deep mineralization within or adjacent to the Basin and Hamburg pits, as well as at the Deep Bogart target, with negative results. The area of the Property that includes the patented ground and open pits then remained idle until 2011.
- 2004: Midway Gold Corp. (Midway) drilled exploration holes in in the Mineral West – Fawcett area.
- 2009 to 2010: Tonogold Resources, Inc. (Tonogold) explored the Mineral West – Fawcett area, which at the time was known as the Mineral Mountain Project. Tonogold collected surface rock samples but did not conduct any drilling. Tonogold commissioned a NI 43-101 Technical Report on the Mineral West – Fawcett area in 2010, which was prepared by Puchski GeoConsultants and included a mineral resource estimate using Pegasus and Tenneco drill data. Heliostar is not treating that estimate as a current Mineral Resource; rather Heliostar is treating it as a historical resource and therefore the estimate should not be relied upon (refer to Section 6.4 for further details).
- 2014: Genesis Gold collected surface rock samples from the Antimony Ridge area.
- 2011 to 2014: Cadillac acquired the patented claims through lease agreements and staked claims in 2011. They assembled a large Project dataset, including historical drill logs, maps, assay certificates, and RC drill chips. In 2011 to 2012, Cadillac exploration drilling was focused primarily on one target to confirm mineralization originally recognized by Tenneco, drilled on north-south oriented sections primarily on the septa between Tenneco's Hamburg and Basin open pits and the area immediately to the west, to confirm mineralization originally recognized by Tenneco. Nine of the 12 holes drilled returned intercepts exceeding 1 g/t Au over downhole intervals of 10 m or more.

6.3 Surface Exploration

6.3.1 Airborne Geophysical Surveys

6.3.1.1 Newmont Mining Magnetic and Radiometric Survey

An airborne magnetic and radiometric survey was flown over the region by Newmont Mining Corporation (Newmont) from March 22 to 25, 2002. Lines were oriented northeast-southwest, with 100 m line spacing and 25 m station spacing. Data were purchased from Newmont, evaluated by Wright (2017), and are summarized below.

The magnetic system was a towed bird system with radiometric crystal pack installed in the rear compartment of a Bell Jet Ranger 206 helicopter operated by El Aero of Elko, Nevada. Mean elevation over terrain is 52 m. Total magnetic intensity data were gridded with a kriging algorithm. Gridded data were reduced to the pole (RTP) with a U.S. Geological Survey (USGS) algorithm. The data were further processed to produce total horizontal gradient and first vertical derivative maps. These grids were masked to remove strong magnetic variations along the north side of the survey area.

Airborne radiometric data were processed by Newmont to equivalent concentrations and gridded with a kriging algorithm. Grids were produced for equivalent K, U and Th, as well as total counts.

Gridded magnetic data (Figure 6-3) clearly differentiated several stratigraphic units on the Property. Paleozoic strata in the southern half of the Property showed a low relief, relatively low magnetic response. The Claron Formation, as well as interbedded tuffs and limestones, including the Needles Range, Isom, and particularly the overlying Leach Canyon tuffs, showed a slightly lower response. Conversely, the Miocene volcanic rocks, including the Swett-Bauer and Harmony Hills volcanic sequences, are strongly magnetic, suggesting that airborne magnetics can be a useful tool for outlining Oligocene and Miocene volcanic rocks.

Gridded radiometric data showed a low response for Paleozoic strata and a generally high response for volcanic rocks, with the Claron Formation and associated limestones and Needles Range and Isom tuffs, having an intermediate response in the total count radiometric image in Figure 6-4.

6.3.1.2 Fox Geophysics Gradient Array Resistivity Survey

Fox Geophysics carried out resistivity surveys over portions of the Property in 1989, 1990, and 1992. That data was re-acquired by scanning and digitizing the historical hardcopy maps. Line spacing was 120 m or 60 m depending on location, with a 30 m reading interval. Lines were oriented north-south except for the easternmost block, for which lines were oriented east-west in the southern part of the block and northeast-southwest in the northern part of the block. No additional information is available with respect to methodology, and no chargeability data was recorded during the survey. This data was also evaluated by Wright (2017).

The merged gradient array resistivity dataset is shown in Figure 6-5. In the figure, high resistivities are depicted with cool colours (i.e., purples and blues) and low resistivity with warmer colours (i.e., greens to pinks). Observed values, as with the other surveys, are consistent with the mapped rock types. Paleozoic rocks are high resistivity while the overlying Tertiary volcanic units are generally lower. In theory, alteration such as silicification would increase resistivity while clay alteration would lower resistivity, although this degree of detail is not immediately evident.

Figure 6-3: Reduced to Pole Magnetic Map of the Goldstrike Property



Notes:

1. Paleozoic strata and Claron formation are generally blue (low).
2. Leach Canyon tuff is purple (very low), and Miocene volcanic rocks reflect shades of cyan to pink (high).
3. Faults, drill collars and mineralization zones shown for reference.

Figure 6-4: Total Count Radiometrics Map of the Goldstrike Property



Source: Liberty Gold 2025.

Note: Paleozoic strata in blue (low TC), volcanic strata from the Leach Canyon tuff to younger volcanic rocks in pink, orange, etc. (high TC) and Claron Formation and related strata in intermediate colours.

Figure 6-5: Gradient Array Apparent Resistivity Map of the Goldstrike Property



Source: Liberty Gold 2025.

Note: mineralized zones shown for reference.

6.3.2 Geologic Mapping

Various campaigns of geologic mapping have been performed at several different scales and focused on different portions of the Project area. Adair (1986) described his mapping efforts over much of the area for Permian. Of note is detailed geological mapping by Inspiration, from 1985 to 1987, covering the area from what is now the Padre Pit east to the Arsenic Gulch area, encompassing the Padre, Main, Hassayampa, Hamburg, Basin and Goldtown pits. This (pre-mine) mapping proved extremely useful in understanding the detailed structural geology in the mine area. From 1987 to 1992, Tenneco carried out extensive detailed mapping over many of the outlying targets not mapped by Inspiration. The northwestern portion of the Property was compiled into the Docs Pass Quadrangle Map by Rowley et al. (2007). Liberty Gold compiled the more reliable mapping efforts noted above into a single digital map, with extensive spot checking and remapping of key areas. All geologic maps in this report reference this compilation map, or maps simplified from this map, described and illustrated in Section 7.

6.3.3 Soil Sampling

Heliostar's digital database includes data derived from 7,912 historical soil samples that cover most of the pit areas and the fault corridors within which the pits are situated. Most of this area was sampled along north-south soil lines spaced 400 ft (120 m) apart, with samples along the lines spaced at 100 ft (30 m) intervals. Near some of the pits, the sample-line spacing is reduced to 200 ft (60 m) or 100 ft (30 m). Few details are known about the accuracy of the sample locations, sampling methods, operators, laboratories, or analytical techniques. Some samples were analyzed for gold only; others were analyzed for up to seven additional elements, including Ag, Hg, As, Sb, Ba, Cu, and Zn.

It is clear that soil geochemistry played a critical part in determining historical exploration targets, as there is an excellent correlation between elevated gold-in-soils, mineralization in underlying bedrock, and the locations of historical deposits and pits.

All soil samples collected to date are illustrated in Section 7.

6.3.4 Drainage-Sediment Geochemistry

Stream-sediment surveys were carried out by some operators, but Heliostar has not yet digitized the data to incorporate it into the exploration model.

6.3.5 Rock-Chip Geochemistry

A large number of surface rock samples were taken during the course of exploration of the Property. A total of 507 Tenneco, Genesis Exploration, Bonanza Exploration, and Tonogold historical rock sample locations were digitized by Liberty Gold.

All rock chip samples are illustrated in Section 7.

6.3.6 Landsat Thematic Mapper Study

Greenan (1985) carried out a Landsat Thematic Mapper study of the Goldstrike district. Vegetative cover hampered the effort to differentiate different lithological units beyond "carbonate", "sandstone", and "volcanic rock". Landsat data were effective at identifying clay, silica, and iron-oxide alteration, although most areas of alteration had been previously mapped.

6.3.7 Field Spectrometer and XRD Study

Greenan (1985) also carried out a study using a SIRIS (single-beam visible/infrared intelligent spectro-radiometer) portable field spectrometer on 96 rock-chip samples from the Padre Pit. The study detected illite, montmorillonite, kaolinite, and dickite, as well as jarosite and goethite. X-ray diffraction (XRD) was used to further differentiate between the clays. This technique identified interlayered 2M1 illite and montmorillonite in many of the samples. This information was used, in turn, to infer that the temperature of formation of the clays was between 200°C and 250°C.

6.3.8 Petrographic Study

Effner (1992) carried out a petrographic study of 177 samples from the West Hamburg and Padre pits. This effort yielded a paragenetic interpretation of the sequence of mineralization (Section 7) that is still in use at present.

6.4 Historical Estimates

All but one of the estimates described in this section were prepared prior to 2000 and are presented here as items of historical interest with respect to exploration targets at Goldstrike. All the estimates were originally reported in imperial units. The classification terminology is presented as described in the original references, but it is not known if they conform to the meanings ascribed to the Measured, Indicated, and Inferred Mineral Resource classifications or Proven and Probable Mineral Reserve classifications by the Canadian Institute of Mining, Metallurgy and Petroleum (CIM 2014). Neither Heliostar nor SLR have completed sufficient work to classify these historical estimates as current Mineral Resources or Mineral Reserves, and Heliostar is not treating these historical estimates as current Mineral Resources or Mineral Reserves.

The first reported historical “ore reserve” known to Heliostar was calculated by Permian and consisted of 1.17 million tons at an average grade of 0.064 oz/ton Au (Willden and Adair 1986). This estimate was made on the basis of 17 drill holes in five separate areas. No further information is known about this historical estimate.

In 1981, Houston International estimated a total of 1 million tons of 0.06 oz/ton Au “from several areas” according to Callaway and Gates (1981).

Tenneco estimated historical “ore reserves” and historical “resources” for the Hassayampa zone calculated “manually” from 27 drill holes (Hebert 1988). This exercise returned an estimated resource of 565,490 tons at an average grade of 0.028 oz/ton Au for 15,834 ounces of gold. A pit-constrained “reserve” of 10,256 ounces of gold was derived from the resource.

An estimated historical “reserve” for the Beavertail Pit area was reported in Parsley (1994); this estimate included 285,604 tons at an average grade of 0.03 oz/ton Au for a total of 7,857 ounces.

None of the above historical estimates are relevant to the current status of the Goldstrike Project, as all or portions of the materials estimated were subsequently mined.

In 2010, Puchski GeoConsultants of St. George, Utah, prepared an estimate of mineral resources in the Mineral West – Fawcett area at the request of Tonogold that was summarized in a NI 43-101 technical report (Puchlik 2010). The estimate was based on drilling by Pegasus in 1989 to 1990, Tenneco in 1990, and Midway in 2004. A total of nine separate mineralized zones were included, which were estimated by polygonal methods to contain, in aggregate, Inferred Resources of 41,144 ounces of gold in 3.4 million tons at an average grade of

0.42 g/t Au (0.0122 oz/ton Au) (Puchlik 2010). This historical mineral resource estimate has been superseded by the estimate in this report. It should not be relied upon and is included for the purpose of providing a complete picture of the historical work on the Project.

6.5 Past Production

There is no record of production from the Goldstrike area until 1912, although some gold and silver was undoubtedly mined. Production attributed to the Goldstrike area by Willden (2006) is provided below in Table 6-1. High-grade gold and silver was mined from underground workings at the Hamburg, Bonanza, and Bull Run mines.

Modern production began after Tenneco completed metallurgical and engineering studies and commenced open-pit heap-leach mining and processing from the Hassayampa Pit in late 1988 (Willden 2006). The mine consisted of an office complex, two heap-leach pads, a crushing plant, and a solution-processing plant. The mining, crushing, and hauling of ore was done by mining contractors. The original heap-leach pad located in the Hassayampa Pit was subsequently levelled and overlain by an expanded heap-leach pad to accept ore from the Main Pit. The Main Pit, in turn, was backfilled with waste from the Hamburg and Padre Hill ore bodies, and a new heap-leach pad was constructed over the backfilled Main Pit. Over time, both the crushing plant and office complex had to be moved to expand the heap-leach facilities and allow mining of one of the two Goldtown ore bodies (Willden 2006). Mining proceeded westward, ending with the Moosehead and Beavertail pits (MEG 2012).

Table 6-1: Summary 1912 to 1942 Gold–Silver Production of the Goldstrike District

Year	Source	Tons	Gold (oz)	Silver (oz)
1912	Heikes, 1913	18	9.39	4
1914	Heikes, 1916	35	23.22	9
1915	Heikes, 1917	173	593.00	222
1916	Heikes, 1919	15	10.49	4
1918	Heikes, 1921	15	9.87	4
1919	Heikes, 1922	1	0.97	2
1928	Gerry and Miller,[1]	6	19.01	6
1929	Gerry, 1932		39.43	15 [2]
1931	Gerry and Luff, 1934	1	1.3	0
1933	Gerry and Miller,[1]	3	11.27	11
1934	Gerry and Miller, 1935	3	41.80	20
1935	Gerry and Miller, 1937	5	1.80	
1936	Gerry and Miller. 1937	20	13.60	9
1937	Miller, 1938	4 [3]	4.00 [2]	4 [3]
1939	Miller and Luff, 1940	1	18.00	3
1949[4,5]	=	11	8.00	
1941	Woodward and Luff, 1943	17	2.00	14

Year	Source	Tons	Gold (oz)	Silver (oz)
1942	1943[4]	10	6.00	6
		Total	**813.95**	**333**

Source: Willden 2006 (and references therein).

Notes:

1. The table in the Wildon 2006 paper does not list a year for the 1928 or 1933 sources.
2. Part of this may have come from Apex mine.
3. Estimated from total Bull Valley production.
4. The table in the Wildon 2006 paper has no source data for 1949 or 1942.
5. The year is written as 1949, but it is believed to be a typographical error and should read 1940.

Tenneco sold the mine to USMX in early 1992 and, through their successor Dakota Mines, closed the mine and reclaimed the Property. Mining ceased in late 1994, with continued rinsing of heaps through 1995. In 1996 during the final phases of mine reclamation, Dakota Mines filed for bankruptcy and the final reclamation monitoring was completed by the State of Utah using funds in the reclamation bond.

Between 1988 and 1996, Tenneco and USMX produced a total of approximately 209,000 ounces of gold and 198,000 ounces of silver (Table 6-2 and Table 6-3) from the heap-leach operation at Goldstrike. Approximately 8 million tons of sediment-hosted disseminated gold ore from sandstone and conglomerate members of the Tertiary Claron Formation and from silty limestone members of the Pennsylvanian Callville Limestone and Mississippian Redwall Limestone was mined from 11 open pits (Table 6-2). The average grade of the ore was reported to be 1.2 g/t Au (0.035 oz/ton Au). Some of the ore was crushed to minus 2 in. (51 mm) and the rest was processed as run-of-mine (Table 6-2). The reported ore cut-off grade was approximately 0.617 g/t Au (0.018 oz/ton Au) over the life of mine. A total of 19 million tons (17 million tonnes) of waste was also mined. Throughout the life of the mine, cash costs, including depreciation, depletion, amortization and reclamation accruals, varied between $220 and $395 per ounce.

Table 6-2: Summary of Goldstrike 1988 to 1996 Gold Production by Pit

Pit	Crusher (tons)	Head Grade [1]	ROM [2] (tons)	Head Grade[1]	Mined (oz)	Waste (tons)
Hassayampa [3]	121,200	0.038	144,400	0.022	7,420	1,019,500
Main Zone	1,263,000	0.048	295,600	0.021	66,350	2,764,600
Hamburg	1,349,900	0.042	937,400	0.023	78,240	6,462,000
Padre Hill	481,100	0.039	331.400	0.022	23,710	2,241,000
Goldtown [3]	111,520	0.043	275,960	0.023	8,980	383,000
Basin	272.620	0.038	73,949	0.020	12,380	1,769,700
Covington	150,000	0.048	240,510	0.025	13,200	463,000
Moosehead & Caribou	547,000	0.048	866,000	0.025	54,000	2,875,000
Beavertail[4]			576,600	0.028	16,140	720,700
Total [5]	**4,296,340**	**0.042**	**3,741,819**	**0.023**	**280,420 [6]**	**18,698,500**

Pit	Crusher (tons)	Head Grade [1]	ROM [2] (tons)	Head Grade[1]	Mined (oz)	Waste (tons)

Source: Willden 2006.

Notes:

1. Head grade = grade in ounces gold per ton.
2. ROM = run-of-mine ore, loaded on heaps without crushing.
3. Two pits combined.
4. All of this ore was treated as run-of-mine although much was of high enough grade to be crushed had the haul to the plant been shorter.
5. An undeveloped ore body lying between the Hamburg and Basin pits was calculated to total 433,100 tons at an average grade of 0.036 opt. The sum of the numbers listed for each pit do not match the total.
6. There is some unresolvable inconsistency in the tonnage and grade figures because an overall grade calculated by multiplying the tonnage by the grade for each deposit does not equal the total shown in the figure as contained ounces.

Table 6-3: Annual Gold and Silver Production 1988 to 1996 (Willden 2006)

Year	Tons	Gold (oz)	Silver (oz)
1988	98,440		
1989	1,015,260	22,709	21,303
1990	956,150	44,202	37,069
1991	665,585	35,658	54,542
1992	1,539,960	34,376	45,667
1993	1,465,000	32,844	20,462
1994	1,117,995	34,486	15,600 (est.)
1995		5,000	3,000
1996		560	none
Total	**6,858,390**	**209,835**	**197,654**

Source: Tons - Utah Division of Oil, Gas and Mining permit files.
Gold and silver- U.S. Bureau of Mines Mineral Industry in Utah in Minerals Yearbook and Utah Geological Survey files

Factors leading to the closure of the mining operation are reported to have included: (1) lack of economic ounces; (2) increasing stripping ratios in some of the pits; (3) increasing haulage distances; and (4) unfavourable royalty payments. Willden (2006) reported that the leach pads had reached their capacity near the end of the mining operations.

The total reported gold production (209,835 ounces) and the total gold ounces reported to have been mined (280,420 ounces; Table 6-2) suggest that the average gold recovery from the heap-leach operations at Goldstrike was approximately 75%. Tenneco and USMX monthly reports suggest that actual recovery varied from approximately 70% to 78% during the life of the mine.

7.0 Geological Setting and Mineralization

7.1 Regional Geology

The Property lies within the Bull Valley Mountains, on the eastern edge of the Basin and Range Province, transitional to the Colorado Plateau. A generalized geological map of the Property is shown in Figure 7-1.

The oldest rocks are of Devonian and Mississippian ages, representing the transition from an open shelf environment to a distal foreland basin related to the Devonian-Mississippian Antler orogeny in central Nevada, and to a return to shallow-water carbonate sedimentation. Pennsylvanian through Permian carbonate and siliciclastic strata in the Bull Valley Mountains represent shallow water and supratidal carbonate deposition in an inner platform setting, with periodic input of siliciclastic material derived from the subaerial exposures to the east. Mesozoic rocks in the district include the Jurassic Navajo Sandstone, consisting of aeolian quartz-rich sandstone.

Rocks as young as Jurassic were strongly deformed during the Late Cretaceous Sevier orogeny, wherein these rocks were folded and thrust imbricated. Thrust faulting and folding were thin-skinned, southeast-vergent and locally placed the Paleozoic section over Mesozoic rocks. The effects of later, Laramide-age contractional deformation are difficult to differentiate from Sevier-age deformation in the area and are likely to be relatively minor. Late Cretaceous to Paleocene basins developed in association with the Sevier highlands and received voluminous deposits of coarse clastic strata, including the Upper Cretaceous Grapevine Wash conglomerate, a syn-tectonic alluvial fan shed off the Square Top Mountain allochthon. The presence of sandstone and conglomerate deposits of Eocene to Oligocene age, including the Claron Formation, suggests continuing active tectonism at that time.

Oligocene and Miocene intermediate to felsic volcanic rocks, including andesite flows and tuffs, overlie the older sedimentary rocks over a large area extending into eastern Nevada (Best, Christiansen and Blank 1989). These are likely related to the “mid-Tertiary ignimbrite flare-up” over most of Nevada, with the age of volcanism becoming progressively younger from approximately 40 Ma north of Elko to 26 to 18 Ma in the Goldstrike area.

East-west and northwest-striking steep faults are common in the region, with both normal and strike-slip movement, resulting in an overall west-northwest structural grain. Strata as young as Miocene in age are tilted gently northeastward, suggesting a listric geometry to at least some of the faults. Paleozoic strata are exposed in a dome-shaped feature in the Mineral Mountain area, perhaps related to uplift from intrusion of the Mineral Mountain laccolith. Faults in the Goldstrike area strike mainly east-northeast, in contrast to the regional structural grain.

Figure 7-1: Generalized Geological Map of the Goldstrike Property



7.2 Property Geology

7.2.1 Property Geology Overview

The Goldstrike area is underlain by Paleozoic rocks comprised of Devonian through Permian interbedded limestone, dolostone, sandstone, siltstone and shale, and Mesozoic rocks comprised of Jurassic and Cretaceous sandstone and conglomerate. As with most areas in the Basin and Range with economic quantities of disseminated gold, the Paleozoic and Jurassic strata are strongly deformed, being complexly folded and faulted during Mesozoic contractional and Cenozoic extensional events.

The Paleozoic and Mesozoic rocks are unconformably overlain by Cenozoic rocks comprised of Paleocene to Oligocene limestone, sandstone and conglomerate, and Oligocene-Miocene ash-flow tuffs (Figure 7-2). Strongly altered mafic dikes of basalt or andesite composition locally intrude the sedimentary section.

The Paleozoic stratigraphy of the Project area is summarized in the stratigraphic column shown in Figure 7-3. Cenozoic stratigraphic units in the Project area are summarized in Figure 7-4. These units are further described in the following sub-sections.

Figure 7-2: Geological Map of the Goldstrike Mine Trend



Source: Liberty Gold 2025.

Figure 7-3: Stratigraphic Column for Paleozoic Rocks in the Goldstrike Project Area



Source: Liberty Gold 2025.

Figure 7-4: Stratigraphic Column for Cenozoic Rocks of the Goldstrike Project Area



Source: Liberty Gold 2025.

7.2.2 Paleozoic Rocks

Paleozoic rocks range in age from possibly Late Devonian through Permian, and form resistant outcrops of limestone, dolomite, and sandstone. The following units are recognized at Goldstrike.

- Mr – Redwall Limestone (Mississippian)
  - This resistant, cliff-forming unit consists of light to medium grey, medium to massively bedded limestone with thin interbeds of white sandstone in the lower half. It is abundantly fossiliferous. Near the middle of the formation, a dark grey bed with abundant syringopora has been mapped as subunit ***Mrc***. A few dolostone beds are also present.
- Chainman Shale and Scotty Wash Quartzite (Mississippian)
  - The Chainman Shale (***Mc***) is recessive, thin bedded, variably carbonaceous, and is locally up to 25 m thick. It contains interbeds of calcareous siltstone and sandy limestone. It is overlain by a thin unit consisting of dark brown orthoquartzite with

shaly partings (***Msw***; Scotty Wash Quartzite). The latter is reported to contain a less than one-metre thick bed of sandstone with abundant plant fragments. In central Nevada, the Chainman Shale represents the distal and youngest manifestation of the Antler Foreland Basin related to the Antler orogenic belt.

- Pc – Callville Limestone (Pennsylvanian)
  - The Callville Limestone consists of relatively resistant, thin- to thick-bedded, variably cherty, fossiliferous, bluish-grey limestone with recessive interbeds of shale and calcareous siltstone. Fossils include corals, brachiopods, crinoids, and bryozoans. The unit is sandy near its base, with one thin orthoquartzite bed. The top of this unit is truncated by a low angle fault. It forms distinctive outcrop patterns due to the alternating recessive siltstone and resistant limestone beds. The Callville Limestone is of variable thickness but has been measured to between 300 m and 450 m thick (Effner 1992). The Callville Limestone is one of the main hosts for gold mineralization.
- Pakoon Formation (Permian)
  - The Pakoon Formation consists primarily of thick beds of yellowish to light grey, variably sandy limestone, sandy dolostone and dolomitic sandstone, with some finer-grained, interbedded siltstone. It can be divided into four subunits, including a lower subunit of primarily dolostone or cherty dolostone (***Ppdl***), a middle subunit consisting of dolomitic sandstone, and one of the main Paleozoic gold hosts (***Pps***), an upper subunit of dolostone (***Ppdu***), and an upper sandy limestone unit (***Ppul***). This formation is often truncated at its base by a low angle fault. Thickness is variable but may be approximately 125 m in total (Effner 1992).
- Pcq – Queantoweap - Coconino Sandstone (Permian)
  - The Queantoweap - Coconino Sandstone consists of well-indurated to sandy weathering, fine-grained, thin- to thick-bedded, variably cross-bedded and locally burrowed quartz arenite. It usually appears yellow-brown in outcrop.

7.2.3 Mesozoic Rocks

Triassic and Jurassic strata are not well exposed on the Property, and are likely more extensive at depth, forming an autochthon under thrusted Paleozoic strata in the hanging wall of the Square Top Mountain thrust fault. A rapidly thickening sequence of late Cretaceous sandstone and conglomerate – the Grapevine Wash Formation - begins at the eastern edge of the Property, thickens rapidly to the south and east, and may represent detritus shed off the hanging wall of the Square Top Mountain Thrust.

- Jns – Navajo Sandstone (Jurassic)
  - The Navajo Sandstone crops out locally in the southern part of the Property, in a small window through the Square Top Mountain Thrust (not shown on Figure 7-3). It consists of relatively massive, pale yellow to white, cross-bedded, quartz-rich sandstone. It is not shown on the cross-sections and stratigraphic columns, as its stratigraphic relationship to other units cannot be determined.
- Kgv - Grapevine Wash Formation (Cretaceous)
  - The Grapevine Wash Formation forms a southward-thickening wedge of coarse clastic material in the southern part of the Property. It is absent in the mine area but is up to 610 m thick a short distance to the south. The Grapevine Wash Formation

consists primarily of crudely bedded, clast-supported, boulder to pebble conglomerate (Goldstrand 1991). It is believed to represent a series of stacked channel deposits, with finer-grained beds within them, consistent with deposition in a stream-dominated alluvial fan environment (Goldstrand 1991). Clastic material was likely sourced from a local highland related to the Square Top Mountain Thrust system. The age of the Grapevine Wash Formation is constrained by the underlying, Upper Cretaceous Iron Springs Formation and the Eocene(?) Claron Formation, which unconformably overlies it (Hintze 1980).

7.2.4 Early Cenozoic Rocks

The Paleocene to Oligocene Claron Formation unconformably overlies strongly deformed and eroded Paleozoic and Mesozoic rocks, and locally overlies the Late Cretaceous (?) Grapevine Wash Formation. At the Property, previous operators subdivided the Claron Formation into seven members, in upper and lower sequences. The Utah Geological Survey and others consider some or all of the upper five members of the Claron Formation as described below to be parts of the Oligocene Wah Wah Springs Formation and Isom Tuff. Given the distinctive nature of the upper members and the Formation status of two of these members, use of the name Claron Formation is here restricted to only the Basal and Red Bed members, and overlying (unnamed) limestone. All early Cenozoic units are highly variable in thickness.

- Claron Formation
  - The Claron Formation (or Claron Formation *sensu stricto*) forms the basal early Cenozoic siliciclastic unit overlying highly deformed Paleozoic and Mesozoic rocks and a Late Cretaceous wedge of coarse clastic rocks. It is poorly sorted and highly variable in composition. The age of this unit is poorly constrained. It is believed to be largely Eocene in age but may locally range in age to as old as Paleocene, based on dating of palynomorph samples from the Pine Valley Mountains (Goldstrand 1991), and as young as middle Oligocene (Rowley et al., 1979). In the Table Cliff Plateau, a 50 Ma fission track age was determined 10 m below the Pine Hollow – Claron contact, suggesting a middle Eocene age for the basal Claron in this area. Fossil gastropods collected in the lower Claron (Goldstrand, 1991) are similar to those reported from the Paleocene to Eocene Flagstaff Formation of central Utah by LaRocque (1960). The Claron Formation is highly variable in thickness region-wide and is relatively thin in the Goldstrike area. It represents deposition of clastic strata in a fluvial-lacustrine basin during the waning phases of the Laramide orogeny (Goldstrand 1994). At Goldstrike, the Claron Formation is subdivided into the following units:
    - Tcb, Basal Clastic Unit
      - The lower unit of the Claron Formation consists of white to yellowish grey, massive to crudely bedded, poorly-sorted, sandstone and conglomeratic sandstone with cement and matrix that may have been originally fairly calcareous. Clasts are polymictic, sub-angular to well-rounded, mostly consisting of limestone, chert, and quartzite sourced from the underlying Paleozoic rocks, and range in size from pebbles to rare boulders. The thickness of the unit ranges from 0 m to more than 30 m, suggesting some relief on the pre-Tertiary contact. Carbonaceous plant fossils are locally present at the basal contact and may have locally acted as a reducing agent for the mineralizing fluids. The Basal Clastic unit of the Claron Formation, particularly the white sandstone, is a main host of gold mineralization at

Goldstrike. It has been demonstrated, in outcrop and drilling, to unconformably overlie units as old as the Mississippian Redwall Limestone and as young as the Late Cretaceous Grapevine Wash Formation.

- Trb - Red Beds Unit
  - The middle unit of the Claron Formation consists of beds of shale, siltstone, sandstone, mudstone, conglomerate, and limestone. In the mine area, this unit is often a distinctive brick red, or maroon colour. Conglomeratic intervals are largely monomictic and contain sub-rounded to sub-angular pebble to cobble-sized clasts of limestone. The thickness of this unit ranges from 0 to 50 m. The red bed unit can also appear white or yellowish if affected by hydrothermal fluids. Where altered, it would likely be identified in core and drill chips as the basal Claron Formation, hence the red bed versus basal Claron designation is not strictly a stratigraphic one, and is at least partially on the basis of alteration.
- Tl1 - Upper Limestone Unit
  - The Upper Limestone unit forms the upper part of the Claron at Goldstrike and consists of thin- to thick-bedded limestone with distinctive interbeds of conglomerate, sandstone and shale. It often has a thin layer of red jasperoid developed at the upper contact. It has a maximum thickness of 50 m and is normally approximately five metres to 15 m thick.
- Tt1 – Needles Range Tuff
  - The Needles Range Tuff at Goldstrike is a recessive slope-former. It is typically greenish brown, dacitic, contains one- to two-millimetre biotite crystals, and is non-welded. The maximum thickness is approximately 10 m and varies widely over the Project area. The Utah Geological Survey has assigned this unit to the “Wah Wah Springs Formation of the Needles Range Group” following the nomenclature of Best and Grand (1987). The Needles Range Tuff is dated at 30.27 ±0.33 Ma using U-Pb methods (DeWitt 2015).

- Isom Formation
  - The Isom Formation at Goldstrike has been divided into three units comprising a middle tuff between upper and lower limestone units.
    - Tl2 - “Lower Limestone”
      - The Lower Limestone unit consists of a poorly to moderately resistant red or yellow to light grey, thinly bedded grey algal limestone, with subordinate sandstone, calc-arenite and recessive-weathering, yellow to tan silty interbeds. It ranges in thickness from three metres to locally over 25 m in thickness.
    - Tt2 - Isom Tuff
      - This unit consists of at least two resistant, trachydacitic cooling units, including an upper purplish-red, densely welded, crystal-poor (approximately 15%) ash-flow tuff, and a lower, dark-grey to black, flinty, densely welded, crystal-poor (approximately 5%) ash-flow tuff that contains linear vesicles. The unit is a prominent cliff former in the mine area. The age of the Isom Tuff

is approximately 27 to 26 Ma. (Best et al. 1989). The maximum thickness of each cooling unit is 12 m, for a total thickness of 25 m.

- Tl3 - “Upper Limestone”
  - The Upper Limestone is a diverse unit consisting of resistant light grey to white algal-bedded limestone with interbedded arkosic sandstone or tuff and red jasper lenses near the top. Locally abundant plant fossils are present. It has a maximum thickness of 50 m and is as little as two to three metres thick in some areas.

7.2.5 Late Cenozoic Rocks

- Leach Canyon Tuff Member
  - This unit forms the lower member of the Quichapa Group and consists of pink, rhyolitic, vitric crystal ash-flow tuff with reddish lithic fragments. Crystals consist of plagioclase, quartz, sanidine, and biotite. The age of the Leach Canyon Tuff is 22.80 ±0.26 Ma by U-Pb methods (DeWitt 2015).
- Bauers and Swett Tuffs, undivided (Condor Canyon Formation)
  - This unit consists of densely welded, purple to reddish-brown andesitic – dacitic ash-flow tuff (Bauers Tuff member) overlying a basal black vitrophyre (Swett member). Crystals include plagioclase, sanidine, and biotite. This unit is believed to be derived from the west, from the Caliente caldera complex.
- Harmony Hills Tuff
  - This member consists of moderately welded crystal-rich tuff, with crystals consisting of plagioclase, biotite, hornblende, quartz, and pyroxene in a pink to reddish matrix.
- Tqv, Tlc - Quichapa Group (Miocene)
  - The Quichapa Group at the Property consists largely of regional ash-flow sheets, and has been divided into three members by Williams (1967) on the basis of distinctive geochemistry and petrography. These are briefly described below and were mapped in a reconnaissance fashion across the Property to estimate the depth to the basal Claron Formation.
- Undifferentiated Tuff and Andesite
  - A number of Miocene volcanic units lie above the Quichapa Group, including the Racer Canyon rhyolite ash-flow tuff, the Tuff of Horse Canyon, and several horizons with andesite flows. The various units are not broken out in Liberty Gold’s mapping and are not shown in Figure 7-4.

7.2.6 Intrusive Rocks

- Mafic Dikes and Sills
  - Dikes and sills with a fine-grained, dark green matrix and 5% to 7% small biotite phenocrysts have been documented cutting through the Paleozoic strata in the mine area and are thought to be largely or entirely of Cenozoic age. Where altered, they are white to tan, with most of the phenocrysts removed by leaching. They may be andesitic or basaltic in composition. They are locally mineralized along their margins. Zones of jasperoid and limonite adjacent to the faulted margins of dikes were some

of the first zones mined at Goldstrike due to the presence of the high-grade and coarsely crystalline gold associated with them. An unaltered dike west of the Hamburg Pit returned a uranium-lead (U-Pb) age date of 18.03 ± 0.29 Ma and a sample of mineralized intrusive near the Covington Pit returned a U-Pb age date of 18.61 ± 0.29 Ma (De Witt 2015). However, dark green lamprophyre(?) dikes cut the 13.51 ±0.14 Ma Mineral Mountain intrusion (see below), implying that there are at least two generations of mafic dikes in the region.

- Felsic to Intermediate Dikes and Sills
  - Dikes and sills of rhyolitic composition have been described near Mineral Mountain but have not yet been recognized in the area of historical open-pit mining (Main Zone). However, there are many zones of white, clay-altered rock near or in larger faults that could have been rhyolitic intrusive rock. The age of these intrusive rocks is unknown, although they appear to post-date Sevier-age deformation, and they have not been seen to cut the Miocene volcanic rocks or the Claron Formation in the Main Mine Area. Quartz-hornblende-feldspar porphyritic dikes are present in the Mineral Mountain resource area. They are virtually identical in composition to the Harmony Hills tuff and may represent feeder dikes. They are not mineralized.
- Mineral Mountain Intrusion
  - The Mineral Mountain intrusion is interpreted to be a laccolith, and consists of resistant light grey to pink, alkali-feldspar granite porphyry with distinctive large phenocrysts consisting of round quartz and quartz-feldspar intergrowths in a matrix of fine-grained orthoclase. Thermal effects in the form of bleaching and recrystallization of limestone and hornfelsing of silty strata extend up to several kilometres from the contacts. The Mineral Mountain intrusion was given a Miocene age of 12.1 ±1.9 Ma based on a questionable $^{40}Ar/^{39}Ar$ age (Rowley et al. 2007). More recent U-Pb age dating yielded a similar result of 13.51 ±0.14 Ma (De Witt 2015). Similar stocks along a linear zone to the northeast, termed the “Iron Axis”, have yielded early Miocene (approximately 21 Ma) K-Ar and $^{40}Ar/^{39}Ar$ ages (Knudsen and Biek 2014).

7.2.7 Structural Geology

Paleozoic and Mesozoic strata at the Project are strongly folded and thrust imbricated. The deepest structural level on the Property is represented by outcrops of the Triassic-Jurassic Navajo Sandstone, which is present in a structural window in the southeastern part of the Property. The overlying Square Top Mountain allochthon, encompassing much of the Project area, is interpreted to be a significant regional feature (Willden 2006). The hanging wall of the Square Top Mountain thrust fault includes the Mississippian Scotty Wash Quartzite and Chainman Shale, which are common units to the northwest, in eastern Nevada, but they do not occur as autochthonous units in southern Utah (Willden 2006). Other units in the hanging wall of the Square Top Mountain thrust include the Redwall Limestone, Callville Limestone, Pakoon Dolomite, and Queantoweap Sandstone. This strongly deformed sequence is in turn overlain by a repeated sequence of the same strata along the Goldstrike thrust fault, the surface expression of which trends roughly northeast across the Property.

The Square Top Mountain and Goldstrike thrust faults are probably of Late Cretaceous-Paleocene (Sevier) age and appear to verge to the southeast, with asymmetric, locally overturned folds in the hanging walls. Significant offset is inferred by the presence of Paleozoic strata emplaced over Mesozoic Colorado Plateau strata. Fault propagation folding along this

thrust fault probably caused the near-vertical bedding in the Pennsylvanian Callville Limestone exposed in the Moosehead Pit. In general, Paleozoic strata in the historical Goldstrike mine trend form an anticlinal structure, the axis of which trends northeast in the western part of the Property, bending around to assume a southeast trend in the eastern part of the Property. A weak axial-planar(?) cleavage is locally developed in shaly to silty units. The distribution of major faults relative to the mined pits at Goldstrike is shown in Figure 7-5.

Figure 7-5: Relative Positions of the Major Structures and Pits from the 1988 to 1996 Mining



Source: Liberty Gold 2025.

Significant vertical relief existed in the district during late Cretaceous time, as evidenced by the Grapevine Wash Conglomerate, which extends southeastward from the Squaretop Mountain allochthon. Very coarse, poorly sorted conglomerate represents colluvial and alluvial fan deposits shed off the allochthon into an adjacent basin to the south.

A significant period of erosion must have taken place post-Sevier thrusting, as rocks younger than Permian are lacking in this area (except for the footwall of the Square Top thrust), and the relatively undeformed Eocene basal Claron Formation overlies the middle to late Paleozoic section and Grapevine Wash Conglomerate on a significant unconformity. Rapid changes in thickness of the basal coarse clastic unit in the Claron Formation suggests some local relief on the erosional surface. There is some debate over whether the Claron Formation in the Goldstrike area represents local deposition in faulted basins, or is more regional in extent. Significant rounding of clasts and diverse clast provenance suggests the latter. Overlying Oligocene to Miocene tuffs are largely conformable, which is suggestive of relative tectonic quiescence during this period.

A major local faulting event most likely occurred in the Miocene following deposition of the volcanic sequence. This event formed faults that trend east-northeast, west-northwest and north-northeast, and created the dominant structural fabric on the Property (Figure 7-1 and Figure 7-2). Faults formed during this event display normal and/or strike-slip displacements of varying magnitude. Faulting resulted in the formation of several horsts, grabens, and tilt blocks. Grabens include the east-trending Goldstrike graben and the northwest-trending Peg Leg graben (Figure 7-5). Willden (2006) interpreted the faulting event that formed the grabens to have exerted some control on the pattern of disseminated gold mineralization.

For example, several deposits including the Basin, Hamburg, and Main pits lie within the Goldstrike graben, while several others, including the Goldtown, Hassayampa and Padre pits, are located in the immediate north footwall area. The south bounding fault of the Goldstrike Graben (Hamburg fault) appears to have been active, or at least present, during mineralization, while the north (Hassayampa) graben-bounding fault has a highly variable geometry and largely or entirely post-dates mineralization, as evidenced by a lack of mineralization in the fault and offset of the (mineralized) Claron basal contact. This horst and graben fabric continues westward in a zone up to two kilometres wide, bounded on the south by the Covington fault and to the north by an unnamed fault. Strata throughout this area are tilted gently to moderately to the north, suggesting listric motion on at least some of the faults.

A prominent set of secondary, west-northwest-striking faults is present throughout the Main Zone. These faults are interpreted as Reidel shears related to right-lateral strike-slip motion along the main graben-bounding faults. Locally, they strongly control mineralization, for example in the Basin Pit. Another set of high angle faults strikes north-northeast, most notably bounding the Main Pit and along the axis of the Padre Pit. These faults are also mineralized and may represent reactivated faults in the Paleozoic rocks that controlled paleotopography to some extent.

7.3 Alteration

The earliest alteration recognized at Goldstrike was interpreted as steep quartz veins, later recognized to be intensely silicified rocks along high-angle faults (Willden 2006). In addition, native gold mineralization in the Hamburg “vein” was believed to be hosted in a coarse calcite vein. Tabular, relatively flat-lying, silicified bodies (jasperoid) were later recognized to be widespread and primarily controlled by stratigraphy.

The most significant zones of mineralization discovered to date are associated with silicified rocks in the basal Claron Formation. Alteration in this unit consists of variably silicified and clay (illite-montmorillonite) altered conglomeratic rocks with associated iron oxide (jarosite – goethite) staining (Greenan 1985), typically with late drusy quartz coatings and coarse crystalline jarosite. Altered zones contain elevated Au, Ag, As, Sb, and Hg. Paleozoic rocks beneath the unconformity are characterized by local zones of silicification, jasperoid, clay alteration, iron oxides, and decalcification of silty carbonate rocks. Late coarse, white calcite veins are present throughout the area. Overall, the alteration and geochemistry are typical of sediment-hosted “Carlin style” systems associated with Paleozoic carbonate strata in Nevada and locally in western Utah.

Effner’s (1992) study is the most in-depth description of alteration to date. He described five periods of hydrothermal activity, including:

- Early-stage carbonate removal (decarbonatization or decalcification) and passive jasperoid replacement:
    - Main hydrothermal stage characterized by brecciation of the jasperoid and addition of silica, disseminated (arsenical) pyrite, illite, and gold;
    - Late-stage quartz veining;
    - Late-stage sulphate deposition; and
    - Final-stage calcite veining.

Subsequently, most of the jasperoid and gold mineralized rocks drilled to date underwent oxidation, such that iron oxides including limonite, jarosite, and goethite are ubiquitous throughout the mineralized zones.

In many areas, oxidized and brecciated jasperoidal gold zones in the basal Claron Formation are overlain by strongly clay altered mudstone with up to 10% disseminated and stringer pyrite. These zones are normally barren of gold, but are weakly mineralized in some locations.

As with the Claron Formation, alteration in the Paleozoic rocks is characterized by local zones of brecciated jasperoid, clay, iron oxides and decalcification of silty limestone or sandstone. Similar to the Claron Formation, two episodes of silicification can be seen clearly in the Paleozoic rocks. The first is represented by passive replacement of calcareous sedimentary rocks, resulting in a massive grey, fine-grained jasperoid, commonly cut by thin irregular calcite veins. This phase of silicification appears to be barren of gold but contains elevated arsenic and/or antimony. Proximal to the major faults, these early jasperoid bodies have been brecciated and then cemented by a second stage of quartz during the main phase of mineralization. These breccias are characterized by abundant iron oxides as gouge fill and can have late calcite, barite, and occasionally stibiconite within the gouge (Figure 7-6).

Zones of clay alteration are common in the Isom and Needles Range tuffs as well as the Leach Canyon Tuff, where they are in close proximity to the fault zones that appear to control mineralization in the Claron Formation. Broad clay alteration zones, with small areas of localized weak silicification with sulphides, are also present in the Harmony Hills and Swett and Bauers Tuffs north of the Beaver Dam Wash. This alteration appears to be related to fault zones and bedding contacts. Given that the Leach Canyon tuff is 22.80 ±0.26 Ma (DeWitt 2015), this evidence suggests that mineralization at Goldstrike may be substantially younger than that in the Carlin Trend, which dates to approximately 38 Ma.

Figure 7-6: Examples of Alteration and Mineralization at Goldstrike



Source: Liberty Gold, 2017

Notes:

A) Early barren passive silica (jasperoid) alteration.

B) Hand sample of mineralized breccia. Clasts are silicified as in 7.6 A. Second stage matrix consists of silica/quartz and iron oxides.

C-G) Examples of alteration and mineralization from PQ (10 cm diameter) core.

C) Tectonic breccia with silicified clasts and Fe-oxide matrix, similar to 7.8B.

D) Collapse breccia with polymictic clast assemblage. Weakly silicified with Fe-oxides.

E) Hydrothermal breccia with polymictic clast assemblage. Strongly silicified with Fe-oxides.

F) Multi-stage breccia developed in basal Claron conglomerate.

G) Basal Claron conglomerate and sandstone, strongly silicified.

7.4 Mineralization

7.4.1 Style of Gold Mineralization

Most of the gold discovered at Goldstrike can be characterized as finely disseminated “micron gold”, incorporated in the lattice of arsenical pyrite grains, in association with strong pervasive silicification. Very little of the mineralization at Goldstrike is preserved in this form, as most of the pyrite has been oxidized to iron oxides including hematite, goethite, and limonite. As discussed above, gold is paragenetically late with respect to silicification, such that most of it is concentrated along fractures. Gold is geochemically correlated with arsenic, silver, antimony,

thallium and mercury, although oxidation tends to disperse elements such as arsenic, making the correlation less strong.

Coarse free gold has been noted in a few locations (see below), in association with silicified Chainman Shale. It is not known how this gold is related to the micron gold described above.

7.4.2 Location of Gold Mineralization

Gold exploited in the late 19th and early 20th century was reportedly mined from structurally controlled jasperoid bodies near the Hassayampa and Hamburg pits (Figure 7-7). In addition, coarse gold was reportedly mined from coarsely crystalline calcite veins at the Hamburg mine (now part of the Hamburg Pit) and Bonanza Mine (Covington Pit), although Willden (2006) asserted that most of the veins were actually silicified zones along faults. The veins at the Hamburg mine were localized along the margin of a strongly altered andesite or basalt dike.

Figure 7-7: View of the Syn-Mineral Hamburg Fault, Hamburg Pit

Source: Liberty Gold 2025.

Note: The Hamburg Fault is a north-side-down fault; offset can be clearly seen in this photo. The Basal Claron Formation and adjacent Redwall Limestone were the primary hosts in the pit, which is now backfilled. The Hamburg Fault is steeply south dipping, with apparent reverse offset, but it is likely that the fault plane has been rotated.

Of greater significance, disseminated micron gold is commonly found in the basal portion of the Claron Formation and Paleozoic strata immediately under it, in association with silicification (jasperoid) and clay alteration, and in particular where the Claron contact is cut by roughly east-west, west-northwest, and north-northeast striking, high-angle faults. This setting is where the Goldtown, Hassayampa, Hamburg, Padre, and Main Zone pits are located (Figure 7-8 and Figure 7-9).

The high-angle faults are primarily mineralized only where they intersect favourable rock types, including conglomerate, sandstone, and calcareous siltstone of the basal Claron above the unconformity. Multiple fault intersections may play a role in localizing mineralization. Most of the graben-bounding faults are mineralized to some degree, with the exception of the Hassayampa fault bounding the north side of the Goldstrike Graben, a feature which post-mineral offsets mineralization in a north side-up configuration. Most of the mineralized faults also show some evidence of post-mineral offset. The main graben-bounding faults bend into a more

southwesterly orientation to the west, with a line of pits along this trend, including the Covington, Caribou, and Moosehead pits. Mineralization in these areas, as well as the Beavertail Pit, is primarily hosted in the Callville Limestone and, to a lesser extent, in the Scotty Wash Quartzite, Chainman Shale, and Redwall Limestone.

Figure 7-8: Generalized Target Concept for Mineralization at Goldstrike



Source: Liberty Gold 2025.

Figure 7-9: Altered Intrusive Rock along a Fault in the Upper Hamburg Mine Area

Source: Liberty Gold 2025

Note: 6.6 g/t Au in sample of oxidized material surrounding the dike.

Faults associated with gold mineralization typically have large zones of calcite veining or calcite vein breccias developed along them. These calcite zones can be up to two metres wide in places. It is assumed that these calcite veins are late with respect to Carlin-style mineralization, and barren, although early reports of gold production state that coarse gold was associated with

the calcite veins. These same fault zones are in places intruded by thin basaltic dikes and sills that locally host coarse gold along their margins and internal steep sheers (Figure 7-9).

Extensive mineralization is also found in favourable Paleozoic carbonate, sandstone and shale units, particularly where they are in proximity to the basal Claron Formation unconformity or large faults. In general, the Paleozoic rock units at the unconformity young east to west in the Main Zone Covington Pit area, with the Redwall Limestone in contact with the Claron Formation in the eastern Main and Hamburg Pit areas and the Queantoweap Sandstone in contact with the Claron Formation north of the Covington Pit. The Callville Limestone is in contact with the Claron Formation in the Moosehead Pit area and probably at Beavertail. In general, the upper portion of the Callville Limestone is the most favourable unit to host mineralization, while the Redwall, Scotty Wash, Chainman, and the middle sandy member of the Pakoon Dolomite also host mineralization. The Queantoweap Sandstone and the upper and lower dolostone members of the Pakoon Dolomite tend to be barren of mineralization. As well, the basal Claron Formation adjacent to these units tends to be less well endowed with gold mineralization than when it is adjacent to more favourable Paleozoic units. This generalization can be extended to locations in the southeast part of the Property where the Claron Formation is in contact with the Grapevine Wash Conglomerate. It is possible that the relative lack of calcite associated with these formations may be a factor in the lack of gold mineralization, or lack of a permeability/porosity contrast.

“Atypical” (for a Carlin system) mineralization has been noted primarily in the Paleozoic rocks, in the form of relatively coarse free gold that is visible with a hand lens and can be panned from drill cuttings or outcrop. Gold is present either in association with medium to pale grey jasperoid or with greenish (chlorite?) altered shale. The total extent of this style of mineralization is unknown at this time. Coarse free gold has been recovered in the historical Hassayampa, Peace, Hamburg, and Bull Run mines as well as along the entire length of the East Fork of the Beaverdam Wash as placer gold.

Disseminated gold mineralization has been documented on a property-wide scale by surface sampling or drilling virtually everywhere that rocks proximal to the Claron Formation unconformity (basal Claron Formation or immediately underlying Paleozoic strata) are exposed, over an approximately 30 km^2 area. The surface extents and depths of known mineralized zones are illustrated in Section 10, Figure 10-3.

The style of disseminated mineralization at Goldstrike is similar to other sediment-hosted gold deposits in the Great Basin, where elemental gold is located within the lattice of arsenical rims on pyrite grains. Mineralization drilled and mined to date is oxidized, and thus the original presence of arsenical pyrite is inferred from the presence of scorodite with iron oxides and by the elevated arsenic content of mineralized rocks. Few other minerals have been noted in association with gold. These include local occurrences of orpiment, realgar, stibnite, and stibiconite.

A number of exploration targets between and around the pits remain, primarily marked by linear zones of elevated gold in soil or rocks, and in shallow drill holes with gold mineralization.

7.4.3 Antimony Mineralization

Weak gold mineralization with strong antimony mineralization is present in the eastern portion of the Property at Antimony Ridge and other areas to the southeast. The mineralization at Antimony Ridge occurs at surface as large, bladed to massive disseminated stibiconite in a multi-phase, silicified breccia with gold (Figure 7-10). Stibiconite, is an antimony oxide formed from the in-situ oxidation of stibnite, the primary antimony sulphide mineral. Many of the surface

exposures of stibiconite have a core of primary sulphide stibnite when broken apart. It is expected that the near-surface antimony oxide mineralization would transition into primary antimony sulphide down dip, below the limit of shallow surface oxidation

Figure 7-10: High-Grade Antimony Mineralization in Outcrop

Source: Liberty Gold 2025.

Note. Bladed crystals of white antimony oxide (stibiconite) with grey/black cores of antimony sulphide (stibnite) from surface exposure of high-grade antimony mineralization in a silicified breccia host rock.

The known high-grade mineralized zone at Antimony Ridge is hosted within a laterally extensive silicified breccia developed along the intersection of high-angle normal faults where they cut through a sequence of Eocene to Miocene lacustrine limestone, epiclastic rock, and tuffs that regionally dip 20° to 25° to the northeast.

8.0 Deposit Types

Goldstrike mineralization is best described to be in the class of sedimentary rock-hosted Carlin-style deposits (e.g., Cline et al. 2005; Robert et al. 2007; Muntean 2018; Muntean and Cline 2018). The Carlin-style class of gold deposits are not unique to the eastern Great Basin. They are characterized by concentrations of very finely disseminated gold in silty, carbonaceous, and calcareous rocks. The gold is present as micron-size to sub-micron-size disseminated grains, often internal to iron-sulphide minerals (arsenical pyrite is most common) or with carbonaceous material in the host rock. Free particulate gold, and particularly visible free gold, is not a common characteristic of these deposits; significant placer alluvial concentrations of gold are therefore not commonly associated with eroded Carlin-style gold deposits.

All Carlin-style deposits in the Great Basin have some general characteristics in common, although there is a wide spectrum of variants (Muntean 2018; Muntean and Cline 2018). Anomalous concentrations of arsenic, antimony, and mercury are typically associated with the gold mineralization; thallium, tungsten, and molybdenum may also be present in trace amounts. Alteration of the gold-bearing host rocks of Carlin-type deposits is typically manifested by decalcification, often with the addition of silica, fine-grained disseminated sulphide minerals, remobilization and/or the addition of carbon, and late-stage barite and/or calcite veining. Small amounts of white clays (illite) can also be present. Decalcification of the host produces volume loss, with incipient collapse brecciation that enhances the pathways of the mineralizing fluids. Due to the lack of free particulate gold, Carlin-style deposits generally do not have a coarse-gold assay problem common in many other types of gold deposits.

Deposit configurations and shapes are quite variable. Carlin-type deposits are typically at least somewhat stratiform in nature, with mineralization localized within specific favourable stratigraphic units. Fault and solution breccias can also be primary hosts to mineralization (Figure 8-1).

Figure 8-1: Cross-Section of a Hypothetical Carlin-style Sediment-hosted Gold Deposit



Source: Robert et al. 2007.

The mineralization identified at Goldstrike shares many of the characteristics of Carlin-type gold mineralization, including:

- Stratigraphic control of mineralization: Goldstrike mineralization is hosted primarily in conglomerate and limestone of the basal Claron Formation, as well as silty limestone in the Callville Formation;
- Structural control on mineralization: occurs in karst cavities, collapse breccias, high-angle faults, and anticlinal fold hinges;
- Geochemical association: elevated arsenic, mercury, antimony, and thallium accompany the Goldstrike gold mineralization, while base-metal concentrations are generally low; and
- Alteration: Goldstrike gold mineralization is associated with decalcification, silicification and/or jasperoid, and clay, as well as pyrite, arsenical pyrite, and arsenopyrite and their oxidized variants.

The Goldstrike deposits also display some characteristics that distinguish them from typical Carlin-style gold deposits (Shabestari and Smith 2020). The general location of the Project is outside the major gold deposit trends in Nevada. Host rocks at Goldstrike are primarily Eocene conglomerate and sandstone with lesser mineralization hosted in Pennsylvanian to Permian silty limestone, whereas the majority of Carlin-style deposits in Nevada are in Ordovician-Devonian platform margin and slope facies rocks. Ag:Au ratios are higher than is typical. Finally, it is likely that mineralization at Goldstrike is considerably younger than Carlin-trend deposits.

9.0 Exploration

Heliostar, through its wholly owned subsidiary Helio Five Resources Ltd., entered into an arms length agreement dated March 20, 2026, to acquire the property from Liberty Gold. This section details exploration activities by Liberty Gold from the time of acquisition of the Goldstrike Project in 2014 up to the Effective Date of the Mineral Resource estimate disclosed in this report. It is exclusive of drilling, which is described in Section 10. Heliostar has not completed any exploration work since acquiring the Project.

9.1 Liberty Gold Compilation

Liberty Gold inherited a partial historical digital drill hole database compiled by North Mining and Cadillac, including unverified spreadsheets, AutoCAD files with drill hole collar information, downhole assay data primarily from original laboratory certificates for most drill holes, some surface geochemical data, and blasthole data for two historical pits as x, y, z coordinates attributed with gold values. Virtually all other historical data came in the form of paper maps, sections, logs, memoranda, and information from the mining operation. Most of these data have been digitized, verified, and assembled into a comprehensive digital database under the supervision of Mr. Shabestari.

As of the Effective Date of this report:

- The drill hole database has a total of 1,391 historical holes. Downhole lithological information has been captured from paper drill logs and all drill hole coordinates have been validated by Liberty Gold through examination of the collar locations against digital topography and photography, as well as some field checking. Laboratory certificates and drill hole logs were used to validate a large proportion of the historical drill hole assays. See Section 12 for additional details on the verification of the Project database.
- Original and/or final pit topography was compiled and digitized from hardcopy maps and digital data from aerial surveys by Olympus Aerial Surveys of Salt Lake City.
- Surface geochemistry was compiled from AutoCAD files and hardcopy maps. As of the Effective Date of this report, a total of 7,912 samples are attributed with locations and gold assays.
- Surface geological mapping in the form of an Adair (1988) map digitized into AutoCAD was properly registered and spot checked and corrected in the field. Pit maps were digitized and amalgamated with this map, and other areas were mapped using data from USGS maps.
- Blasthole data available to Liberty Gold includes a database of approximately 112,000 blast holes from all the open-pit mines except for Hassayampa. Blasthole data from historical bench maps was digitized.

9.2 Liberty Gold Geologic Mapping

Several generations of surface mapping were carried out over three decades, ranging from regional USGS mapping to mining pit maps. The primary references for regional-scale mapping are Hintze et al. (1994) for the southern half of the Property and Rowley et al. (2007) for the northern half. There are a large number of detailed geological maps for the various deposits and target areas in unpublished files from previous operators. The most comprehensive map of the area from Arsenic Nose to Padre Pit is a set of four maps by Inspiration. Tenneco also produced

numerous detailed maps. These maps and other data were evaluated by Liberty Gold, and, where relevant, compiled into a single digital geologic map of the Property. Geological mapping by Liberty Gold staff, primarily by April Barrios and Peter Shabestari, has been ongoing from acquisition of the Property in 2014 through the Effective Date of this report. Figure 7-1 shows a general geologic map of the Property which breaks down the geology into Paleozoic strata, Mesozoic strata, the Claron Formation, Oligo-Miocene volcanic rocks and intrusive rocks. Figure 7-2 provides more detail of the mapped distribution of stratigraphic units in the Goldstrike mine trend.

9.3 Liberty Gold Soil Sampling

Liberty Gold contracted Rangefront Mining Services (Rangefront) consulting company, of Elko, Nevada, on three occasions, once in 2014 and twice in 2016, to carry out a grid-based soil sampling program to expand the footprint of previous soil sampling programs on the Property (Figure 9-1). A total of 1,987 samples were collected by Rangefront on five grids with sample spacing ranging from 100 m x 100 m to 50 m by 75 m. C-horizon mineral soils were generally collected, as organic soil development on the Property is poor. Areas of mine dump and younger stratigraphic units above any known mineralization were not sampled. Further details of sampling and analytical methods are discussed in Section 11.0.

Historical soil sampling was carried out throughout the Goldstrike mine trend, extending southward to the Jedediah area, the Potter's Peak area and the Black Canyon to Mineral Mountain area. Gold in soils can be directly correlated to areas of outcropping mineralization.

Soil sampling by Liberty Gold was extended to areas north, east, and southeast of the Main, Padre, Hassayampa, Goldtown, Hamburg, and Basin pits, where outcropping mineralization gave rise to significant gold-in-soil anomalies in historical soil sampling. Only very minor gold anomalies were detected in this sampling. However, a strong antimony anomaly was detected to the southeast of the pits. Follow-up work discovered a 200 m long jasperoid breccia with abundant stibiconite pseudomorphs after stibnite that yielded anomalous gold in rock samples.

Liberty Gold also extended soil sampling westward along the northern edge of the "western grabens" area to the west of the historical mine trend. Gold-in-soil anomalies were detected in areas underlain by jasperoidized Paleozoic carbonate strata, with > 4 g/t Au detected in one sample.

A separate soil grid over the eastern portion of the Property defined a strong, linear, east-west-trending zone with elevated As and Sb in the vicinity of the Quail Springs target.

Correlation matrices for the Liberty Gold soil samples show a moderate correlation of Au with Hg-Sb-Ni-Te-Zn-Mo-Tl-As-W-Cu.

Figure 9-1: All Historical and Liberty Gold Soil Samples at Goldstrike



9.4 Liberty Gold Rock Sampling

To characterize the alteration and gold mineralization of the Property beyond what had been previously done, Liberty Gold collected 1,331 rock samples throughout the Property, primarily as grab samples, from 2014 through 2024. Sample locations and sample descriptions, including lithologic type and alteration, were logged into a handheld global positioning system (GPS) unit with ArcPad. The sample locations and results are shown on Figure 9-2. Further details of sampling and analytical methods are discussed in Section 11.

Sample values ranged from below detection to a high of 26.3 g/t Au. Correlation matrices for all the rock samples show a strong Au-Ag-Sb-Te affinity and a lesser Au-Hg-Tl-Zn-Ni-As-Mo-Cu correlation. The sampling indicates that gold is most closely associated with multi-phase jasperoid breccias with strong jarosite-limonite-hematite gouge. Late drusy quartz, euhedral jarosite and occasionally barite are common in the higher-grade samples. Jasperoid breccias are typically found within and adjacent to the major fault zones as well as along receptive bedding contacts and the regional unconformity between the Paleozoic rocks and the basal Claron Formation.

The Antimony Ridge area, located in the eastern portion of the Property (Figure 9-3) was explored for gold in previous field campaigns. The presence of antimony mineralization was known and previous operators had done some trenching and bulk sampling. In 2024, a program of rock sampling and mapping was carried out by Liberty Gold to assess the extent of antimony mineralization. This program of sampling and mapping located three new zones of antimony mineralization, with grades up to 5.7% Sb from outcrop grab samples. Antimony mineralization occurs at the contact between the upper Claron Formation and older Miocene volcanic rocks. Disseminated antimony mineralization is present in silicified breccias and as coarse stibiconite veins up to 3 cm wide. Larger crystals commonly have a rind of oxidation and are cored by the antimony sulphide stibnite.

Figure 9-2: All Historical and Liberty Gold Rock Samples at Goldstrike



Figure 9-3: Plan Map of Goldstrike Area Showing Select Antimony Values in Rock Samples



9.5 Liberty Gold Three-Dimensional Modelling

Liberty Gold compiled a three-dimensional (3D) geological model for the Goldstrike property in Leapfrog software to aid in drill targeting and resource estimation. As of the Effective Date of this report, 3D modelled geology extends to the Main, Dipslope, Padre, Peg Leg, Moosehead and Beavertail, all being relatively intensively drilled.

9.6 Liberty Gold Induced Polarity Geophysics

A Volterra 2D Induced Polarization (IP) survey was carried out from July 6 to 21, 2017, consisting of five widely-spaced lines over the historical mine trend, for a total of 11,075 linear metres. The purpose of the survey was to evaluate the usefulness of IP to identify jasperoid bodies (resistors) and/or disseminated sulphide (chargeability highs) that might be related to gold mineralization. One line (4400E; Figure 9-4) was designed to cross several well-drilled areas, in order to observe whether specific features could be seen in the survey.

Figure 9-4: Map Showing Induced Polarity Lines, Goldstrike 2017 Program



The survey was carried out by SJ Geophysics Ltd of Vancouver, British Columbia (Enns 2017). A proprietary data collector system (Volterra Distributed Acquisition System) was used. The survey utilized an interlaced array, with dipole lengths ranging from 50 m to 100 m. Data quality was assessed in the field. Surface contact resistances were relatively low, in part due to the arid and sandy surface conditions. Data were subject to the UBC-GIF inversion algorithm, with the resulting inversion models compared to known 3D geological information.

The chargeability inversion sections (Figure 9-5) show that chargeability features are relatively subdued, with a maximum of approximately 15 milliseconds. The survey successfully modelled features on line 4400E, such as the zone of disseminated pyrite in the clay-altered Claron mudstone that typically overlies silicified oxide gold zones.

Figure 9-5: IP Chargeability 2D Inversion Sections, Goldstrike 2017 Program



Source: Liberty Gold and SJ Geophysics 2017.

The resistivity inversion sections (Figure 9-6) highlight a number of highly resistive features. Small, shallow resistors on line 4400E generally correspond to known areas of jasperoid associated with the basal Claron Formation. Paleozoic rocks including dolostone and limestone are very resistive. A deep resistor on line 4300E was tested with one drill hole (Figure 9-7). It contained a section of jasperoid at the top of the resistor and consisted of massive limestone and dolostone. The silicified area contained anomalous gold mineralization.

Overall the IP survey was very effective at mapping the known structural and lithologic changes (Figure 9-7). Zones of strong sulphide alteration, such as in the Covington intrusive, were mapped well by the chargeability.

Figure 9-6: Resistivity 2D Inversion Sections, Goldstrike 2017 Program



Source: Liberty Gold and SJ Geophysics 2017.

Figure 9-7: Interpreted Geology on Resistivity – Line 4300E, Goldstrike 2017 Program



Source: Liberty Gold and SJ Geophysics 2017.

9.7 Summary Statement on Surface Exploration by Liberty Gold

The SLR QP cannot comment on the soil and rock sampling methods and sample quality. These data were not the focus of SLR's data verification efforts.

10.0 Drilling

Heliostar, through its wholly owned subsidiary Helio Five Resources Ltd., entered into an arms length agreement dated March 20, 2026, to acquire the property from Liberty Gold. This section details drilling programs completed by historical operators and by Liberty Gold up to the March 23, 2026 effective date of the Mineral Resource estimate disclosed in this report. Heliostar has not completed any drilling since acquiring the project.

10.1 Historical Drilling

Heliostar's Goldstrike Project historical drill hole database has a record of 11 companies carrying out RC, rotary, and core drilling on the Goldstrike property from 1978 to 2012 prior to Liberty Gold acquiring it (refer to Section 6.2 for descriptions of the areas targeted and explored), for a total of 1,389 holes for 87,020 m drilled (Table 10-1, Figure 10-1, and Figure 10-2).

Table 10-1: Summary of Historical Drilling in Heliostar's Database

Company	Year	RC/Rotary Holes		Core Holes		Total	
		No.	Metres	No.	Metres	No.	Metres
Occidental Minerals	1978	10	629.4			10	629.4
Houston International	1980-1981	37	2,054.4			37	2,054.4
Permian	1982-1987	39	1,822.7			39	1,822.7
Inspiration	1985-1986	205	9,318.7	5	160.0	210	9,478.7
Tenneco	1987-1992	910	57,526.6	2	69.2	912	57,595.8
Goldsil	1988-1989	30	2,487.2			30	2,487.2
Pegasus	1989-1990	2	70.1			2	70.1
USMX	1993	128	7,863.8			128	7,863.8
North Mining	1997			3	664.5	3	664.5
Bull Valley	1999	6	2,706.6			6	2,706.6
Cadillac	2011-2012	3	566.9	9	1,079.9	12	1,646.8
Historical Drilling Totals		*1,370*	*85,046.4*	*19*	*1,973.6*	*1,389*	*87,020.0*

Reported totals, and occasionally hole types, sometimes conflict with the Project database, as not all holes are documented sufficiently to be entered into the database. The drilling totals are derived from historical reports where possible or from Heliostar's Project database. There are no downhole survey data in the Project database for any of the historical holes. Almost 80% of the historical holes in the database were reportedly drilled vertically, and only 32 of the 1,389 historical holes were drilled to depths in excess of 125 m.

Additional historical drilling programs records include:

- Goldsil, 1998 to 1999. C&L drilling of Nampa, Idaho was the RC drilling contractor.
- Tenneco, 1987 to 1992. The drill contractors known to be used by Tenneco in 1990 include Miller Drilling Company of Orem, Utah and Five O Drilling of Las Vegas, Nevada.

Miller Drilling Company was also used during at least part of 1991. Company files suggest that Stratagrout Drilling of Las Vegas, Nevada was utilized in 1992.

- North Mining, 1997. The drilling was performed by Boart-Longyear utilizing a Longyear 44 drill rig and wireline diamond coring. The core diameter was HQ (63.5 mm) except where it was necessary to reduce to NQ (47.6 mm). The collars were surveyed, but the type of survey is not known. A downhole survey was taken every 61 m down hole. The type of survey tool is unknown.
- Bull Valley, 1999. Hole depths ranged from 366 m to 512 m.
- Cadillac, 2011 to 2012. The drill contractor was More Core Diamond Drilling Services Ltd. of Stewart, B.C. Core diameter was NQ. The RC holes were drilled using a Schram 685 track-mounted drill rig operated by National Drilling of Elko, Nevada. No downhole surveys were carried out. Cadillac determined the drill collar locations with a handheld GPS.

Figure 10-1: General Map of Historical and Liberty Gold Drilling Sites



Figure 10-2: Drilling by Company and Year



10.2 Liberty Gold Drilling, 2015 to 2022

10.2.1 Liberty Gold Drilling Summary

Liberty Gold conducted seven drilling programs at Goldstrike from: November 2015 to December 2015; March 2016 through December 2016; February 2017 through December 2017; March 2018 to November 2018; May 2019 to June 2019; June 2021 to December 2021 and March 2022 to August 2022. As of the Effective Date of this report, the drill hole database contains a total of 984 holes for 130,218 m of drilling. Drilling from 2015 to 2022 at the Project includes 922 RC holes for 125,053 m, 39 core holes for 4,364 m, and 23 sonic holes for 802 m. This includes 18 RC holes drilled in 2017 and 2018 from the Mineral Mountain and Jedediah areas that are no longer part of the Goldstrike property (Table 10-2).

Table 10-2: Summary of 2015 to 2022 Liberty Gold Drilling

Company	Year	RC Holes		Core Holes		Sonic Holes		Total	
		No.	Metres	No.	Metres	No.	Metres	No.	Metres
Liberty Gold	2015	18	2,877.3					18	2,877.3
Liberty Gold	2016	164	24,644.6	11	1,556.2			175	26,200.8
Liberty Gold[1]	2017	284	45,638.6					284	45,638.6
Liberty Gold[2]	2018	200	23,298.9	15	1,395.8			215	24,694.7
Liberty Gold	2019	48	4,575.0					48	4,575.0
Liberty Gold	2021	108	15,572.2					108	15,572.2
Liberty Gold	2022	100	8,446.0	13	1,412.0	23	801.5	136	10,659.5
Liberty Gold Drilling Total		*922*	*125,053*	*39*	*4,364*	*23*	*802*	*984*	*130,218*
Historical Drilling Totals		*1372*	*85,202*	*19*	*1,974*			*1,391*	*87,175*
Totals		**2,294**	**210,254**	**58**	**6,338**	**23**	**802**	**2,375**	**217,394**

Notes:
1. Includes 14 RC holes (1937.0 m) that are no longer on Goldstrike Claims
2. Includes 4 RC holes (368.8 m) that are no longer on Goldstrike Claims

In late 2015, Liberty Gold drilled in the Main and Moosehead areas. In 2016, further holes were drilled in the Main, Peg Leg, Dip Slope, Western Grabens, and Moosehead areas. In 2017, holes were drilled in the Main, Peg Leg, Dip Slope, Western Grabens, Padre, Moosehead, Beavertail, Mineral Mountain, Jack's Camp, and Jedediah areas. Drilling from 2018 and onward focused primarily on infill and step-out drilling around the historical pits and defined targets. No drilling took place in 2020, and no drilling was carried out in 2023 or 2024.

The drilling contractor for the 2015 RC drilling program was Major Drilling of Salt Lake City, Utah. A truck-mounted Schramm 450 type drill rig was utilized with a rotating wet "cyclone" type splitter sample return and 4.5 in. to 6 in. diameter bits. All drilling was done with water injection.

The drilling contractor for RC holes drilled subsequently in 2016 through 2022 was Boart Longyear of Elko, Nevada. Track-mounted Foremost MPD 1500 type drill rigs were utilized, with a rotating wet "cyclone" type splitter for sample return and 4.5 in. to 6 in. diameter standard or centre-return bits. All drilling was done with water injection.

Downhole surveys for the RC holes through PGS001-PGS690 (2015-2018) were carried out by logging contractor International Directional Services (IDS) of Elko, Nevada. IDS utilized a truck-mounted, through-the-drill steel Reflex Gyro gyroscopic survey instrument. Readings were taken at the bottom, top, and at 15 m intervals throughout the completed drill hole. There generally can be more deviation in RC holes, however, significant drill hole deviations have not been encountered in the RC drilling at Goldstrike. While an attempt was made to conduct a downhole survey on every hole, there are 25 Liberty Gold holes without surveys due to logistical considerations.

For Liberty Gold's 2019 drill program, downhole surveys were conducted using a north-seeking, solid state gyroscopic tool (Reflex EZ-Gyro) that was rented from Imdex Limited, along with a paired depth counter and a wireline winch mounted on a trailer. The tool was programmed to read at set depth intervals of 15.2 m as it travelled down the hole, with a second survey run at the same intervals on the way out of the hole. The downhole surveys were completed by Liberty Gold personnel, who then manually downloaded the data from the tool to a handheld device where the data was checked for accuracy before the hole was abandoned.

For Liberty Gold's 2021 and 2022 surveys, a north-seeking, solid-state gyro tool made by SPT was rented from IDS, along with a blue-tooth-paired depth counter and wireline winch. The tool reads continuously as it travels the hole, with the Gyromaster software programmed to export a reading at each 15.2 m interval. The downhole surveys were completed by Liberty Gold personnel, with specific protocol followed to verify precision of the survey before the hole was abandoned. The Gyromaster software compares the in-run and the out-run of each survey, and a threshold of <1.4% variance is met before any survey is considered complete. If needed, such as on deeper holes and holes steeper than -75°, spring centralizers were installed on the tool to reduce rotation during the survey.

The drilling contractor for the core holes drilled was Major Drilling of Salt Lake City, Utah, using a track-mounted LF-90 drill rig and PQ tools. Downhole surveys for core holes were completed with a Reflex E-Z Shot electronic solid-state single-shot downhole camera supplied by Major Drilling. Readings were taken at the collar and at approximately 30 m intervals down hole. Significant hole deviations were not encountered. The Major E-Z Shot tool was cross checked using the IDS instrument and no major discrepancy was noted.

Collar locations were initially located in the field by Liberty Gold personnel using a Trimble GeoXH type handheld GPS unit receiver with differential correction accuracy of 0.5 m in the X and Y directions and one metre in the Z direction. Subsequent to drilling, drill holes were abandoned according to Nevada state regulations. After completion of the holes, the collars were marked with stamped brass tags on a steel wire and their locations were again surveyed by Liberty Gold personnel using a Trimble GeoXH type GPS unit. At the end of 2016 and 2017, most of the drill pads were surveyed by All Points North Surveying and Mapping (All Points North) of Elko, Nevada, using a geodetic survey-grade Trimble 4000-series GPS receiver with a base station for real-time correction. Accuracy of the measurements is ±2 cm in the X and Y directions and ±3 cm in the Z direction. The surveys were specific to some, but not all drill collars. Where multiple holes were drilled from one pad, normally only the most recent collars were recovered, while previous collar locations were destroyed by subsequent drilling activity. For unrecoverable drill collars, the X and Y coordinates from the previous Liberty Gold survey were used, with the Z coordinate from the All Points North survey.

The primary purpose of the 2015 program was to validate drilling carried out by previous operators, and to test the hypothesis that mineralization extends down-dip of the historical pits along the Claron Formation basal contact. Holes were drilled over approximately 4 km along the

historical Goldstrike mine trend. The drilling provided proof of concept that mineralization extends down dip and lateral to the historical pits.

The drill program in 2016 focused primarily on resource definition in the Main Zone, defined as mineralization contained within the Goldstrike Graben. Late in the year, other targets, including the dip slope north of the Hassayampa Fault, the Covington Pit area and the Peg Leg Graben south of the Main Zone, were tested.

In 2017, in addition to continued drilling in the areas listed above, drilling was significantly expanded to include the Padre Pit area, and areas in the western portion of the historical mine trend, including the Moosehead and Caribou pits and several unnamed areas to the north. The Mineral Mountain area was also drilled. Late in the season, several outlying target areas were tested.

In 2018, 21 RC holes were drilled into the heap-leach pad to test for unleached gold in leach material and underlying pad fill and bedrock. Results indicated the presence of unleached gold throughout the heap-leach pad area and beneath it. Six RC holes tested backfill in the Goldtown Pit, with four holes returning gold intercepts. Exploration drilling focused on the Main Zone, an initial drill test of the Peg Leg area, the Dip Slope, and the Beavertail Pit area. Several outlying targets including Potters Peak, Jedi, Jacks Camp, and Big Red were also tested.

Fifteen large-diameter metallurgical core holes totalling 1,357 m were drilled into the Moosehead and Beavertail zones.

In 2019, a relatively modest RC drilling program tested an area west of the historical Beavertail Pit and extended mineralization in the Dip Slope Area. Infill and step-out drilling in the Main Zone was also carried out.

In 2021, Liberty Gold drilled 108 RC holes. The Hamburg Pit area of the Main Zone was drilled to convert Inferred Resources to Indicated and extend mineralization along the Basin Fault. The Hassayampa Pit area was drilled down dip to the north. Backfill material in the Hassayampa Pit was also drill tested, with encouraging results. Areas around the Beavertail Pit, Basin Pit and the Dip Slope were also drill tested.

In 2022, eleven bulk samples were collected for metallurgical testing. Twelve large diameter metallurgical core holes were drilled in the Main, Padre, and Hassayampa areas. One hundred resource definition, condemnation, and exploration RC drill holes totalling 8,453 m were added to the Padre, Dip Slope, Peg Leg, and Main Zone areas.

Also in 2022, Liberty Gold completed 801.5 m of sonic drilling in 23 holes in the two leach pads making up the historical heap-leach pad and in adjacent and underlying backfill areas. All holes returned at least 15 m true thickness of above reporting cut-off grade (0.15 g/t Au) oxide gold mineralization, with some holes in the thicker portions of the pads returning up to 44 m of continuous mineralization. Cyanide solubility of gold in assay pulps, as expected, returned a wide range of values, but generally showed a good correlation between grade and solubility, with some higher-grade intervals returning in excess of 90% cyanide solubility. These data suggest that much of the gold in the historical heap-leach pad was incompletely leached during the historical mining operation and is potentially available for extraction by re-leaching.

10.2.2 Main Zone (Goldstrike Graben)

The Main Zone is defined as the area within the Goldstrike Graben as far west as the western margin of the Aggie Zone and including the Main, Basin, and Hamburg pits.

Nine holes were drilled in the Main Zone in 2015. This test demonstrated the continuity of mineralization along the basal Claron unconformity down dip and between historical pits. Highlights include:

- 39.6 m grading 1.01 g/t Au in hole PGS003.
- 41.1 m grading 0.84 g/t Au in PGS004.
- 22.9 m grading 1.68 g/t Au in PGS008.
- 36.6 m grading 1.06 g/t Au in PGS010.

Liberty Gold continued drilling in the Main Zone area in 2016, with the primary goal of obtaining sufficient information for estimation of a resource. Drill holes were designed to provide an optimal spacing of no more than 50 m throughout the main area. Drilling in the Main Zone generally supported the concept that mineralization is widespread along the basal contact of the Claron Formation, with elevated grades noted along cryptic west-northwest- and northeast-striking faults. Thickness of the basal Claron Sandstone, which can vary over relatively short distances due to the paleotopography present in the Paleozoic rocks, was also recognized as a local control to mineralization. Core drilling in particular highlighted the importance of breccias; while jasperoid is widespread along the basal Claron Formation contact, grades in excess of 1 g/t Au are generally only associated with jasperoids that were subject to tectonic or hydrothermal brecciation and subsequent deposition of additional silica and gold.

Near the east end of the Main Zone, relatively high-grade and thicker mineralization extends north-northeastward from the eastern Hamburg Pit. This area of the Main Zone, yielded several long intercepts of gold mineralization, including:

- 2.10 g/t Au over 35.1 m in PGS019, including 4.42 g/t Au over 13.7 m.
- 3.28 g/t Au over 38.1 m in PGS048, including 4.92 g/t Au over 22.9 m, including 8.27 g/t Au over 10.7 m.

Along reference section lines displayed on Figure 10-3, the Hassayampa to Hamburg section illustrates a vertical section through the Main Zone into the eastern Dip Slope Zone, highlighting Liberty Gold drilling and the Leapfrog model derived from drill holes and blast holes (Figure 10-4). This area of better-than-average gold grade and thickness may be related to reactivated, older faults in the Paleozoic that acted as controls to the paleotopography and hence to the thickness and composition of the Basal Claron Formation. North-northeast striking faults also likely acted as fluid pathways.

At the west end of the Main Zone, a zone of mineralization called the Aggie Zone was discovered in 2015 drill hole PGS-10 (Figure 10-5). This zone contains elevated concentrations of gold in an unusually thick section of conglomerate and breccia. Mineralization was drilled to the northwest of the Aggie Zone in an area named the Warrior Zone. Subsequent drilling showed that the two areas form a single zone, connected by a narrow, northwest-striking fault zone.

Figure 10-3: Vertical Section Locations, Main Area and Peg Leg to Dip Slope Zone



Source: Liberty Gold 2025.

Figure 10-4: Hassayampa-Hamburg Pit Section, View to the East



Figure 10-5: Dip Slope - Aggie - Peg Leg Cross Section, View to the East



Source: Liberty Gold 2025.

Highlights from the Main Zone include:

- 1.07 g/t Au over 30.5 m in PGS020.
- 1.56 g/t Au over 27.4 m in PGS025.
- 1.19 g/t Au over 57.9 m in PGS026.
- 1.14 g/t Au over 47.2 m in PGS027.
- 1.05 g/t Au over 24.4 m in PGS035.
- 1.85 g/t Au over 30.5 m in PGS041C, incl. 2.63 g/t Au over 18.3 m –(core hole)
- 0.87 g/t Au over 61.0 m in PGS049, incl. 2.83 g/t Au over 7.6 m.
- 0.87 g/t Au over 45.4 m in PGS046C – (core hole)
- 0.76 g/t Au over 67.1 m in PGS053, including 1.91 g/t Au over 6.1 m.
- 2.24 g/t Au over 58.8 m in PGS054C, including 2.77 g/t Au over 36.2 m – (core hole)
- 0.96 g/t Au over 76.2 m in PGS058, including 1.98 g/t Au over 19.8 m.
- 1.53 g/t Au over 25.9 m including 3.48 g/t Au over 9.1 m in PGS242.
- 0.85 g/t Au over 50.3 m including 1.81 g/t Au over 15.2 m in PGS235.
- 0.62 g/t Au over 50.3 m including 1.61 g/t Au over 7.6 m in PGS243.
- 1.43 g/t Au over 13.7 m including 2.33 g/t Au over 7.6 m in PGS237.

Infill drilling in the Main Zone, including relatively untested areas along the western extension of the Hamburg Fault, continued from 2018 through 2022, but did not change the model in a material way.

10.2.3 Dip Slope Zone

Near the end of 2016, drilling was expanded to the “Dip Slope Zone”, comprising the footwall of the Hassayampa Fault, which includes the historical Goldtown, Hassayampa, and Padre pits (Figure 10-4 and Figure 10-5). Strata are generally flat lying near the Hassayampa Fault, then roll over to dip gently to moderately northward toward Beaverdam Wash. Due to disturbance and access constraints, as well as the shallow nature of mineralization, holes drilled in this area in 2016 were widely spaced, with mixed results. It is apparent from this drilling that the basal Claron Formation thins north of the Goldtown Pit, and has highly variable thickness in the Dip Slope, limiting potential for thicker, continuous mineralization in the Basal Claron Formation. There is a fair degree of structural control on the distribution of mineralization in this area, with holes adjacent to northwest-striking faults yielding significant intercepts, while holes drilled a short distance away yielding only anomalous or low-grade mineralization. 2016 highlights from the Dip Slope Zone include:

- 0.51 g/t Au over 41.1 m including 1.24 g/t Au over 6.1 m in PGS142.
- 1.14 g/t Au over 6.1 m in PGS144.
- 0.58 g/t Au over 21.3 m in PGS153.
- 2.81 g/t Au over 3.0 m in PGS161.
- 0.66 g/t Au over 36.6 m including 1.16 g/t Au over 15.2 m in PGS220.

With the receipt of the Plan of Operations in 2017, access to the Padre Pit area and to the area north of the Hassayampa Pit was established. Results from this area include:

- 1.93 g/t Au over 10.7 m within 0.67 g/t Au over 53.3 m in PGS335
- 0.96 g/t Au over 10.7 m and 0.38 g/t Au over 39.6 m in PGS342
- 1.35 g/t Au over 10.7 m within 0.69 g/t Au over 39.6 m in PGS347
- 1.89 g/t Au over 13.7 m within 1.22 g/t Au over 32.0 m in PGS362
- 2.03 g/t Au over 3.0 m within 0.65 g/t Au over 38.1 m in PGS365
- 2.39 g/t Au over 7.6 m within 0.91 g/t Au over 82.3 m in PGS461.

North of the Hassayampa Pit and west of the Padre Pit, the Dip Slope Zone of mineralization is relatively deep, and extends below the zone of oxidation, limiting upside.

Limited drilling took place north of Beaverdam Wash, demonstrating that the Dip Slope Zone is present in this area. However, the topography relative to the northerly dip of the zone would present challenges to mining in this area.

10.2.4 Peg Leg Graben

Fifteen holes in late 2016 tested for mineralization in the Peg Leg Graben area located to the south of the western extent of the Main Zone (Figure 10-5). The Peg Leg area was tested in historical drilling with several shallow drill holes into mineralized jasperoid hosted in the Callville Formation in the north footwall of the Graben. Only five historical holes tested the graben itself. Liberty Gold drilled widely-spaced holes over a 1000 m x 200 m portion of the graben floor. Holes targeting the unconformity in the southeastern portion of the graben were largely barren, but holes in the western part of the graben contained significant intercepts of gold mineralization, particularly where located adjacent to fault zones. 2016 Highlights from the Peg Leg graben include:

- 1.78 g/t Au over 29.0 m including 3.54 g/t Au over 12.2 m in PGS179.
- 0.90 g/t Au over 6.1 m and 0.76 g/t Au over 33.5 m including 1.47 g/t Au over 6.1 m in PGS183.
- 1.33 g/t Au over 18.3 m in PGS187.

Infill drilling continued in 2017, with an emphasis on the mineralized northern bounding fault of the Graben. Results include:

- 0.64 g/t Au over 33.5 m and 0.77 g/t Au over 4.6 m and 0.96 g/t Au over 1.5 m in PGS338.
- 0.52 g/t Au over 32.0 m in PGS355.
- 0.56 g/t Au over 7.6 m and 1.71 g/t Au over 3.0 m within 0.77 g/t Au over 22.9 m in PGS356.
- 2.32 g/t Au over 3.0 m within 0.82 g/t Au over 13.7 m in PGS363.

Additional drilling in subsequent years better defined the zone of mineralization. However, depth to the zone and lack of oxidation of the mineralized rocks limit potential in this area.

10.2.5 Covington Pit

One hole was drilled in 2015 north of the historical Covington Pit, targeting an altered mafic dike with gold associated with oxidized shears exposed in a roadcut. It returned:

- 18.3 m grading 2.72 g/t Au in PGS012, including 10.7 m grading 4.32 g/t Au, with a single high sample of 18 g/t Au.

The dike strikes east-west and is near vertical in orientation. Subsequent results include:

- 1.57 g/t Au over 6.1 m and 4.10 g/t Au over 7.6 m including 6.32 g/t Au over 4.6 m in PGS191.
- 1.15 g/t Au over 10.7 m in PGS182.
- 0.83 g/t Au over 3.0 m and 7.36 g/t Au over 1.5 m in PGS178.
- 0.74 g/t Au over 6.1 m in PGS 185.

Drilling was largely unsuccessful in an attempt to extend mineralization remaining in the Covington Pit either laterally or down dip, suggesting a wedge-shaped, rootless geometry of mineralization.

10.2.6 Moosehead and Caribou Pits

In 2015, the proof of concept drilling program tested this area with several holes. Highlights include:

- 0.48 g/t Au over 71.6 m in PGS013.
- 0.47 g/t Au over 39.2 m in PGS014.

In 2017, the Moosehead and Caribou Pit areas were targeted for drilling down dip and slightly north of mineralization in historical drill holes, as well as between the pits and laterally to the northeast and southwest of them (Figure 10-6). Results include:

- 0.90 g/t Au over 3.0 m and 0.45 g/t Au over 79.2 m and 0.38 g/t Au over 10.7 m in PGS279.
- 2.09 g/t Au over 6.1 m within 0.69 g/t Au over 30.5 m; and
  0.41 g/t Au over 7.6 m; and 0.48 g/t Au over 13.7 m; and
  1.79 g/t Au over 10.7 m within 0.74 g/t Au over 41.1 m in PGS281.
- 1.20 g/t Au over 6.1 m within 0.62 g/t Au over 44.2 m in PGS289.
- 1.97 g/t Au over 6.1 m within 0.65 g/t Au over 36.6 m in PGS291.
- 1.62 g/t Au over 9.1 m within 0.78 g/t Au over 27.4 m in PGS295.
- 0.74 g/t Au over 30.5 m in PGS298.
- 0.97 g/t Au over 6.1 m within 0.48 g/t Au over 39.6 m in PGS317.

Significant mineralization was encountered in subsequent drilling in the area between the Moosehead and Caribou pits.

Figure 10-6: Moosehead Pit Section, View to the Northeast



Source: Liberty Gold 2025.

Mineralization in this area is hosted within multiple strands of the steeply dipping Covington fault zone, as well as in entrained lenses of the basal Claron Formation that step down to the northwest within the fault zone.

10.2.7 Mineral Mountain

Mineral Mountain is no longer included in the Property, as the lease with Ray Hunter was not renewed. This information is included for historical information.

The Mineral Mountain area, in the northwest corner of the Property, had seen considerable drilling by several operators, including Tenneco and Tonogold (Puchlik, 2010). The area was mapped, sampled and modelled by Liberty Gold before 13 RC holes were drilled to test for down-dip extensions of mineralization along a normal fault bounding the west side of the mineralized zone, as well as locations to the north of the previously drilled area. Gold mineralization was intersected by several holes. Results include:

- 2.03 g/t Au over 6.1 m and 0.74 g/t Au over 13.7 m in PGS275.
- 0.94 g/t Au over 15.2 m and 0.83 g/t Au over 6.1 m in PGS282.
    - g/t Au over 12.2 m and 0.75 g/t Au over 9.1 m and 0.31 g/t Au over 9.1 m in PGS286.
    - g/t Au over 13.7 m and 0.74 g/t Au over 10.7 m in PGS253.
- 1.16 g/t Au over 25.9 m including 3.48 g/t Au over 4.6 m in PGS255.
- 0.58 g/t Au over 6.1 m and 0.51 g/t Au over 7.6 m in PGS264.
- 0.79 g/t Au over 29.0 m including 1.97 g/t Au over 4.6 m in PGS265.
- 0.39 g/t Au over 19.8 m and 0.53 g/t Au over 6.1 m in PGS268.
- 0.53 g/t Au over 10.7 m in PGS273.
- 1.78 g/t Au over 67.1 m including 3.14 g/t Au over 32.0 m in PGS277.

Drilling showed relatively limited potential for expansion of the target, and distance from other zones and limited oxidation of the mineralized material limit potential for economic extraction.

10.2.8 Other Targets

In late 2017, several outlying targets were drill tested. Locations are shown on Figure 10-1, with historical names. All drill holes targeted the Claron unconformity as well as the potential for mineralization hosted in the middle Pakoon Sandstone (Pps)/Lower Pakoon Dolomite (Ppdl) contact and along potentially mineralized structures.

10.2.8.1 The Beach

The Beach (Deep Bogart) target is located 450 m northwest of the Covington Pit. Historical drilling identified gold, but geology had been misinterpreted and made targeting difficult. In addition, the presence of the Queantoweap Sandstone (Pcq) underlying the Claron unconformity in many of the historical holes made this a less compelling target. Re-logging of historical holes and better understanding the faults and geology led to some significant drill intercepts in 2017. Liberty Gold drilled a total of 21 RC holes in 2017. Gold mineralization was intersected locally, including:

- 0.44 g/t Au over 45.7 m including 0.81 g/t Au over 18.8 m in PGS296.

- 0.92 g/t Au over 19.8 m including 1.50 g/t Au over 10.7 m in PGS364.
- 0.40 g/t Au over 15.2 m in PGS395.

10.2.8.2 Big Red

The Big Red target area is located approximately 1.5 km northwest of the Moosehead Pit on the north side of Beaverdam Wash. Historical drilling at Big Red primarily targeted jasperoids at the Pakoon Lower Dolomite/Calville Limestone contact, with variable success. Up to 6.0 g/t Au in single drill samples was achieved in historical drilling, although intercepts were relatively short. Geologic modelling of this area was hampered by a lack of precise locations for historical drill collars. Liberty Gold drilled six widely spaced holes late in 2017 to test the Claron unconformity, the Pps/Ppdl contact, and adjacent high-angle faults. Results include:

- 0.41 g/t Au over 6.1 m in PGS468
- 0.42 g/t Au over 6.1 m in PGS470
- 0.75 g/t Au over 1.5 m in PGS472

10.2.8.3 Fenceline

The Fenceline (Deep Bogart) target is located approximately 1.7 km northwest of the Beavertail Pit on the north side of Beaverdam Wash, along the westward projection of faults associated with mineralization in the historical mine trend. Very shallow, poorly located historical drill holes tested jasperoids at the Pps/Ppdl and Ppdl/Pc contacts that crop out on surface, with indications of a few metres of gold mineralization at surface. Re-mapping the area and surface sampling, including a 4.5 g/t Au soil sample and 17.8 g/t Au in a rock sample, helped to better understand and target this area. One hole was drilled by Liberty testing the Pps/Ppdl contact at depth that intersected 1.46 g/t Au over 24 m. It returned:

- 2.25 g/t Au over 13.7 m within 1.46 g/t Au over 24.4 m in PGS473.

10.2.8.4 Jack's Camp and Jedediah Targets

The Jacks Camp (Antimony Shafts) and Jedediah targets are located approximately 1.8 km and 3.0 km south-southwest of the Beavertail Pit, respectively. In both areas, argillic to intermediate argillic altered feldspar porphyritic andesitic to dacitic rocks are faulted against Paleozoic rocks. The igneous rocks have either a volcanic or high-level intrusive origin. Gold is associated with intermediate argillic alteration, silicification and rare dark gray quartz veining in both the igneous rocks and wall rocks.

At Jack's Camp, several historical drill pads have been located, however, Liberty Gold is not in possession of any data for them. Liberty Gold drilled three RC holes in this area, with the best results possibly related to a fault zone: 0.78 g/t Au over 12.2 m in PGS466.

At Jedediah, historical drilling comprises 14 poorly located holes, with the best gold results in quartz rich dacitic rocks. Liberty Gold drilled one hole in 2017, which recovered minor gold associated with a fault zone near a contact with basement Paleozoic rocks. This hole returned:

- 0.23 g/t Au over 4.6 m in PGS467.

10.3 SLR Comments

The Goldstrike Project drill hole database comprises a total of 2,375 holes for 217,394 m drilled by 11 companies including Liberty Gold, from 1978 through 2022. Most of the historical holes

drilled are vertical RC/rotary holes, whereas a majority of Liberty Gold holes are angled holes. Most holes are RC or rotary (2,294 RC/rotary holes for 210,254 m), with limited core drilling (58 core holes for 6,338 m) and sonic drilling, the latter testing the historical heap-leach pad (23 sonic holes for 802 m).

- The core holes in the database account for approximately 2% of the drilling.
- The sonic holes in the database account for approximately 1% of the drilling.

The downhole lengths of the drill samples in the Project database average 1.57 m, with 99% of the sample intervals having a length of 1.524 m (5 ft).

SLR is not aware of the details regarding the drilling contractors, drilling methods, sampling procedures, collar-survey methods, and types of drill rigs utilized in the historical Goldstrike drilling programs other than those summarized above in Section 10.1 and Section 10.2.

Because of the age of some of the drilling and lack of data or conflicting hardcopy data, the drill hole database was constantly refined by Liberty Gold. It is possible that Heliostar will add additional historical drill holes to the database or locations will be found for missing holes as the Project progresses. For example, there are gaps in the Tenneco hole numbering, and historical documents suggest that some of these holes were drilled, but backup data has yet to be found. The type of hole is also not explicitly documented in many of the historical holes; these are reasonably assumed to be RC holes, but it is possible that some are conventional rotary holes. The drill hole database as presented in this report has an effective date of March 23, 2026.

The overwhelming majority of the historical holes at Goldstrike have been drilled at vertical to sub-vertical angles, which cut the generally shallow-dipping mineralization that dominates the gold deposits at high angles. There are some holes that are poorly oriented with respect to the mineralization encountered, especially in cases of vertically oriented holes intersecting mineralization controlled by high-angle structures within the Paleozoic strata, or by favourable units in the Paleozoic that are steeply dipping. In these cases, gold intersections can have downhole lengths that exaggerate true thickness. The thickness of mineralization is variable, and the sample lengths are appropriate for the style of mineralization at Goldstrike.

The SLR QP does not consider the lack of downhole survey data to be a significant issue as nearly 80% of the historical holes are vertical and relatively short, with only 3% drilled deeper than 125 m.

Heliostar's Goldstrike Project drill hole database includes assay data for 1,391 holes drilled by historical operators, totaling 87,175 m (Table 10-1), and 984 holes for 130,218 m drilled by Liberty Gold in 2015 through 2022 (Table 10-2). The average length of historical holes is 63.6 m, whereas the average length of Liberty Gold drill holes is 156.7 m. Drill hole locations are shown in Figure 10-1. There are hole locations for an additional 20 historical holes that are not shown on Table 10-1 because no assay data have been found (three Pegasus, two Permian, fourteen Tenneco, and one USMX holes).

11.0 Sample Preparation, Analyses, and Security

11.1 Historical Drilling Programs

This section summarizes available historical drilling programs sample preparation, analysis, and security information for the period from 1978 through 2012.

- 1978: Occidental Minerals
  - Occidental Minerals' RC drilling samples were assayed for gold, with results posted to the handwritten drill logs. There is no information on drilling, sampling, and analytical procedures.
- 1980 to 1981: Houston International
  - For RC drilling by Houston International, samples were collected at 5 ft (1.524 m) intervals and split to "about a five pound size" according to reports by Schaubs (1981) and Callaway and Gates (1981). SLR has no information on how the samples were split, or whether they were collected wet or dry. The RC samples were assayed for gold and silver at Bondar-Clegg of Denver, Colorado. Results were reported in ppm, and the assay methods are not known.
- 1982 to 1987: Permian
  - No information is available for Permian's sampling and analytical methods used for their rotary(?) or RC(?) drilling. Samples were assayed for gold in 1982 to 1985, and the laboratory and methods are not available.
- 1985 to 1986: Inspiration
  - Inspiration's rock-chip and drill samples were analyzed at Inspiration's Talco laboratory in Safford, Arizona, at Hunter Mining Laboratory, Inc. in Sparks, Nevada (Hunter), and in 1986 at Rocky Mountain Geochemical Corp. in Sparks, Nevada (Rocky Mountain). SLR has no information on the RC and core sampling procedures. At Inspiration's laboratory, gold was determined by fire assay, and no further information is available. Hunter used fire assay with atomic absorption (AA) finish for gold analyses. Some samples were assayed for silver and arsenic, and SLR has no information on the methods used. Inspiration's samples sent to Rocky Mountain were assayed for gold and silver by fire assay, and arsenic was determined by colorimetric analyses, and no further information is available.
- 1988 to 1989: Goldsil
  - Goldsil's RC samples were collected on 5 ft (1.524 m) intervals in a cyclone and split in a Jones slitter (Schurman 1987), and SLR has no information on whether the samples were collected wet or dry. Goldsil's samples were assayed by Iron King Assay Inc., of Humboldt, Arizona, for gold and silver by fire assay with AA finish. No other information is available.
- 1988 to 1989: Pegasus
  - Pegasus' RC samples were collected on 5 ft (1.524 m) in the Mineral West Area.
- 1987 to 1992: Tenneco
  - For Tenneco's RC and/or rotary drilling, SLR has no information on the drill sampling procedures, or whether the samples were collected wet or dry. The drill cuttings were

analyzed at Rocky Mountain's laboratory in West Jordan, Utah. Gold and silver were analyzed using a "one-ton fire assay", and no further information is available. Also in 1991, selected samples were analyzed for gold by a cyanide-leach method at Metallurgy Testing and Research Associates, the location of which is no longer known.

- 1993 to 1994: USMX
  - USMX's drill cuttings were analyzed at Rocky Mountain in West Jordan, Utah. SLR has no information on the sampling procedures used, or whether the samples were collected wet or dry. Gold and silver were analyzed using a "one-ton fire assay", and there is no further information on the assay methods. Some of USMX's samples were analyzed for cyanide-soluble gold at Rocky Mountain by AA. In 1993, six samples from DH93GG-17 were analyzed at Rocky Mountain for Cu, Pb, Zn, Mo, As, Sb, Hg, Bi, and Te by AA. A few samples were analyzed for tin at Cone Geochemical Inc. (Cone), in Lakewood, Colorado.
- 1997: North Mining
  - The North Mining HQ and NQ core logs recorded lithology, structure, alteration and mineralization, and core recovery. The core was photographed and sampled on 3.5 ft (1.067 m) to 5 ft (1.524 m) intervals. Drill core samples were analyzed for gold by fire assay with AA finish. Silver, As, Bi, Cu, Mo, Hg, Pb, Sb, and Zn were determined by inductively coupled plasma (ICP) following an aqua regia digestion. Liberty Gold infers the North Mining samples were possibly analyzed at Barringer Laboratories, Inc., in either Reno, Nevada, or Denver, Colorado. There is no evidence that QA/QC samples were inserted into the sample stream.
- 1999: Bull Valley
  - Bull Valley's RC drilling samples were taken over 20 ft (6.1 m) lengths, and SLR has no further information on sampling procedures, or whether the samples were collected wet or dry. The samples were submitted to Cone for determination of Au, Ag, As, Sb, and Hg. Gold was determined by 30 g fire assay with AA finish. Silver was determined by four acid digestion and an "AA/BC" method that is presumed to be a type of AA method.
- 2004: Midway
  - SLR has no information on the drill rig or contractor for Midway's RC drilling. According to Puchlik (2010): "The Midway drill sampling involved taking splits of each 5 ft (1.524 m) intervals. Samples were collected at each drill site and put into shipping bags that were sealed. These bags were transported to a secure facility until delivered to American Assay Laboratory for analysis by FA30."
- 2011 to 2012: Cadillac
  - Samples were collected on 5 ft (1.524 m) intervals. Cadillac's core samples were transported to a ranch located on the Property. The core samples were halved using a core saw, with one half sent to the laboratory for analysis and the other half retained in the original box. Core samples were assayed for gold by 30 g fire assay with AA finish at ALS Minerals, a division of ALS Ltd. (together ALS) in North Vancouver, British Columbia, following sample preparation at ALS in Reno, Nevada. Pulps were resubmitted for silver assays by a combined ICP and mass spectrometry (MS) method.

11.1.1 Historical Surface Sampling

SLR is unaware of the sample preparation and analytical methods used for the historical surface samples, most of which are attributed to Tenneco.

11.1.2 Liberty Gold Surface Samples

11.1.2.1 Liberty Gold Soil Samples

Rangefront collected soil samples using handheld GPS units with pre-programmed sample locations. Samples generally ranged in weight from 0.3 kg to 0.8 kg. Samples were transported by Rangefront directly to ALS's sample preparation facility in Elko, Nevada, where they were transported to Winnemucca for preparation. Samples were screened to -180 µm. The less than 180 µm fractions were analyzed for gold by 30 g fire assay with AA finish (ALS method code Au-AA23) and 51 elements by ICP-MS following aqua regia digestion (ALS method code ME-MS41).

11.1.2.2 Liberty Gold Rock Samples

Rock samples were collected by Liberty Gold personnel and transported to the ALS sample preparation facility in Elko, Nevada. Sample weights were generally between 1 kg and 2 kg. Data recorded at the sample site include handheld GPS locations, type of sample (grab, chip), rock type, and alteration. Samples were crushed to 70% passing 2 mm mesh, split, and pulverized to 85% passing 75 µm mesh. Gold was determined by 30 g fire assay with AA finish (ALS code Au-AA23). Fifty-one elements were determined by ICP-MS following aqua regia digestion (ALS method code ME-MS41).

11.1.3 Liberty Gold Drill Samples

11.1.3.1 Liberty Gold Core Drilling

Liberty Gold geologists were on site during the Liberty Gold drilling programs; they carried out geological logging of drill core and defined the core sample intervals to correspond to lithologic breaks. Drill core was collected at the drill sites by Liberty Gold personnel. The core was logged on site in or adjacent to a trailer designated for that purpose, using a purpose-built Excel template that records rock type, alteration, rock quality designation (RQD), and other parameters.

All drill core was sampled except for some backfill and pad-fill material, as well as the upper portions of holes drilled from the same drill pad where mineralization was not expected. Sampled intervals were identified based on geological considerations. Sample lengths vary from approximately 0.24 m to 5.8 m, with an average length of 1.5 m. After logging, the core was transported to Liberty Gold's core processing and storage facility in Elko by Liberty Gold staff. Personnel from Rangefront photographed the core wet and dry, then cut the core lengthwise into halves, then sawed one half into quarters using diamond saws. One quarter sample was sent to the assay laboratory, with the remaining three-quarters core retained for metallurgical testing. All samples were transported by ALS personnel from the Liberty Gold cutting facility to the ALS sample preparation laboratory in Elko, Nevada. After sample preparation, sample pulps were sent from the ALS Elko laboratory to the ALS laboratory in Reno, Nevada, for analysis of gold by fire assay, and to the ALS laboratory in North Vancouver, British Columbia, for multi-element geochemical analyses.

11.1.3.2 Liberty Gold RC Drilling

Liberty Gold's RC samples were collected wet, with water injection, on 5 ft (1.524 m) intervals, each sample generally weighing in the range of approximately 5 kg to 10 kg, directly into pre-labelled, water-permeable cloth sample bags. Excess water was drained from the samples at the drill sites. The drill samples were transported periodically to the ALS facility in Elko, Nevada, by Liberty Gold personnel, or by contractor Feller Enterprises of St. George, Utah, or by Legarza Exploration of Elko, Nevada. At times during the program, it was deemed necessary by ALS to transport samples from Elko to an alternate preparation laboratory, either in Reno, Nevada; Vancouver, British Columbia; Thunder Bay, Ontario; or Hermosillo, Mexico. After sample preparation, sample pulps were sent to the ALS laboratory in Reno, Nevada, for analysis of gold by fire assay, and to the ALS laboratory in North Vancouver, British Columbia, for multi-element geochemical analyses.

11.1.3.3 Liberty Gold Sonic Drilling

In 2022, in order to better define the remaining mineralization in the heap-leach pads and waste dumps, Liberty Gold contracted with Boart Longyear to drill 23 holes totalling 802 m. Eleven holes were drilled into the upper heap-leach pad,10 holes were drilled into the lower heap-leach pad, one hole was drilled into the waste dump below the lower heap-leach pad, and one hole was drilled into the Hamburg Pit backfill. Drilling was conducted using a LS600 Sonic Rig with a 6 in. sample diameter. Drill output from the rig typically consisted of a 2.5 ft (0.76 m) sample run with the material captured in a plastic bag labelled with a sample number and depth. This bagged sample was sent down from the drill platform along a slide and laid out in order in an area adjacent to the drill rig. These samples were then transported by a Liberty Gold geologist or Liberty Gold contractor to a sample splitting area where they were first weighed to determine an approximate density. Two, 2.5 ft samples were then split in half with a trowel and combined into two composite samples, each five feet (1.52 m) in length. A small amount of material was added to a plastic chip tray for later geological logging. One five foot sample split was then sent to ALS laboratories for a full assay and the other was kept on site for use in metallurgical testing.

All samples were transported by Liberty Gold personnel from the site to the ALS sample preparation laboratory in Elko, Nevada. After sample preparation, sample pulps were sent from the ALS Elko laboratory to the ALS laboratory in Reno, Nevada, for analysis of gold by fire assay, and to the ALS laboratory in North Vancouver, British Columbia, for multi-element geochemical analyses.

11.1.3.4 Sample Preparation and Assay Procedures

Liberty Gold employed a blind numbering system for both core and RC samples, such that the hole number and downhole footage were not known to the assay laboratory. ALS was the primary assay laboratory for Liberty Gold.

ALS is a large, multinational laboratory analytical services company that is independent of Liberty Gold. Most ALS geochemistry laboratories, including the preparation and assay facilities in Elko and Reno, Nevada, and North Vancouver, British Columbia, are registered or are pending registration to ISO 9001:2008, and a number of analytical facilities have received ISO 17025 accreditations for specific laboratory procedures.

After drying and weighing, the samples were crushed to 70% at less than 2 mm particle size. The crushed material was riffle-split to obtain a 250 g sub-sample that was ring-mill pulverized to 85% at less than 75 µm. The pulps were analyzed for gold by 30 g fire assay with AA finish

(ALS method code Au-AA23) at the ALS laboratory in Reno, Nevada. Pulps returning a fire assay of >0.10 g/t Au were also analyzed for cyanide-soluble gold by cyanide leach and AA analyses, wherein a sample of pulp is agitated for one hour in a 0.25% NaCN solution (ALS method code Au-AA13), also in the ALS Reno laboratory. Samples returning a fire assay of >5.0 g/t Au were re-assayed and completed with a gravimetric finish. For these samples, the gravimetric data were utilized in any further calculations.

Metallic screen techniques were employed in the rare instances where the presence of coarse free gold was suspected. In this process, approximately 1,000 g of coarse reject material is pulverized and screened. Two splits of the fine fraction are assayed, as well as all material that does not pass through the screen (the coarse fraction). The final gold assay reported is a weighted average of the coarse and fine fractions.

Silver, Cu, Pb, Zn, Ba, Al, As, B, Be, Bi, Ca, Cd, Ce, Co, Cr, Cs, Fe, Ga, Ge, Hf, Hg, In, K, La, Li, Mg, Mn, Mo, Na, Nb, Ni, P, Rb, Re, S, Sb, Sc, Se, Sn, Sr, Ta, Te, Th, Ti, Tl, U, V, W, Y, and Zr were analyzed by ICP-MS after aqua regia digestion (ALS method code ME-MS41) at the ALS laboratory in North Vancouver, British Columbia, using 1.0 g sub-samples of the pulps.

QA/QC procedures used by historical operators and Liberty Gold are described in Section 11.3 .

In the SLR QP's opinion, the sampling preparation, security and analytical procedures used by Liberty Gold are consistent with generally accepted industry best practices and are therefore adequate.

11.2 Specific Gravity Data

ALS completed 697 bulk specific-gravity (SG) determinations for Liberty Gold. The measurements were made on selected samples of one-half cut PQ core (mineralized and some unmineralized) from 2016, 2018, and 2022 and HQ core from 2012 and 1989, recovered from the Main Zone, Peg Leg-Cov Zone, the Moosehead Zone and Beavertail zones. Locations of drill holes used to collect specific gravity samples are illustrated in Section 13. Samples were selected to reflect the range of ore types and degrees of oxidation in the areas tested by large diameter core holes for metallurgical testing.

The method employed was water immersion on wax-dipped samples (ALS code OA-GRA08n). SG values ranged from a low of 1.56 to a high of 2.82, with an average value of 2.49.

There was no external QA/QC carried out on these samples.

11.3 Quality Assurance and Quality Control Programs

11.3.1 Historical Drilling Programs

This section summarizes available historical drilling programs' QA/QC, sample preparation, analysis, and security information for the period from 1978 through 2012. Various duplicate check analyses were completed by Inspiration and Tenneco, which together drilled 80% of the holes in the Project database. Additional QA/QC samples are reported by Puchlik (2010) for the 2004 Midway drilling program, and Cadillac reportedly inserted blanks into the sample stream from their 2011 to 2012 drilling campaign.

- 1978: Occidental Minerals:
    - There is no QA/QC information for Occidental Minerals' RC drilling samples preparation, analyses, and security for gold.

- 1980 to 1981: Houston International
  - No information for the RC drill samples collected by Houston International, and if any gold and silver QA/QC samples were employed during assaying.
- 1982 to 1987: Permian
  - For Permian's 1982 to 1985 rotary(?) or RC(?) drill samples, there is no information on whether gold QA/QC assay samples were inserted or analyzed.
- 1985 to 1986: Inspiration (see Section 11.3.1.1)
  - The only QA/QC data known from the Inspiration drilling programs pertains to Rocky Mountain Laboratory 1986 gold, silver, and arsenic analyses, consisting of duplicates of unknown origin and third-party check assays of original pulps.
- 1988 to 1989: Goldsil
  - There is no QA/QC information available for the Iron King laboratory gold and silver assay of Goldsil's RC samples.
- 1989 to 1990: Pegasus
  - There is no QA/QC information available.
- 1987 to 1992: Tenneco (see Section 11.3.1.2).
  - For Tenneco's RC and/or rotary drilling samples, check gold and silver assaying was reportedly completed on 1988 to 1990 Rocky Mountain laboratory duplicates of uncertain origin. Similar check analyses were completed on 1991 duplicates.
- 1993 to 1994: USMX
  - It is unknown whether any QA/QC samples were utilized during gold and silver assay of USMX's drill cuttings by Rocky Mountain laboratory.
- 1997: North Mining
  - There is no evidence that QA/QC samples were inserted into the Barringer Laboratories Au, Ag, As, Bi, Cu, Mo, Hg, Pb, Sb, and Zn assay of North Mining's core samples.
- 1999: Bull Valley
  - Certain Bull Valley RC drilling sample intervals were re-sampled and sent to Chemex Labs, Inc. (now ALS) in Sparks, Nevada, for gold determination by fire assay with AA finish.
- 2004: Midway (see Section 11.3.1.3)
  - For the Midway RC drilling samples, Puchlik (2010) stated: "Gold standards along with splits of selected 5 ft (1.524 m) intervals were randomly inserted in the sample number sequence as external checks of assay results."
- 2011 to 2012: Cadillac (see Section 11.3.1.4)
  - For assay of Cadillac's core samples for gold and silver at ALS, Cadillac inserted blank samples, but no standards or duplicate samples.

SLR was informed about the historical information for the period from 1978 through 2012 as described above; however, no evaluation of the data from this period was conducted by SLR. Of

the 200,182 metres of drilling supporting the Mineral Resource estimate, 75,863 m (38 %) of core and RC holes were historical and 124,319 m (62 %) of core, RC, and sonic holes were drilled by Liberty Gold.

11.3.1.1 Inspiration

A total of 288 duplicate pairs were compiled from Hunter assay certificates from 1986 that include samples from holes 86-25 through 86-122. The duplicates are identified on the certificates by asterisks, with the duplicates listed immediately following the original (primary) samples. The total number of samples provided on the header of the certificates includes the duplicates, and all of the samples in aggregate are referred to as cuttings. Based on this information, it is likely that the duplicates represent field duplicates (analyses of duplicate samples collected at the drill rig along with the primary samples).

Figure 11-1 illustrates the relative percent difference (y-axis) between each Hunter duplicate and its corresponding primary sample, providing an assessment of analytical precision.

The x-axis of the graph plots the means of the gold values of the paired data in a sequential, non-linear fashion. The red line shows the moving average of the relative differences of the pairs and provides a visual guide to trends in the data, which aids in the identification of bias. Positive relative difference values indicate that the duplicate sample analysis is greater than the primary sample assay.

The relative differences are calculated as follows:

$$\frac{(duplicate\ -\ original)}{lesser\ of\ (duplicate, original)}$$

A total of 217 pairs in which both the original and duplicate analyses are less than the detection limit (0.0343 g/t Au (0.001 oz/ton)) are removed from the graph in Figure 11-1, as are four extreme outlier pairs; two of the extreme pairs removed have means of the pairs that exceed 0.1 g/t Au.

The means of the original Hunter analyses (0.703 g/t Au) and the duplicate analyses (0.700 g/t Au) are very close for all of the data and remain very close at mean-of-the-pairs (MOP) cut-offs of 0.2 g/t, 0.5 g/t, and 1.0 g/t Au. No consistent bias is evident. The variability of the data, as indicated by the average of the absolute values of the relative differences, is 10% at a MOP cut-off of 0.2 g/t Au, decreasing to 6% at a 1.0 g/t Au cut-off.

Figure 11-1: Hunter Assays of Duplicates Relative to Original Hunter Analyses



Source: Liberty Gold 2018.

Inspiration also requested Hunter to send 65 original pulps from samples from 12 holes drilled in 1986 to Talco, Inspiration's in-house laboratory that was located in Safford, Arizona. The Talco check assays are compared to the original Hunter analyses in Figure 11-2; three extreme outlier pairs are excluded. The detection limit for the Talco analyses is assumed to be 0.17143 g/t (0.005 oz/t) Au. The certificates list "trace" but do not define what value it refers to. The lowest value assayed is 0.005 oz/t so it can be assumed that anything below that was listed as "trace".

The Talco check analyses are systematically higher than the original Hunter analyses. This bias is highest at the lowest grades (MOPs less than approximately 0.15 g/t Au) and gradually decreases through to a MOP of approximately 1.5 g/t Au, where the Talco assays are approximately 3% higher than the original Hunter analyses. Independent of this bias, the variability in the paired data is surprisingly high for pulp-check analyses, up to a MOP of approximately 1.5 g/t Au but is at a more expected level of approximately 5% at higher grades.

It should be noted that the dataset compared in Figure 11-2 does not represent the actual grade distribution of the Goldstrike mineralization, as it is biased towards relatively well-mineralized samples (the average grade of the pairs for the entire dataset is 2 g/t Au). A sample selection bias such as this could result in the check assays being low relative to the original analyses, especially if there is a nugget effect (which is generally not the case at Goldstrike), but the opposite relationship is seen in this duplicate dataset.

Figure 11-2: Talco Check Assays Relative to Original Hunter Analyses



Source: Liberty Gold 2018.

11.3.1.2 Tenneco

Cone assayed Tenneco drill-sample duplicates from 70 holes drilled in 1988 through 1990 that were originally analyzed by Rocky Mountain; the type of duplicate is not known. The duplicate dataset consists of 97 pairs, excluding four pairs whereby both analyses in the pair are less than the detection limit (Figure 11-3). The detection limit for Rocky Mountain was 0.17143 g/t (0.005 oz/t) Au in 1986 and was 0.0343 g/t (0.001 oz/t) Au in 1988. The detection limit for the Cone lab analyses was 0.171 ppm (0.005 oz/t).

The mean of the duplicate analyses (1.114 g/t Au) is 4% lower than the mean of the original analyses (1.155 g/t Au), and these means indicate that the dataset is biased somewhat to the high side of the full grade distribution of the Goldstrike mineralization, which has a mean of approximately 0.7 g/t Au. The means of the duplicate analyses remain approximately 4% lower than the original assays at MOP cut-offs of 0.2 g/t, 0.5 g/t, and 1.0 g/t Au, but no consistent bias is seen in the data. As indicated by the average value of the absolute values of the relative differences, variability is approximately 45% at an MOP cut-off of 0.2 g/t Au, dropping to 25% at an MOP of 0.5 g/t Au.

Figure 11-3: Cone Assays of Duplicates Relative to Original Rocky Mountain Analyses



Source: Liberty Gold 2018.

In late 1991, Tenneco sent Rocky Mountain 133 duplicate samples from 28 holes drilled earlier in the year. The samples, which were originally assayed by Rocky Mountain, were typically selected at 50 ft (15.24 m) intervals in each hole. The samples are described as cuttings on the certificate, which means they were most likely RC field duplicates, although they could have been preparation duplicates (pulps derived from splits of the coarsely crushed materials that remain after the primary splits were taken).

The duplicate analyses are compared to the original assays in Figure 11-4. A total of 72 pairs in which assays that returned less than detection limits are excluded, as are nine outlier pairs (only two of which have an MOP greater than 0.1 g/t Au).

Figure 11-4: Rocky Mountain Assays of Cuttings Duplicates Relative to Original Rocky Mountain Analyses



Source: Liberty Gold 2018.

The mean of the duplicate analyses is identical to the mean of the original assays (0.717 g/t Au), and the means remain very close at various cut-offs. While the duplicate analyses are biased high at low grades, this is attributed to the low number of duplicate pairs analyzed and expected scatter at values near the detection limit. The detection limits of the RMGC analyses were between 0.0343 g/t (0.001 oz/t) and 0.17143 g/t (0.005 oz/t) Au depending on the year. The bias disappears at pertinent grades (MOP grades above approximately 0.2 g/t Au). Variability at and above this cut-off is approximately 20%.

11.3.1.3 Midway

According to Puchlik (2010), Midway selected samples for check assaying, as well as a large number of duplicate samples, from random drill samples from their eight-hole 2004 drilling program at Mineral Mountain. Mineral Mountain is no longer part of the Liberty Gold Goldstrike Project and this information is included for reference. Puchlik (2010) reported average variations of 23% for the check assays and 22% for the duplicate analyses, and stated this variability could be due to internal variation in the gold, poor sample splitting, or poor assay preparation.

Puchlik (2010) further reported that assay results from hole MM-04-1 were analyzed by both American Assay (the primary laboratory) and ALS. The results are reported to show an average difference of 29%, with ALS values almost always being higher than the American Assay analyses. It was concluded that this discrepancy is an important consideration for future drilling and sample handling.

Finally, Puchlik (2010) stated that standards were inserted into the drill-sample stream during the course of the drilling program, although the results of the analyses of the standards are not discussed.

11.3.1.4 Cadillac

Cadillac inserted blank samples into their 2011 to 2012 drill-sample streams and apparently completed no other QA/QC analyses.

11.3.2 Liberty Gold Quality Assurance/Quality Control Program

11.3.2.1 QA/QC Program Method

The QA/QC program instituted by Liberty Gold for the Goldstrike 2015 to 2022 drilling programs included the systematic analysis of standards, coarse blanks, and RC field duplicates. Preparation duplicates and analytical duplicates (or replicates) were also routinely analyzed by ALS as part of their in-house QA/QC program. The Liberty Gold QA/QC program was designed to ensure that at least one of each standard, blank, and field duplicate was inserted into the drill-sample stream for every 36 drill samples, which is the number of samples in each ALS analytical batch. Splits from ALS pulps in mineralized zones were sent to Inspectorate Laboratories in two batches after each drill program for check assaying.

11.3.2.2 Certified Reference Material (CRM)/ Standards

Certified standards were used to evaluate the analytical accuracy and precision of the ALS analyses during the time the drill samples were analyzed. The twenty certified standards used at Goldstrike include nine custom standards prepared by Minerals Exploration and Environmental Geochemistry (MEG) of Carson City, Nevada, ten sourced from Rocklabs, of Auckland, New Zealand, and one from CDN Resource Laboratories (CDN) of Langley, British Columbia (Table 11-1). The standard designated with the prefix “FG” was produced from coarse-reject material obtained from RC drill samples from Fronteer Gold drilling at the Long Canyon gold deposit. Pilot Gold (now Liberty Gold) was a spin-off from Fronteer Gold after it was purchased by Newmont Corporation in 2011. Standards designated with “PG” were custom prepared from material sourced from Pilot Gold drill samples from its Kinsley Gold Project and standards with the prefix “LG” were prepared from carbonate material from Liberty Gold’s Black Pine Project. Long Canyon and Kinsley are sedimentary rock-hosted gold deposits in eastern Nevada and Black Pine is a sedimentary rock-hosted gold deposit in southern Idaho, with similar metallurgical characteristics to Goldstrike.

Table 11-1: Liberty Gold Certificate Standards

Standard ID	Standard Source	Certified Value (g/t Au)	Standard Deviation (g/t Au)	No. of ALS Standard Analyses	No. of Failures	Bias (%)
Au19.09	MEG	0.711	0.032	6	0	3.07
Au19.10	MEG	0.81	0.036	24	1	2.82
CDN-GS-P6A	CDN	0.738	0.028	205	11	-0.41
FGS2011A	MEG custom	7.089	0.373	10	0	-3.3
LG19001	MEG custom	0.698	0.027	56	0	-1.76

Standard ID	Standard Source	Certified Value (g/t Au)	Standard Deviation (g/t Au)	No. of ALS Standard Analyses	No. of Failures	Bias (%)
LG21.01	MEG custom	0.408	0.014	69	2	0.55
LG21.02	MEG custom	1.097	0.042	80	0	-0.39
OxA71	Rocklabs	0.085	0.006	20	0	-2.82
OxD57	Rocklabs	0.413	0.012	19	0	-0.5
OxD87	Rocklabs	0.417	0.013	26	2	1.45
OxF65	Rocklabs	0.805	0.034	57	0	-0.37
OxF85	Rocklabs	0.805	0.025	63	0	-0.68
Oxi54	Rocklabs	1.868	0.066	15	0	0.89
OxJ68	Rocklabs	2.342	0.064	35	0	0.76
PG13001X	MEG custom	1.873	0.075	329	1	-3.22
PG13002X	MEG custom	2.188	0.087	155	5	-1.63
PG14001X	MEG custom	0.328	0.017	529	3	-1.83
SE58	Rocklabs	0.607	0.019	51	4	-2.56
SG40	Rocklabs	0.976	0.022	61	2	-0.98
Si54	Rocklabs	1.78	0.034	14	0	1.48

The standards were pre-assigned sample numbers in sequence with their accompanying drill samples prior to sampling the RC holes and then inserted into the drill-sample stream. In cases where the rocks were likely to be unmineralized (either by taking note of unfavourable rock type or lack of alteration), no standard was inserted. Where possible, the standards were selected for insertion to try to match the expected gold values of the accompanying drill samples.

In the case of normally distributed data, 95% of the standard analyses are expected to lie within the two standard-deviation (2SD) limits of the certified value, while only 0.3% of the analyses are expected to lie outside of the three standard-deviation (3SD) limits. Note, however, that most assay datasets from metal deposits are positively skewed.

All samples outside of the 3SD limits were considered as failures. As it is statistically unlikely that two consecutive analyses of standards would lie between the 2SD and 3SD limits, such samples would also be considered failures unless further investigations suggest otherwise. Failures trigger investigation, possible laboratory notification of potential problems, and a possible re-run of all samples included with the failed standard result. With respect to failures identified in this sample set, if the failed standards were within a mineralized zone (defined by a sequence of samples with >0.15 g/t Au assays), a re-run was requested. If the failed standards lay within an unmineralized zone, no action was taken other than notifying the laboratory of the failure. A re-run consists of a re-assay of the standard along with 20 samples above and below the standard. All standards identified for re-assay passed the second time.

As defined above, the ALS analyses of the twenty standards yielded 31 failures out of 1,824 (Figure 11-5 to Figure 11-24) standard analyses, or approximately 1.7%, an acceptable rate of failure. Systematic low or high biases in the laboratory analyses relative to the expected value of the standard can lead to failures as defined above but are more properly characterized as bias. For example, in the chart of standard PG14001X, the mean of all values is 0.320 g/t Au,

compared to a certified value of 0.328 g/t Au, a difference of 2.4%. While a number of samples lie below the 3SD limits and therefore could be considered as ‘failures’, it is evident that the ALS analyses are biased low with respect to the certified standard value. It is this low bias, not excessive variability, which may be the cause of many of the ‘failures’.

A high outlier was identified in the CRM OXD87 dataset, significantly impacting bias and performance assessment. To ensure accurate analysis, this sample was removed to prevent data distortion.

Liberty Gold initially used a standard deviation (SD) of 0.056 for CRM CDN-GS-P6A. However, CDN provides recommended values and the ‘between-lab’ 2SD. The data were re-processed using 1SD (0.028) for consistency. SLR recommends using 1SD in all analyses for reliable results.

A small number of samples assayed much lower than expected. In these cases, the laboratory was notified, and the cause of the abnormally low assay value was investigated. In these cases, the laboratory identified issues such as sample swaps or spillage of the sample. These issues are a concern, as they might otherwise go unnoticed in the general sample stream.

Figure 11-5: Chart of Standard Performance for Goldstrike Standard Au19.09



Source: Liberty Gold 2025.

Figure 11-6: Chart of Standard Performance for Goldstrike Standard Au19.10



Source: Liberty Gold 2025.

Figure 11-7: Chart of Standard Performance for Goldstrike Standard CDN-GS-P6A



Source: Liberty Gold 2025.

Figure 11-8: Chart of Standard Performance for Goldstrike Standard FGS2011A



Source: Liberty Gold 2025.

Figure 11-9: Chart of Standard Performance for Goldstrike Standard LG21.01



Source: Liberty Gold 2025.

Figure 11-10: Chart of Standard Performance for Goldstrike Standard LG21.02



Source: Liberty Gold 2025.

Figure 11-11: Chart of Standard Performance for Goldstrike Standard LG19001



Source: Liberty Gold 2025.

Figure 11-12: Chart of Standard Performance for Goldstrike Standard OxA71



Source: Liberty Gold 2025.

Figure 11-13: Chart of Standard Performance for Goldstrike Standard OxD57



Source: Liberty Gold 2025.

Figure 11-14: Chart of Standard Performance for Goldstrike Standard OxD87



Source: Liberty Gold 2025.

Figure 11-15: Chart of Standard Performance for Goldstrike Standard OxF65



Source: Liberty Gold 2025.

Figure 11-16: Chart of Standard Performance for Goldstrike Standard OxF85



Source: Liberty Gold 2025.

Figure 11-17: Chart of Standard Performance for Goldstrike Standard OxJ68



Source: Liberty Gold 2025.

Figure 11-18: Chart of Standard Performance for Goldstrike Standard Oxi54



Source: Liberty Gold 2025.

Figure 11-19: Chart of Standard Performance for Goldstrike Standard PG13001X



Source: Liberty Gold 2025.

Figure 11-20: Chart of Standard Performance for Goldstrike Standard PG13002X



Source: Liberty Gold 2025.

Figure 11-21: Chart of Standard Performance for Goldstrike Standard PG14001X



Source: Liberty Gold 2025.

Figure 11-22: Chart of Standard Performance for Goldstrike Standard SE58



Source: Liberty Gold 2025.

Figure 11-23: Chart of Standard Performance for Goldstrike Standard SG40



Source: Liberty Gold 2025.

Figure 11-24: Chart of Standard Performance for Goldstrike Standard Si54



Source: Liberty Gold 2025.

11.3.2.3 Liberty Gold Coarse Blanks

Coarse blanks are samples of barren material that are used to detect possible contamination, which is most common during sample preparation stages. In order for analyses of blanks to be

meaningful, they must be sufficiently coarse to require the same crushing and pulverizing stages as the drill samples. It is also important for blanks to be placed in the sample stream within a series of mineralized samples, which would be the source of most contamination issues (in practice, this is much easier to accomplish with core samples than RC). Blank results that are greater than 5X the lower detection limit are typically considered failures that require further investigation and possible re-assaying of associated drill samples. The detection limit of the ALS fire assay is 0.002 g/t Au, so blank samples assaying in excess of 0.01 g/t Au would be considered failures under the 5X rule. However, a failure threshold of 0.025 g/t Au was adopted, as the difference between 0.01 g/t Au and 0.025 g/t Au, relative to the average grade of the deposit, is not material, and because ALS uses 0.005 g/t Au as the detection limit in many of their internal QA/QC documents.

In 2015, Liberty Gold used coarse blank material from a bulk sample of “carbonate” blank material consisting of coarse crushed cinder-block material that was provided as certified blank material by MEG. Starting in 2016, the blanks were sourced from Vigoro brand “pond pebbles”. These blanks were coarse enough to require primary and secondary crushing, in order to monitor the entire sample-preparation process experienced by the drill samples. Blanks were inserted approximately every 36 samples. The blanks were pre-assigned sample numbers in sequence with their accompanying drill samples prior to sampling the RC holes and then inserted into the drill-sample stream. In cases where the rocks were likely unmineralized (either by taking note of unfavourable rock type or lack of alteration), no blank was inserted. Where possible, the blanks were selected for insertion to try to correspond with intervals with elevated gold values.

Between 2015 and the end of 2022, a total of 1,954 coarse blank analyses were obtained from the drilling program. Of these, four of the ALS analyses of the blanks exceeded the failure threshold of 25 ppb Au (Figure 11-25). Of the eleven highest assay results, nine were inserted in intervals returning multi-gram gold intercepts. This performance well exceeds that guaranteed by ALS (<1% contamination).

Figure 11-25: 2015 to 2022 Blank Performance, Goldstrike Drill Program



Source: Liberty Gold 2025.

11.3.2.4 Liberty Gold Field Duplicates

Field duplicates are secondary splits of drill samples. Field duplicates are mainly used to assess inherent geologic variability and sub-sampling variance. The field duplicate samples were submitted to ALS at the same time as their associated original drill samples.

In the case of Liberty Gold's core drilling, field duplicates consisted of quarter-core splits, with the paired originals also being quarter-core splits (all other primary samples were half-core splits). The RC field duplicates were splits of the cuttings collected at the drill rig at the same time as the primary samples. The outlet on the cyclone was set up with a "Y" splitter and, for the field duplicate, a second bucket was added to the secondary outlet of the "Y", so that two samples were collected for the interval. The field duplicates were collected randomly in the case of RC drilling, which resulted in a large number of duplicates of unmineralized intervals.

A total of 2,035 RC duplicates and 53 core duplicates were collected by Liberty Gold and analyzed by ALS. The RC and core duplicate data are presented in Figure 11-26 as a plot of the percent difference in gold grade between the pairs. Pairs with a mean value below 10 ppb, as well as four extreme outliers, possibly due to sample swaps or coarse gold, were removed from the dataset, leaving 940 pairs. With the remaining pairs, the percent difference ranges from a low of 90.3% to a high of 300.0%. Most duplicate pairs are within 20% of the mean, an acceptable level of difference. When the outlier 16 g/t Au pair is removed from the dataset, the mean of all original samples is 0.278 g/t Au, while the mean of all duplicate pairs is 0.287 g/t Au, a difference of 3.24%.

Figure 11-26: Liberty Gold Field Duplicate Data



Source: Liberty Gold 2025.

11.3.2.5 Liberty Gold Preparation Duplicates

Preparation duplicates are analyses of pulps derived from second splits of the coarsely ground material that remained after the primary split was taken. These duplicates can therefore be used to evaluate the variability introduced by sub-sampling of the coarsely crushed material. ALS routinely creates and analyzes preparation duplicates as part of their internal QA/QC protocols, so Liberty Gold requested and tracked these results through 2017.

A relative difference graph that plots the preparation duplicate data from the 2015 to 2022 drilling program is shown in Figure 11-27; all pairs in which one or both analyses are equal to or

less than 10 ppb Au have been removed, for a total of 479 remaining samples. Because these duplicates provide information relative to the variability introduced after coarse crushing of the drill samples, both core, RC and surface rock sample data are shown together. Within this sample set, the percent difference between the original and duplicate samples ranges from a low of -89.7% to a high of 154.5%, with the highest variability generally seen in samples close to the detection limit. As a whole, both the duplicate and original sample sets average 0.262 g/t Au, and most sample pairs lie within 10% of the mean.

Figure 11-27: 2015 – 2022 Liberty Gold Preparation Duplicate Data



Source: Liberty Gold 2025.

11.3.2.6 Liberty Gold Analytical Duplicates

Analytical duplicates (or replicates) are second analyses of the original pulps that are usually performed routinely by the primary analytical laboratory. These duplicates can be used to evaluate the precision of the sub-sampling of the pulp, and of the analysis itself. ALS completes analytical duplicates as part to their internal QA/QC routine, and Liberty Gold received these analyses on the drill hole sample assay certificates.

A relative difference graph that plots the preparation duplicate data from the 2015 to 2022 drilling program is shown in Figure 11-28; all pairs in which mean is equal to or less than 10 ppb Au, or for which one or both analyses are above the >10 g/t Au over-limit, or for which there was insufficient sample for the duplicate analysis, have been removed, for a total of 2,449 samples in the dataset. Because these duplicates provide information relative to the variability introduced after coarse crushing of the drill samples, both core and RC data are shown together. Within this sample set, the percent difference between the original and duplicate samples ranges from a low of -96.2% to a high of 166.7%, with the highest variability generally seen in samples close to the detection limit. As a whole, both the duplicate and original sample sets average 0.410 g/t Au, and most sample pairs lie within 10% of the mean. Most sample pairs with a mean greater

than 0.1 g/t Au returned a percent difference less than 5%, suggesting that the samples are well homogenized, and the analytical precision is high.

Figure 11-28: 2015 – 2025 Liberty Gold Analytical Duplicate Data



Source: Liberty Gold 2025.

11.3.2.7 Liberty Gold Check Assaying

As a further check on analytical accuracy, Liberty Gold selected a portion of the original sample pulps from the 2015 to 2022 drill programs and sent these to Inspectorate/Bureau Veritas (BV) Laboratories for re-assaying of gold content by fire assay with AA finish. Inspectorate/BV is an ISO 17025 accredited, independent laboratory located in Sparks, Nevada. The procedure for selection of check assays consisted of querying all samples that returned greater than 130 ppb Au and less than 5,000 ppb Au and assigning these a random number. The selection was then sorted on the random number and approximately 7% of these were selected for re-assay, for a total of 1,304 samples. The original ALS pulps were used for the check assays. Standards and blanks were also submitted to Inspectorate/BV along with the ALS pulps. A similar analytical method was used at Inspectorate/BV for the gold check analyses. These check analyses are compared to the original ALS assays in Figure 11-29. The dataset as a whole shows an excellent correlation between primary and check assays, with a difference of +0.82% between Inspectorate/BV and ALS (Inspectorate/BV numbers are slightly higher than ALS numbers).

However, the dataset as a whole obscures a significant difference between results from 2015 and 2016 sampling relative to ALS primary assays and subsequent check assays. The 2015 to 2016 check assaying, carried out in early 2017, returned a significant negative bias in BV check assaying, with samples returning assays an average of 9.08% lower than ALS assays. In contrast, check assaying of 2017 samples, carried out in January/February 2018, returned an average 1.42% higher in BV check assaying compared to the original ALS assay results. This

trend can be clearly seen in Figure 11-30, with percent difference/ALS assay results (same scale) plotted against sample number, with 1-204 representing 2015 to 2016 samples and 205-511 representing 2017 samples. A number of samples in the 2015 to 2016 BV sample set skewed very low relative to ALS assays, whereas there is closer agreement in the 2017 samples. There were no standard failures with either batch. The source of this discrepancy in unknown at this time. Given that ALS procedures have remained constant through the three-year period of assaying described above, and in subsequent years, the BV check assays from the first batch of samples are regarded as suspect.

Check assaying in subsequent years does not show a significant bias. Large discrepancies in individual assay pairs are mainly restricted to samples with lower concentrations of gold.

Figure 11-29: Comparison of ALS Primary and BV Check Assays



Source: Liberty Gold 2025.

Figure 11-30: Percent Difference Graph of BV Check Assays versus ALS Assays



Source: Liberty Gold 2025.

11.3.2.8 QA/QC Discussion, Liberty Gold

Liberty Gold QA/QC Historical Programs

It is difficult to assess the adequacy of historical sampling, sample preparation, and assaying due to a lack of sufficient QA/QC data. However, some QA/QC analyses were completed by Inspiration, Tenneco, Midway, and Cadillac. Inspiration, Tenneco, and USMX drilled 93% of the holes in the historical Project database, and all were well-recognized and reputable mining companies at the time (1980s and early 1990s).

The 1986 Inspiration duplicate analyses by Hunter show good agreement with the original Hunter assays, and variability is not high considering the duplicates were likely field duplicates. However, the check analyses completed by Talco are systematically higher than the original Hunter assays. Given that Talco was an in-house Inspiration laboratory of uncertain reliability, especially with respect to gold assaying, while Hunter was a well-known and widely used commercial laboratory at the time, Liberty Gold believes it cannot be concluded that the Hunter analyses are biased low.

The mean of cone analyses of the 1988 to 1990 Tenneco duplicates of unknown origin (likely field or preparation duplicates) is approximately 4% lower than the mean of the original Rocky Mountain analyses, although no consistent bias is seen in the dataset and the average grade of the data is high relative to the mean grade of the Goldstrike mineralization. Variability is approximately 45% at an MOP cut-off of 0.2 g/t Au and approximately 25% at a MOP cut-off of 0.5 g/t Au. The variability at the lower cut-off is not surprising for field duplicates but could be somewhat high if the duplicate samples were preparation duplicates.

Tenneco also requested Rocky Mountain to complete duplicate analyses of samples of cuttings from the 1991 drilling program that were originally analyzed by Rocky Mountain (again, the duplicates were likely either field or preparation duplicates). The means of the duplicate and original analyses are very close, no bias is evident at pertinent grades (MOP grades above approximately 0.2 g/t Au), and the variability is acceptable for either field or preparation duplicates (approximately 20%).

Liberty Gold did not evaluate the blank samples analyses Cadillac inserted into their 2011 to 2012 drill-sample streams.

Liberty Gold concluded that the historical QA/QC data, while limited, do not identify any significant issues.

Liberty Gold QA/QC Programs – Drilling Samples

Liberty Gold did not identify any significant issues from their drilling program's QA/QC samples.

Liberty Gold's certified-standard results show systematic low biases (ALS analyses lower than expected values) for several standards. With few exceptions, the ALS analyses are within the 2SD limits defined by the certified standards. Liberty Gold does not believe the biases are significant, especially in consideration of the limited data used to arrive at the expected values of the custom standards. If the individual analyses of a standard for each of the laboratories that participated in the certification process are compared to the actual expected value, most of the certifying laboratories will have high or low biases of varying magnitudes relative to the expected value.

The Inspectorate/BV check assays of the 2015 to 2022 drilling programs appear to have a low bias relative to the original ALS analyses.

11.3.2.9 SLR Conclusions and Recommendations

Historical Surface Sampling

SLR is unaware of QA/QC employed for sample preparation, analytical methods, and security of historical surface samples, most of which are attributed to Tenneco.

SLR is aware that for the soil samples collected by Rangefront and assayed at ALS for gold by fire assay and other elements by ICP-MS, no QA/QC samples were inserted.

SLR is aware that for the rock samples collected by Liberty Gold and assayed at ALS no QA/QC samples were inserted.

Liberty Gold QA/QC Programs - Drilling

SLR reviewed and analyzed blanks, duplicates, CRMs, and check assays conducted by Liberty Gold for the Goldstrike Project between 2015 and 2022. The results confirmed Liberty Gold's QA/QC assessments, and the SLR QP has provided the following additional observations and recommendations:

- CRMs performed within acceptable limits, with a bias of less than 5% and control limits set at ±3SD from expected values. However, SLR recommends reducing the number of CRM types to three or four (high-grade, medium/high-grade, medium-grade, and low-grade). This adjustment is sufficient to monitor laboratory performance and detect potential biases or systematic errors over time.
- No significant contamination was identified during sample preparation.

- Duplicate analyses at ALS demonstrated acceptable precision levels.
- External check assays showed good reproducibility of gold values between the primary laboratories, ALS, and Inspectorate/BV.
- During the initial QA/QC review, numerous outliers were identified in CRMs and blanks, showing significant deviations from expected values. Some discrepancies were attributed to mislabelling between CRMs and blanks or among different CRM types. These discrepancies were reported to Liberty Gold, which conducted data verification and cross-checked the results using multi-element geochemistry. The affected samples were then re-assigned to their correct CRM or blank groups and updated in the database. The QP recommends reviewing and reinforcing procedures to ensure sampling protocols are strictly followed, minimizing mislabelling errors.
- There are only 20 CRM samples (OxA71) that test grade below 0.3 g/t Au. Future work should focus on confirming the 0.1 to 0.3 g/t Au grade range.

The SLR QP concludes that the QA/QC program implemented at Goldstrike is adequate. The assay data within the database are suitable for use in Mineral Resource estimation and comply with industry standards.

12.0 Data Verification

12.1 Verifications by Liberty Gold – Drill Hole Database

12.1.1 Drill Hole Database Auditing

Liberty Gold inherited a Project drill hole database and hardcopy documentation as part of its acquisition of the Goldstrike property. Liberty Gold subsequently undertook extensive efforts to digitize, validate, and improve the accuracy of the Project data. Following Liberty Gold's verification and resultant updating of the database, Mine Development Associates (MDA) completed a verification, as summarized below, of the historical data for a NI 43-101 Technical Report (Gustin and Smith, 2016).

12.1.2 Collar and Survey Tables

The locations of many of the historical drill holes at Goldstrike are uncertain. Most of the drill holes in the mined pit areas were originally surveyed by traditional methods using a local grid referenced to a surveyed section corner. Due to mining disturbance, these holes can no longer be found and re-surveyed. Other drill hole collars, particularly for holes drilled at various exploration targets that were not mined, are shown on sketch maps but do not match exactly with their locations in the database. It is also difficult to find and verify the locations of these holes due to disturbance and post-mining reclamation.

Liberty Gold contracted All Points North Surveying and Mapping of Elko, Nevada to locate and accurately survey the section corner that served as the origin for the local grid used to locate holes drilled prior to 2000. The local grid coordinates of these holes were then converted to UTM NAD83 coordinates, and the drill hole collars were overlain on a satellite image and shifted to nearby drill sites where appropriate. The elevations of some hole collars that were clearly in error were pressed onto an accurate terrain model. While this work corrected many problems, a number of hole locations were still suspect, and Liberty Gold attempted to locate these in the field and survey them using a Trimble Geo Explorer XH GPS receiver with differential correction accuracy of 0.5 m in the X and Y directions and 1.0 m in the Z direction. Other location problems were corrected by researching historical documentation that showed the inherited database coordinates were inaccurate.

MDA, as part of the 2016 Technical Report (Gustin and Smith 2016), reviewed the drill collar locations relative to drill pads and roads as shown on the satellite imagery and has worked with the drill hole data in detail on cross-sections. During the cross-sectional work, several holes were identified that seemed to be out of place due to incongruous gold assays and/or geologic codes as compared to adjacent holes. In these cases, Liberty Gold researched available historical documentation at MDA's request and, in most cases, the holes were found to have inaccurate database coordinates or orientations (azimuth and/or dip). While some location errors no doubt survive the verification efforts of Liberty Gold, SLR believes the materiality of these errors is mitigated by the large number of holes drilled and the overwhelming number of these holes that show geologic and analytical coherence, as well as locations that are well supported.

As noted in Section 10.1, there are no downhole survey data in the Project database for any of the historical holes, and MDA (Gustin and Smith 2016) found no such surveys in the historical documentation. MDA used available historical documentation, primarily handwritten geologic logs, to audit the drill-collar azimuths and dips of 35% of the historical holes in the Project database. Twenty of the audited holes were found to have database azimuth and/or dip values

that were in conflict with the historical documentation. Liberty Gold was provided with the list of discrepancies, at which point all of the historical azimuth and dip data in the collars table were cross-checked against hardcopy historical drill summary tables and the historical drill logs. Where discrepancies were found, an effort was made to determine which is the correct value, either by further validation, or an examination of which value would be the most reasonable from a geologic standpoint.

12.1.3 Assay Table

ALS was chosen as Liberty Gold's primary laboratory based on a rigorous 2008 audit by consultant Barry Smee of all Nevada assay laboratory facilities. The audit was performed for Fronteer Gold, predecessor to Liberty Gold.

Liberty Gold compiled all available historical assay certificates and used them to comprehensively check the gold values in the Project database. This effort resulted in the auditing of assays from 853 holes drilled by Tenneco, 127 by Inspiration, and 133 by USMX. Over 70% of the historical sample intervals in the Project database were thereby checked by Liberty Gold and corrected where appropriate. Liberty Gold found an error rate in the database gold values of less than 1%, not including various discrepancies relating to the treatment of less-than-detection-limit results and unassayed intervals.

MDA (Gustin and Smith 2016) completed an audit of the updated Liberty Gold assay table using the same historical assay certificates and found an error rate of 0.2%. MDA re-checked a total of 171 of the 1,113 holes audited by Liberty Gold. More than half of the limited discrepancies found by MDA were from a continuous 45 ft (13.7 m) interval in a single hole, and the apparent errors could therefore be due to re-assaying of this sample interval. Liberty Gold's efforts with respect to verifying and correcting the Goldstrike assay database were effective.

To audit the assay data from Liberty Gold's 2015 drilling program, MDA obtained original digital assay certificates directly from ALS. The original ALS data were compiled into a single spreadsheet and compared against the results provided to MDA by Liberty Gold. All Liberty Gold 2015 sample intervals were thereby verified by MDA (Gustin and Smith 2016).

12.2 Verifications by GL Simmons Consulting, LLC

Mr. Simmons visited the Goldstrike Project site on February 15, 2017, May 18, 2018, and May 16, 2022. The primary purpose of Mr. Simmons most recent site visit on May 16, 2022 was to plan ongoing metallurgical programs, examine ore and waste in the field and in core, and the layout of the historical mines and pits.

Mr. Simmons directly supervised the planning of the metallurgical programs and generation of all the metallurgical data. The historical USMX 1993 Kappes, Cassiday and Associates (KCA) and Liberty Gold 2016 – 2014 KCA metallurgical test program data was reviewed by Mr. Simmons, and is deemed acceptable for gold extraction modelling for the Goldstrike Project.

12.3 Verifications by SLR

12.3.1 SLR Site Verification Procedures

Lorraine Tam, P.Geo., the SLR QP, visited the Property on March 5, 2025. The site visit included inspections of the historical open-pit faces, the locations of the waste dumps, backfill dumps, historical heap-leach pads, and the locations of chip samples taken from the Antimony Ridge area.

No drilling or other exploration work was taking place at the time of the site visit. There has not been any drilling on the Property since 2022. Discussions were held with Liberty Gold Senior Resource Geologist, April Barrios, regarding the geological interpretation and sampling procedures during Liberty Gold's 2015 to 2022 drill programs. Because there has not been any active drilling since 2022 and there is no infrastructure on site, all core was moved to Liberty Gold's Black Pine Project in Idaho. The SLR QP did not view any of the drill core.

12.3.1.1 Confirmation of Drill Hole Locations

The SLR QP confirmed the location of several of the Liberty Gold drill hole collar locations. The completed holes were marked using a metal tag as shown in Figure 12-1. The locations were verified using the "GPS Tracks" application on an iPhone 11. In total, seven collar locations were verified and were compared with the drill hole database ("Actual") coordinates (Table 12-1). Considering the accuracy of the iPhone GPS, the QP is of the opinion that the drill hole collars measured are properly located.

As noted in 12.1.2, the locations of the historical drill collars are unknown due to mining activity and reclamation work. Attempts were made to locate drill hole collars from Liberty Gold's pre-2019 drill programs but were unsuccessful. The QP notes that ground disturbance was visible and there was evidence of possible drilling; however, reclamation work has covered the collars and/or removed the metal tags identifying the collars.

Figure 12-1: Liberty Gold Drill Hole Collar Location (PGS741)

Source: SLR 2025.

Table 12-1: Verification of Drill Hole Collar Locations During Site Visit

Drill Hole ID	Easting (m)	Northing (m)	Elevation (m)	Actual Easting (m)	Actual Northing (m)	Actual Elevation (m)	Easting Difference (m)	Northing Difference (m)	Elevation Difference (m)
PGS907	244,011	4,142,048	1,445	244,012	4,142,048	1,440	1	1	-5
PGS840	244,073	4,142,003	1,468	244,072	4,141,999	1,465	-1	-4	-3
PGS839	244,074	4,141,998	1,468	244,074	4,141,997	1,466	0	-1	-2
PGS838	244,068	4,141,997	1,469	244,069	4,141,994	1,466	1	-3	-3
PGS743	241,415	4,139,339	1,513	241,414	4,139,336	1,512	-1	-3	-1
PGS741	241,439	4,139,423	1,510	241,437	4,139,420	1,510	-2	-3	0
PGS721	244,072	4,142,219	1,411	244,064	4,142,222	1,405	-8	3	-6

12.3.2 Database Validation

SLR conducted cross-checks between the Goldstrike assay database (PGS_Assays.csv) and the original ALS assay certificates up to the cut-off date of November 2022. The database contains a total of 81,702 samples; however, 2,231 samples do not have recorded gold or silver assay values.

SLR compared the entire database, verifying data from 979 drill holes and 938 assay certificates covering the years 2015 to 2022. No discrepancies were identified in gold or silver values between the database and the assay certificates.

The SLR QP concludes that the database verification procedures for the Goldstrike Project comply with industry standards and are adequate for Mineral Resource estimation.

13.0 Mineral Processing and Metallurgical Testing

The prior Goldstrike NI 43-101 report, which reported the original and re-stated Mineral Resource estimates (SRK 2018A and B), provides a comprehensive evaluation of the mineral processing and metallurgical testing aspects of the Project. This work is summarized herein.

13.1 Historical Metallurgical Testing

Historical metallurgical sampling and testing (pre-Liberty Gold) extends back to the 1980s, though meaningful results are limited. Parsley (1994) reported that in 1993, USMX retained KCA to carry out cyanide-soluble assaying and column-leach testing on material from the Beavertail (BEV) and Moosehead (MOS) deposits (USMX 1993). Material for two columns was crushed to 100% passing 4 in. (10.2 cm). The columns utilized 708 kg of material from BEV and 805 kg of material from MOS. The material from BEV averaged 0.079 oz/ton Au (2.71 ppm Au) and that from MOS averaged 0.032 oz/ton Au (1.10 ppm Au). The column tests were carried out on a portion of each sample over a total of 61 days. Gold recovery was reported to be 78% for the MOS sample and 80% for the BEV sample.

13.2 Phase 1 - Liberty Gold Metallurgical Test Program

A Phase 1 bottle roll and column leach metallurgical program was commissioned by Liberty Gold in mid-2016 with work being conducted by KCA in Sparks, Nevada (KCA 2027). The scope of work covered by KCA included:

- Sample preparation
- Head assays and geochemical analysis
- Comminution characterization, comprising SMC Testing Pty Ltd (SMC) test work, as well as Bond abrasion index test work that was sub-contracted to Hazen Research Inc. in Golden, Colorado
- 10 mesh and 200 mesh bottle roll tests
- Column leach testing at 80% passing (P_{80}) 12.5 mm and 25.0 mm
- Tails screen analysis and assay by size fraction
- Load permeability testing (LPT)
- Environmental characterization

13.2.1 Phase 1 Sample Selection

Metallurgical core samples were selected from ten PQ diamond core holes drilled in early 2016 from the Main Zone, in the eastern portion of the historical mine trend of mineralization (Figure 13-1).

Figure 13-1: Phase 1 - Goldstrike Project Metallurgical Core Plan Map



A total of 24 variability composites were selected based upon the following geo-metallurgy criteria:

- Gold/Silver head grade
- Cyanide solubility (AuCN %)
- Lithology
- Alteration assemblages
- Rock geochemistry

Information related to Formation, Subunit, Au Final, AuCN %, and Ag Final assay was extracted from the Goldstrike Project geology database and these were the primary geo-metallurgical parameters used for composite selection and makeup.

Six variability composites were made up of intervals taken from two or three adjacent drill holes with similar Formation, Subunit, and Lithology characterization.

Metallurgical sampling and testing was limited to the Main Zone of mineralization. Composites from the Moosehead, Caribou, Covington, Peg Leg, and Padre areas were not tested in Phase 1.

13.2.2 Phase 1 - Head Assays

Gold and silver head assays were conducted by KCA (KCA, 2017). Cyanide solubility (AuCN), preg-robbing assays, carbon and sulphur speciation, and ICP analysis were conducted by ALS.

- Gold grade ranged from 0.247 ppm to 3.175 ppm.
- Silver grade ranged from 2.3 ppm to 58.9 ppm.
- Copper values were very low, ranging from 3 ppm to 34 ppm.
- Cyanide soluble gold content ranged from 38% to 102%.
- Cyanide soluble silver content ranged from 12% to 65%.
- AuCN % assays correlated with sulphide sulphur assays, with higher sulphide sulphur ($S^{=}$) content correlating to lower AuCN %.
- Organic carbon values were low and ranged from 0.05% to 0.09%. Preg-robbing analysis indicated two of the composites to be mildly preg-robbing.
- Sulphide sulphur ranged from <0.01% to 1.65 %, and five of the 23 composites contained values >0.30% sulphide sulphur.

From multi-element ICP geochemical analysis:

- Arsenic (As) levels were low, ranging from 86 ppm to 552 ppm.
- Mercury (Hg) levels were low, ranging from 0.06 ppm to 0.50 ppm.
- Concentrations of primary cyanide consumers (Cu, Ni, and Zn) were low, suggesting minimal potential to effect cyanide consumption rates.
- Whole rock analysis was conducted on all composites:
- Silica (SiO_2) levels were high, ranging from 61.9% to 92.8%, but do not appear to have a material effect on cyanide solubility or gold extraction.

- Clay levels were low to moderate except for three composites that exhibited elevated Al_2O_3 content.
- Calcium levels were low to moderate with four composites containing Ca >5.0%.

13.2.3 Comminution Characterization (Hazen)

Ten samples were selected for comminution test work from drill holes where enough material was available and where the material represented major gold host rock types. Samples were subjected to the modified Semi-Autogenous grinding (SAG) Mill Comminution (SMC) drop weight test procedure to generate data for SAG mill, crushing, and high-pressure grinding roll (HPGR) comminution evaluation by JK Tech and abrasion index (Ai) testing at Hazen Research, Inc. (Hazen 2016) in Golden, Colorado. A comminution test work summary is provided in Table 13-1.

Table 13-1: Goldstrike Phase Comminution Testing

KCA Sample No.	Description	SG	A	b	A x b	DW_i (kWh/m^3)	DW_i (%)	M_{ia} (kWh/t)	M_{ih} (kWh/t)	M_{ic} (kWh/t)	t_a	SCSE (kWh/t)
76401 A	GS-01	2.58	52.6	1.92	101.0	2.56	8%	9.4	5.7	3.0	1.01	6.80
76406 A	GS-06	2.62	55.6	0.99	55.0	4.76	27%	15.2	10.5	5.4	0.54	8.50
76407 A	GS-07	2.62	61.1	1.02	62.3	4.20	21%	13.8	9.3	4.8	0.62	8.08
76408 A	GS-08	2.62	58.8	1.21	71.1	3.70	16%	12.5	8.2	4.2	0.70	7.69
76409 A	GS-09	2.58	56.8	1.11	63.0	4.10	20%	13.8	9.2	4.8	0.63	8.03
76411 A	GS-11	2.61	52.8	1.14	60.2	4.32	22%	14.2	9.6	5.0	0.60	8.19
76413 A	GS-13	2.59	59.1	1.07	63.2	4.09	19%	13.7	9.2	4.7	0.63	8.02
76415 A	GS-15	2.62	70.4	0.54	38.0	6.88	55%	20.5	15.2	7.9	0.38	9.97
76417 A	GS-17	2.65	62.9	0.68	42.8	6.16	45%	18.5	13.5	7.0	0.42	9.49
76422 A	GS-22	2.6	58.7	0.88	51.7	5.03	30%	16.1	11.2	5.8	0.52	8.70

Notes:
SG: Specific Gravity
A: Maximum Breakage
b: Relation between energy and impact breakage
A x b: Overall AG-SAG hardness
DW_i: Drop-weight index
M_{ia}: Coarse particle component
M_{ih}: High-pressure grinding roll component
M_{ic}: Crusher component
t_a: Low energy abrasion component of breakage
SCSE: SAG circuit specific energy

13.2.3.1 SAG Mill Comminution Testing

Key comminution parameters tested on the ten composites included:

- A x b is a measure of resistance to impact breakage, and low values indicate hard materials, while high values indicate soft materials. The range of A x b, for the 10 composites, spanned a low of 38.0 to a high of 101.0 and averaged 60.8.

- Drop Weight Index (DW_i, kWh/m^3) values are derived from the A x b results. It is a power input function required to calculate SAG Mill horsepower requirements for these materials being comminuted in a SAG Mill. The DW_i ranged from 2.56 kWh/m^3 to 6.88 kWh/m^3, indicating soft to medium hard material.
- The Goldstrike Project A x b and DW_i values can be categorized as soft to moderate in comparison to the SMC worldwide database values. Although the Goldstrike oxide resource is not envisioned to require a milling circuit, the SAG comminution parameters are a primary component (output) of the SMC test, which also provides crushing energy parameters which are needed to design conventional crushing circuits, such as primary crushers and HPGR.

Other SMC test values that were evaluated include:

- M_{ih}, which is the work index for grinding in HPGR mills. (Not required for Goldstrike unless crushing finer than 12.5 mm is considered.)
- M_{ic}, which is the work index in conventional crushers. Conventional crushing related M_{ic} results range from 3.0 kWh/t to 7.9 kWh/t. Similar to the DW_i results for SAG milling, the conventional crushing power input requirements are considered low to moderate, in the 10% to 50% cumulative range of all samples tested by SMC.

13.2.3.2 Abrasion Index (Ai) Tests

Bond Abrasion Index (Ai) tests were performed at Hazen. A summary is provided in Table 13-2.

Table 13-2: Abrasion Index Test Results

KCA Sample No.	Description	Abrasion Index
76401 A	GS-01	0.2170
76406 A	GS-06	0.4861
76407 A	GS-07	0.5319
76408 A	GS-08	0.4391
76409 A	GS-09	0.1444
76411 A	GS-11	0.6895
76413 A	GS-13	0.4441
76415 A	GS-15	0.7332
76417 A	GS-17	0.5087
76422 A	GS-22	0.5255

The A_i for the 10 composites tested ranged from 0.1444 g to 0.7332 g and averaged 0.472 g, indicating moderate abrasiveness of the tested materials. The A_i results can be used by design engineers to calculate crusher and liner wear rates and corresponding operating cost for installed crushing plant and conveying equipment.

13.2.4 Bottle Roll and Column Leach Testing (KCA)

Bottle roll and column leach characterization test work was performed by KCA (KCA 2017). A summary of gold and silver extractions and reagent consumption is provided in Table 13-3.

Table 13-3: Summary Phase-1 Goldstrike Bottle Roll and Column Leach Test Results

Goldstrike Phase-1							Bottle Roll Tests		Column Tests	
KCA Sample No.	Composite ID	Resource Area	Historical Mine Area	Material Type	Head Assay Au (g/t)	Cyanide Solubility AuCN (%)	200 mesh (75µm)	10 mesh (1.70mm)	12.5mm (1/2 inch)	25mm (1.0 inch)
76401B	GS-1	Main	Basin Pit	oxide	0.490	91.0	88.8	87.5	87.7	
76402A	GS-2	Main	Basin Pit	oxide	0.730	95.5	91.9	88.3	N/A	N/A
76403A	GS-3	Main	Basin Pit	sulfide	0.200	38.1	32.9	38.3	38.0	
76404A	GS-4	Main	Basin Pit	oxide	0.370	99.0	77.8	75.7	81.1	
76405A	GS-5	Main	Basin Pit	trans	0.160	64.8	51.9	52.0	N/A	N/A
76406B	GS-6	Main	Basin Pit	oxide	0.230	76.2	80.4	75.3	77.9	
76407B	GS-7	Main	Basin Pit	oxide	0.320	90.6	90.2	74.7	80.2	
76408B	GS-8	Main	Basin Pit	oxide	0.390	94.0	93.8	85.9		83.3
76409B	GS-9	Main	Basin Pit	oxide	0.640	98.2	95.3	91.2	91.7	
76410A	GS-10	Main	Hamburg Pit	oxide	2.400	84.4	78.3	74.3	77.3	
76411A	GS-11	Main	Hamburg Pit	sulfide	1.080	40.8	35.8	41.2	N/A	N/A
76412A	GS-12	Main	Hamburg Pit	oxide	0.630	77.9	73.3	69.4	75.3	
76413B	GS-13	Main	Hamburg Pit	oxide	1.210	94.6	80.9	73.3		78.8
76414A	GS-14	Main	Hamburg Pit	oxide	0.660	93.4	92.9	83.3	83.6	
76415B	GS-15	Main	Hamburg Pit	oxide	0.470	92.6	91.4	86.1		76.4
76416A	GS-16	Main	Hamburg Pit	trans	0.240	73.7	70.8	63.8	65.3	
76417B	GS-17	Main	Aggie Zone	oxide	0.340	92.7	80.7	74.6	77.6	
76418A	GS-18	Main	Aggie Zone	oxide	1.080	99.7	94.9	91.8	93.6	
76419A	GS-19	Main	Aggie Zone	oxide	2.780	102.5	97.4	94.2		96.5
76429A	GS-20	Main	Aggie Zone	oxide	2.180	96.5	97.5	96.7	97.0	
76421A	GS-21	Main	Aggie Zone	oxide	1.930	98.1	88.7	83.6	84.9	
76422B	GS-22	Main	Aggie Zone	oxide	2.380	98.5	94.2	88.4		92.5
76423A	GS-23	Main	Aggie Zone	oxide	3.190	100.5	93.4	85.5	87.5	
76424A	GS-24	Main	Aggie Zone	oxide	0.300	85.0	90.4	85.6	N/A	N/A

The following is a summary of the methodology, results, and conclusions of the KCA report.

Laboratory scale bottle roll and column leach cyanidation testing was conducted on 24 drill core composites. The main objective for the testing program was to evaluate amenability of the Goldstrike resources to crush or run-of-mine (ROM) heap leaching treatment methods. Direct agitated cyanidation (bottle roll) tests were conducted on all drill core composites at a target particle size of P_{80} 1.7 mm and 75 µm, to determine gold extraction, extraction rate, reagent consumptions, and sensitivity to feed size. Column percolation leach tests were conducted on 20 of the 24 composites, targeting P_{80} feed size of either 12.5 mm or 25.0 mm, to evaluate heap-leach amenability.

Based on column leach and bottle roll tests, 21 of the 24 composites were considered oxide, with AuCN >70%. Of the 20 samples that were column leached, 19 were considered oxide and all were readily amenable to simulated heap-leach cyanidation treatment. Column gold extractions for the 19 composites ranged from 65% to 97% and averaged 83.6% after 81 to 112 days of leaching.

Column test gold extraction rates were rapid, with greater than 80% of the total extractable gold recovered in the first 10 days of leaching. Additional gold was extracted after 10 days, but at a much slower rate.

Oxide column test cyanide (NaCN) consumptions ranged from 0.55 kg/mt to 1.13 kg/mt and averaged 0.85 kg NaCN/mt. KCA and industry experience related to commercial heap-leach NaCN consumption rates indicate that consumption will be considerably lower. *"Based upon KCA's experience with mostly clean non-reactive ores, cyanide consumption in production heaps would be only 25 to 33 percent of the laboratory column test consumptions. For ores containing high amounts of leachable copper, higher factors should be utilized."*

Oxide column test lime consumption ranged from 0.5 kg/t to 3.1 kg/t and averaged 1.3 kg/t.

One sulphide column sample (GS-03) required 1.6 kg/t (4.0 lb/st) of cement addition for agglomeration prior to column loading and leaching.

13.3 Phase 2 - Liberty Gold Metallurgical Test Program

A Phase 2 bottle roll and column leach metallurgical program was commissioned by Liberty Gold in late 2018 with work being conducted by KCA (KCA 2018). The scope of work (SOW) covered 29 variability composites selected from large diameter PQ metallurgical core from the Main, Cariboo, Moosehead, and Beavertail areas. The SOW conducted by KCA included:

- Sample preparation
- Head assays and geochemical analysis
- 10 mesh and 200 mesh bottle roll tests
- Column leach testing at P_{80} 12.5 mm and 25.0 mm
- Tails screen analysis and assay by size fraction
- Environmental characterization

13.3.1 Phase 2 Sample Selection

Metallurgical core samples were selected from 14 PQ diamond core holes drilled in early 2018 from the Main Zone, Moosehead, and Beavertail areas in the south and western portions of the historical mine trend (Figure 13-2, Phase 2 blue dots).

Figure 13-2: Phase 2 - Project Metallurgical Core Map



A total of 30 variability composites were selected based upon the following geo-metallurgy criteria:

- Gold/silver head grade
- Cyanide solubility (AuCN %)
- Lithology
- Alteration assemblages
- Rock geochemistry

Information related to Formation, Subunit, Au Final, AuCN % and Ag Final assay was extracted from the Goldstrike Project geology database and these were the primary geo-metallurgical parameters used for composite selection and makeup.

Four variability composites were made up of intervals taken from two adjacent drill holes with similar Formation and Subunit characterization.

Metallurgical sampling in Phase 2 focused upon historical pit areas (Main, Caribou, Moosehead, and Beavertail).

13.3.2 Phase 2 - Head Assays

Gold and silver head assays were conducted by KCA (KCA 2018). Cyanide solubility (AuCN), preg-robbing assays, carbon and sulphur speciation, and ICP analysis were conducted by ALS.

- Gold grade ranged from 0.214 ppm to 2.048 ppm.
- Silver grade ranged from 0.20 ppm to 1.89 ppm.
- Copper values were very low, ranging from 3 ppm to 10 ppm.
- Cyanide soluble gold content ranged from 81% to 102%.
- Cyanide soluble silver content ranged from 23% to 73%.

With one exception, organic carbon values were low and ranged from 0.03% to 0.28% and averaged 0.17%. There was one outlier at 1.53% (GS-42) but it was not preg-robbing.

Preg-robbing analysis indicated two of the composites to be mildly preg-robbing, GS-37 and GS-45 at 14.7% and 16.7% respectively.

Sulphide sulphur ranged from <0.01% to 0.04%. All composites are considered oxide.

From multi-element ICP geochemical analysis:

- As levels were low, ranging from 82 ppm to 388 ppm.
- Hg levels were low, ranging from 0.03 ppm to 0.97 ppm.
- Concentrations of primary cyanide consumers (Cu, Ni, and Zn) were low, suggesting minimal potential to effect cyanide consumption rates.

Whole rock analysis was conducted on all composites:

- Whole rock silica (SiO_2) levels were moderate, ranging from 23.3% to 93.3%, averaging 63.4%.
- Clay levels were low by considering Al_2O_3 content, which averaged 1.8%.

- Calcium levels were moderate ranging from 0.13% to 29.5%, averaging 11.9%.

13.3.3 Phase 2 - Bottle Roll and Column Leach Testing (KCA)

Bottle roll and column leach characterization test work was performed by KCA in Reno, Nevada (KCA 2018). A summary of gold and silver extractions and reagent consumption is provided in Table 13-4.

Coarse and fine milled bottle-roll leach tests were completed on each of the 29 variability composites. Splits of head samples for each composite were subjected to bottle-roll leach testing at target P_{80} sizes of 75 µm and 1,700 µm, and to column-leach testing at either 12.5 mm (six composites) or 25.0 (24 composites). The main objective of these tests was to evaluate the laboratory-scale leachability character of the Goldstrike resources in terms of gold extraction, extraction rate, reagent consumption, and sensitivity to feed size.

The bottle-roll testing used standard procedures that are described in the final laboratory report (KCA 2018), using 144 hours of retention time for the 1.7 mm tests, and 72 hours for the 75 µm tests.

Column-leach tests were conducted utilizing material crushed to their target P_{80} sizes and placed in columns of 10 cm and 15 cm diameters. During testing the material was leached between 49 to 50 days with a dilute NaCN solution. After leaching, each column was washed/rinsed for four days with water. A portion of the leached and washed column residues from each column was assayed for “tail screen” analyses by size fraction. Note – composite ID# GS-25 was skipped.

Table 13-4: Summary Phase-2 Goldstrike Bottle Roll and Column Leach Test Results

KCA Sample No.	Composite ID	Resource Area	Historical Mine Area	Material Type	Head Assay Au (g/t)	Cyanide Solubility AuCN(%)	Bottle Roll Test		Column Test	
							200 mesh (75µm)	10 mesh (1.70 mm)	12.5mm (1/2 in.)	25mm (1.0 in.)
83702A	GS-26	Main	Dip Slope	oxide	1.247	93.0	90.3	89.9		89.1
83703A	GS-27	Main	Dip Slope	oxide	0.328	94.5	88.8	85.5		87.0
83704A	GS-28	Main	Dip Slope	oxide	0.305	91.8	90.0	75.9	72.9	
83705A	GS-29	Main	Hassayampa	oxide	0.431	81.2	74.7	68.6		66.3
83706A	GS-30	Main	Hassayampa	oxide	0.403	94.3	86.0	79.6	82.1	
83707A	GS-31	Moosehead	Caribou	oxide	0.519	86.7	89.5	84.0		86.0
83708A	GS-32	Moosehead	Caribou	oxide	0.531	92.3	91.6	88.7		91.9
83709A	GS-33	Moosehead	Caribou	oxide	0.240	87.5	84.5	81.9		81.6
83710A	GS-34	Moosehead	Caribou	oxide	1.171	88.8	90.8	90.5	91.7	
83711A	GS-35	Moosehead	Caribou	oxide	0.810	81.5	93.3	89.9		92.2
83712A	GS-36	Moosehead	Caribou	oxide	0.468	96.2	90.8	86.3		88.1
83713A	GS-37	Moosehead	Caribou	oxide	1.854	100.3	94.8	93.3		94.5
83714A	GS-38	Moosehead	Moosehead	oxide	0.800	101.3	91.6	88.5		90.1
83715A	GS-39	Moosehead	Moosehead	oxide	0.851	102.2	93.6	92.9		92.2
83716A	GS-40	Moosehead	Moosehead	oxide	0.457	94.1	90.5	87.3	88.7	
83717A	GS-41	Moosehead	Moosehead	oxide	0.554	90.3	91.9	85.7	84.6	
83718A	GS-42	Moosehead	Moosehead	oxide	0.214	84.1	81.0	80.9		87.9
83719A	GS-43	Moosehead	Moosehead	oxide	1.056	91.9	91.6	85.8	86.0	
83720A	GS-44	Moosehead	Moosehead	oxide	0.630	100.0	94.2	88.1		90.6
83721A	GS-45	Moosehead	Moosehead	oxide	2.048	95.2	95.3	88.8		82.2

KCA Sample No.	Composite ID	Resource Area	Historical Mine Area	Material Type	Head Assay Au (g/t)	Cyanide Solubility AuCN(%)	Bottle Roll Test		Column Test	
							200 mesh (75µm)	10 mesh (1.70 mm)	12.5mm (1/2 in.)	25mm (1.0 in.)
83722A	GS-46	Moosehead	Moosehead	oxide	0.295	94.9	84.0	77.3		83.2
83723A	GS-47	Moosehead	Moosehead	oxide	0.618	85.8	87.4	82.5		81.8
83724A	GS-48	Moosehead	Moosehead	oxide	1.029	99.1	93.1	89.7		91.2
83725A	GS-49	Beavertail	Beavertail	oxide	0.258	93.0	81.5	62.4		72.0
83726A	GS-50	Beavertail	Beavertail	oxide	0.498	90.4	79.6	62.8		65.5
83727A	GS-51	Beavertail	Beavertail	oxide	0.376	90.4	69.5	64.4		67.2
83728A	GS-52	Beavertail	Beavertail	oxide	0.730	86.3	78.8	57.8		53.2
83729A	GS-53	Beavertail	Beavertail	oxide	0.286	87.4	81.4	75.0		78.0
83730A	GS-54	Beavertail	Beavertail	oxide	0.385	90.9	79.9	63.6		46.4

The following is a summary of the bottle roll and column leach test methodology and results from the KCA (2018) report:

- Laboratory scale bottle roll and column leach cyanidation testing was conducted on 29 drill core composites. The main objective for the testing program was to evaluate amenability of the Goldstrike resources to crush or ROM heap leaching treatment methods. Direct agitated cyanidation (bottle roll) tests were conducted on all composites at a target particle size of P_{80} 1.7 mm and 75 µm, to determine gold extraction, extraction rate, reagent requirements, and sensitivity to feed size. Column percolation leach tests were conducted on all 29 composites, targeting P_{80} feed size of either 12.5 mm or 25.0 mm, to evaluate heap-leach amenability.
- All 29 composites are considered oxide, with AuCN >70%.
- Fine grind (75 µm) bottle roll test gold extractions ranged from 74.7% to 95.3%, with a weighted average of 89.7%.
- Coarse bottle roll (1.7 mm) tests gold extractions ranged from 62.4% to 92.9%, with a weighted average of 84.4%.
- Column leach gold extractions at target P_{80} of 12.5 mm (six composites) ranged from 72.9% to 91.7%, with a weighted average of 86.4% at an average head grade of 0.66 ppm Au.
- Column leach gold extractions at target P_{80} of 25 mm (24 composites) ranged from 66.3% to 94.5%, with a weighted average of 84.2% at an average head grade of 0.67 ppm Au.
- Column leach silver extractions for all 30 composites ranged from 5.9% to 51.8%, with a weighted average of 19.6% at an average head grade of 2.25 ppm Ag.
- Column test gold extraction rates were rapid, with greater than 80% of the total extractable gold being recovered in the first 10 days of leaching.
- Column test cyanide (NaCN) consumptions ranged from 0.34 kg/t to 0.74 kg/t and averaged 0.55 kg/t. KCA and industry experience related to commercial heap-leach NaCN consumption rates indicate that consumption will be considerably lower. *“Based upon KCA’s experience with mostly clean non-reactive ores, cyanide consumption in production heaps would be only 25 to 33 percent of the laboratory column test consumptions.”*
- Column test lime consumption ranged from 0.5 kg/t to 2.0 kg/t and averaged 0.96 kg/t.

Five of the column leach composites were agglomerated with 2.0 kg/t cement to prevent column compaction. These five columns did not require any lime for alkalinity control during leaching and are left out of the lime consumption numbers in the above bullet summary.

13.4 Phase 3 - Liberty Gold Metallurgical Test Program

Phase 3 metallurgical testing was a two-part program:

1 Part 1 involved sonic drilling and testing of material from historical Leach Pads 1 and 2, pad under-liner backfill, and two nearby historical mine waste dumps.

2 Part 2 involved testing of 11 backhoe bulk samples excavated in and around historical pits and unmined mineralized surface exposures.

Sonic drill samples were bagged and sent to KCA for sample preparation, geochemical assaying, and Master Composite selection.

The eleven bulk samples were selected from known resource areas with limited previous met core drilling and testing. Bulk samples were crushed to 100% minus 100 mm (4 in.) to represent material for a potential future Crush/Agglomeration flowsheet envisioned for Goldstrike.

Geo-metallurgical characterization assays, bottle roll and column leach testing were commissioned by Liberty Gold in late early 2023 and test work was conducted by KCA (KCA 2023a). The scope of work tested material derived from 22 sonic drill holes and 11 bulk samples. The SOW conducted by KCA included:

- Sample preparation
- Low-grade and high-grade Master Composite selection/makeup from Leach Pad 1 and 2 heap-leach residues.
- Head assays and geochemical analysis
- 10 mesh and 200 mesh bottle roll tests
- Column leach testing at 80% passing 75 mm
- Load Permeability testing
- Tails screen analysis and assay by size fraction
- Environmental characterization

13.4.1 Phase 3 Sample Selection

Phase 3 Sonic Drill and Bulk Sample locations are shown in Figure 13-3.

Twenty-four (24) sonic holes were drilled, including 11 in Leach Pad 1, eleven 11 in Leach Pad 2, and two in nearby historical mine dumps designated Main and Hamburg (green dots in Figure 13-3).

Eleven bulk samples were excavated from existing pits and known mineralized surface locations. Bulk Sample Composite IDs and Zone locations are shown in Table 13-5. Initial bottle roll testing and assaying proved that one of the bulk samples (GS-BS#10) was below the cut-off grade for gold and testing was terminated on this sample.

Table 13-5: Bulk Sample Location Areas

KCA Sample No.	Composite ID	Sample Location	Resource Area
PHASE 3 - Mine Area Backhoe Bulk Sample Testing			
84380 A	GS-BS#1	Moosehead Road	Moosehead
84381 A	GS-BS#2	Moosehead Pit	Moosehead
84382 A	GS-BS#3	Beavertail Road	Beavertail
84383 A	GS-BS#4	Beavertail Pit	Beavertail
84384 A	GS-BS#5	Covington Pit	Peg Leg-Cov
84385 A	GS-BS#6	Peg Leg Road	Peg Leg-Cov

KCA Sample No.	Composite ID	Sample Location	Resource Area
84386 A	GS-BS#7	Hamburg Pit	Main
84387 A	GS-BS#8	Leach Pit	Main
84388 A	GS-BS#9	Dipslope Road	Main
84389 A	GS-BS#10	Dipslope Road	Main
84390 A	GS-BS#11	Dipslope Road	Main
Note: Testing terminated on GS-BS#10 as it is below cut-off for gold.			

Figure 13-3: Phase 3 – Sonic Drill Hole and Bulk Sample Location Map



13.4.2 Phase 3 Head Assays and Sample Makeup

Gold and silver head assays were conducted by KCA (KCA 2023a). Cyanide solubility (AuCN), preg-robbing assays, carbon and sulphur speciation, and ICP analysis were conducted by ALS Chemex.

13.4.2.1 Sonic Drill Assays and Master Composite Make-up

A summary of the Sonic Drilling Master Composite makeup is provided in Table 13-6.

Table 13-6: Sonic Master Composite Assays

						Sonic Physical Characteristics				
Composite ID	**Location**	**Au Final ppm**	**AuCN ppm**	**AuCN %**	**Ag ppm**	**Mass Clay**	**Clay**	**Fines**	**Rock**	**Comments**
SONIC MET COMPOSITES										
SonicPad1_LG-MC#1	Pad 1LG	0.336	0.18	54.6	3.24	18	15	18	49	
SonicPad1_HG-MC#2	Pad 1HG	0.993	0.8	81	5.06	18	20	20	42	
SonicPad2_LG-MC#3	Pad 2LG	0.28	0.15	54.6	5.04	25	18	20	36	
SonicPad2_HG-MC#4	Pad 2HG	0.714	0.45	63.3	7.53	26	16	24	35	
SonicPad(BKFL_LG)-MC#5	Pad 1+2	0.239	0.19	80.8	1.54	8	27	23	42	
SonicPad(BKFL_HG)-MC#6	Pad 2	0.617	0.32	52.1	2.46	8	23	26	32	Blk Carbon(5/18)
Sonic-MainDump #7	Main Waste Dump	0.803	0.59	73.5	2.92	27	20	23	30	
Sonic-Hamburg Dump #8	Hamburg North	0.262	0.21	79.1	1.72	30	9	21	18	

Approximately one-third of the Leach Pad 1 and 2 sonic drill samples were low-grade (<0.20 ppm Au) and are considered waste. The > 0.20 ppm Au samples were separated into two grade ranges: low-grade (Au values between 0.20 ppm and 0.40 ppm) and high-grade (>0.40 ppm Au).

Leach Pad 1 and 2 low-grade and high-grade Master Composites were assembled for metallurgical testing by KCA (KCA 2023a).

Sonic drill samples from two leach-pad backfill areas (MC#5 and MC#6), and two mine waste dump (Main Dump #7 and Hamburg Dump #8) areas were also included in the KCA Phase 3 test program.

13.4.2.2 Bulk Sample Head Assays

The eleven bulk samples were processed using the same flow sheet as Phase 1 and Phase 2 core samples. Sample preparation and Master Composite assembly was handled by KCA. Head assays were performed by KCA and ALS. A summary of select bulk sample head assays are presented in Table 13-7.

Table 13-7: Bulk Sample Head Assays

KCA Sample No.	Composite ID	Resource Area	Head Assays							Preg-rob Analysis*1		
			AuFA ppm	AuCN ppm	AuCN %	AgCN ppm	AgCN %	C(org) %	S(sulfide) %	AA31 w/spike	AA31a w/o spike	AuPR %
84380A	GS-BS#1	Moosehead	0.868	0.880	101.4	1.24	33.2	0.25	<0.01	1.37	0.37	0.0%
84381A	GS-BS#2	Moosehead	0.087	0.080	92.5	0.12	16.4	0.23	<0.01	1.04	0.04	0.0%
84382A	GS-BS#3	Beavertail	0.149	0.130	87.2	0.16	13.3	0.2	<0.01	1.06	0.08	2.0%
84383A	GS-BS#4	Beavertail	1.888	1.875	99.3	1.04	37.1	0.17	<0.01	1.82	0.87	5.0%
84384A	GS-BS#5	Peg Leg-Cov	1.375	1.300	94.5	2.20	48.9	0.04	<0.01	1.59	0.61	2.0%
84385A	GS-BS#6	Peg Leg-Cov	0.608	0.580	95.5	1.24	44.3	0.147	<0.01	1.24	0.26	2.0%
84386A	GS-BS#7	Main Zone	0.504	0.490	97.2	3.00	45.4	0.21	<0.01	1.25	0.26	1.0%
84387A	GS-BS#8	Main Zone	0.132	0.130	98.5	1.36	44.3	0.2	<0.01	1.03	0.05	2.0%
84388A	GS-BS#9	Main Zone	3.290	3.325	101.1	2.72	33.2	0.05	<0.01	2.50	1.55	5.0%
84389A	GS-BS#10	Main Zone	0.031	0.045	145.2	0.08	17.1	0.17	<0.01	1.00	0.01	1.0%
84390A	GS-BS#11	Main Zone	0.127	0.135	106.3	0.06	15.0	0.08	<0.01	1.04	0.06	2.0%
Note.*1 Preg-rob Analysis uses a 1.0 ppm spike												

Bulk Sample #10 (GS-BS#11) proved to be below gold cut-off grade and testing was terminated on this composite.

The following is a summary of key head assay and geo-metallurgical characterization analysis of the bulk samples extracted from the KCA (KCA 2023a) report:

- Gold grade ranged from 0.087 ppm to 3.29 ppm.
- Silver grade ranged from 0.12 ppm to 3.0 ppm.
- Copper values were very low, ranging from 4 ppm to 29 ppm.
- Cyanide soluble gold content ranged from 87% to 106%.
- Cyanide soluble silver content ranged from 13% to 49%.
- Organic carbon values were low and ranged from 0.04% to 0.25%.
- Preg-robbing analysis were low ranging from 0.0 to 5.0%.
- Sulfide sulfur was undetected at <0.01%. All composites are considered oxide.
- From multi-element ICP geochemical analysis:
  - As levels were low, ranging from 59 to 319 ppm.
  - Hg levels were low, ranging from 0.9 to 2.9 ppm.
  - Concentrations of primary cyanide consumers (Cu, Ni, and Zn) were low, suggesting minimal potential to effect cyanide consumption rates.

Whole rock/quantitative XRD (QXRD) analysis was conducted on all composites:

- Whole rock SiO_2 levels were moderate, ranging from 31.9% to 94.4%, averaging 77.8%.
- Clay levels were elevated as measured by QXRD:

- Muscovite ranged from 1.7% to 9.0% and averaged 4.7%
- Swelling clays ranged from 2.8% to 8.6% and averaged 5.3%.
- One bulk sample composite contained kaolin at 1.3%.
- Calcium levels were moderate, ranging from 0.18% to 18.2% and averaging 1.2%.

13.4.3 Phase 3 – Sonic Drill Composites Bottle Roll and Column Leach Testing (KCA)

Bottle roll and column leach test work was performed by KCA (KCA 2023a). A summary of gold and silver extractions and reagent consumption is provided in Table 13-8.

Table 13-8: Summary of Sonic Leach Pad, Pad Backfill and Mine Waste Dump Composites, Bottle Roll and Column Leach Test Results

Sonic Drill Composites		Deposit Zone	Mine Area	Material Type	Head Assay Au	Cyanide Solubility AuCN (%)	Bottle Roll & Column Au Ext %				Reagent Consumption		
KCA Sample No.	Composite ID						200 mesh (75µm)	10 mesh (1.70mm)	25mm (1.0 inch)	75mm (3.0 inch)	NaCN Kg/t	Lime Kg/t	Cement Kg/t
PHASE 3 - Leach Pads 1&2 Sonic & Bulk Sample Testing													
84370 A	SonicPad1_LG-MC#1	LP-1 LG Residue	LP1	oxide	0.331	53.0	57.2	51.2		44.5	0.37	0.0	6.0
84371 A	SonicPad1_HG-MC#2	LP-1 HG Residue	LP1	oxide	1.030	78.2	79.4	75.6		76.0	0.33	2.0	4.0
84372 A	SonicPad2_LG-MC#3	LP-2 LG Residue	LP2	oxide	0.242	62.0	57.1	41.6		28.6	0.3	0.0	5.9
84373 A	SonicPad2_HG-MC#4	LP-2 HG Residue	LP2	oxide	0.590	65.3	68.2	57.2		46.3	0.33	0.0	6.1
PHASE 3 - LP Backfill & Mine Dumps Sonic Bulk Sample Testing													
84374 A	SonicPad(BKFL_LG)-MC#5	LP Backfill		oxide	0.231	82.4	86.4	78.9		81.7	0.53	0.0	8.1
84375 A	SonicPad(BKFL_HG)-MC#6	LP Backfill		oxide	0.524	66.8	73.5	76.6		70.5	0.61	0.0	8.2
84376 A	Sonic-MainDump #7	Main Dump		oxide	0.725	93.1	93.8	91.9	91.2		1.16	4.0	8.1
84377 A	Sonic-HamDump #8	Hamburg Dump		oxide	0.207	75.1	87.1	79.0		71.7	0.29	0.0	8.1

Coarse and fine milled bottle-roll leach tests were completed on each of the eight sonic composites. Splits of head samples for each composite were subjected to bottle-roll leach testing at target P_{80} sizes of 75 µm and 1.7 mm.

Column-leach testing parameters for the sonic composite samples are summarized in Table 13-9.

Table 13-9: Sonic Drill Column Leach Crush Size and Charge Weight Data

KCA Sample No.	Description	Crush size (100% Passing)	Columns Size (mm)		Charge Weight (kg)
			Diameter	Height	
84370A	SonicPad1_LG-MC#1	100 mm	0.30	3.09	327.9
84371A	SonicPad1_HG-MC#2	100 mm	0.30	3.10	313.3
84372A	SonicPad2_LG-MC#3	100 mm	0.30	3.06	317.7
84373A	SonicPad2_HG-MC#4	100 mm	0.30	3.08	317.9
84374A	SonicPad(BKFL_LG)-MC#5	100 mm	0.30	3.12	317.7
84375A	SonicPad(BKFL_HG)-MC#6	100 mm	0.30	3.97	288.6
84376A	Sonic-MainDump #7	37.5 mm	0.15	2.22	57.0
84377A	Sonic-HamDump #8	100 mm	0.30	3.19	312.7

The main objective of the Leach Pad 1 and 2 Sonic Drill composite testing was to evaluate the commercial-scale leachability character of the Leach Pad residues, since no additional crushing is required, in terms of gold extraction, extraction rate, and reagent consumption.

The main objective of the Pad Backfill and Mine Waste Dump Sonic composite testing was to evaluate the commercial-scale leachability character of these materials in terms of gold extraction, extraction rate, reagent consumption, and sensitivity to particle size.

The bottle-roll testing used standard procedures that are described in the final laboratory report (KCA 2023a), using 144 hours of retention time for 1.7 mm tests, and 72 hours for 75 µm tests.

Column-leach tests were conducted utilizing material crushed to 100% passing 100 mm and placed in columns of 150 mm to 250 mm diameters. During testing these composites were leached between 69 to 70 days with a dilute NaCN solution. After leaching, each column was washed/rinsed with water. A portion of the leached and washed residue from each column was assayed for “tail screen” analyses by size fraction and subjected to LPT. LPT parameters and results are shown in Table 13-10.

Table 13-10: Summary of Load Permeability Test Results for Sonic Drill Composites

KCA Sample No.	Description	Crush size (100% Passing)	Col residue Fines	LPT Results	
			%-200M	Pass/Fail	Height
Sonic Samples - Leach Pad 1 and 2					
84370 A	SonicPad1_LG-MC#1	100mm	17.8	Pass	100m
84371 A	SonicPad1_HG-MC#2	100mm	7.3	Pass	100m
84372 A	SonicPad2_LG-MC#3	100mm	19.0	Pass	100m
84373 A	SonicPad2_HG-MC#4	100mm	15.2	Pass	100m
Sonic Samples - Pad under-liner and Main and Hamburg Mine Dumps					
84374 A	SonicPad(BKFL_LG)-MC#5	100mm	27.3	Fail	75m
84375 A	SonicPad(BKFL_HG)-MC#6	100mm	25.5	Fail	50m
84376 A	Sonic-MainDump #7	37.5mm	23.0	Fail	50m
84377 A	Sonic-HamDump #8	100mm	24.0	Fail	75m

- Highlights >15% -200 mesh in column leach feed.

The following is a summary of comments relating to the heap leachability of the Sonic Drill composites.

- Leach Pad 1 and 2 residues, pad under-liner mineralized material and Main and Hamburg waste dumps all required significant amounts of cement for agglomeration before column leaching. Column leach residues for Pad Backfill (MC#5 and MC#6) and Main Dump #7 and Hamburg Dump #8 all failed LPT at 75 m, 50 m, 50 m, and 75 m, respectively. This is supportive of the planned coarse crush/agglomeration flowsheet envisioned for Goldstrike.
- Leach Pad 1 and 2 residues from low-grade and high-grade master composites all passed LPT at 100 m, and achieved respectable gold extractions, indicating potential commercial viability of re-heap leaching this material.
- It is recommended that the leach pad residues, pad under-liner, Main and Hamburg mine dumps be stockpiled and blended with freshly mined ore to prevent this material from all being placed on the bottom lifts of a new heap-leach pad to prevent potential lower lift permeability problems.
- It is recommended that a clay model be developed for Goldstrike reserves/resources to identify the pervasiveness of clay-rich materials throughout the various pits. This should result in a better mine/process blend plan to help cement additions required at the crusher to minimize leach pad operational issues.

13.4.4 Phase 3 – Bulk Sample Bottle Roll and Column Leach Testing (KCA)

Bottle-roll and column-leach test work on bulk samples was performed by KCA in Reno, Nevada (KCA 2023a). A summary of gold and silver extraction and reagent consumption is provided in Table 13-11.

Coarse and fine milled bottle-roll leach tests were completed on 10 of the 11 bulk composites. Composite GS-BS#10 was too low grade, and testing was terminated before column leaching.

Splits of head samples for each composite were subjected to bottle-roll leach testing at target P_{80} sizes of 75 µm and 1.7 mm.

Column leach testing was performed at a crush size of 100% passing 100 mm (4 in.), targeting a P_{80} approximating 75 mm.

Table 13-11: Summary of Bulk Sample Bottle Roll and Column Leach Test Results

Bulk Sample Composites		Resource Area	Material Type	Head Assay Au (g/t)	Cyanide Solubility AuCN (%)	Bottle Roll & Column Au Ext %			Reagent Consumption		
KCA Sample No.	Composite ID					200 mesh (75 µm)	10 mesh (1.70 mm)	75mm (3.0 in.)	NaCN (kg/t)	Lime (kg/t)	Cement (kg/t)
PHASE 3 - Mine Area Backhoe Bulk Sample Testing											
84380 A	GS-BS#1	Moosehead	oxide	0.868	101.4	91.3	85.0	85.0	0.33	0.0	6.0
84381 A	GS-BS#2	Moosehead	oxide	0.087	46.2	91.3	79.1	81.3	0.39	0.0	4.0
84382 A	GS-BS#3	Beavertail	oxide	0.149	87.2	94.2	86.0	83.7	0.48	0.0	4.0
84383 A	GS-BS#4	Beavertail	oxide	1.888	99.3	94.9	88.4	81.2	0.56	0.0	2.0
84384 A	GS-BS#5	Peg Leg-Cov	oxide	1.375	94.5	93.5	83.4	76.6	0.43	0.0	2.0
84385 A	GS-BS#6	Peg Leg-Cov	oxide	0.608	95.5	86.1	82.5	83.9	0.72	0.0	6.0
84386 A	GS-BS#7	Main Zone	oxide	0.504	97.2	90.4	80.7	61.8	0.44	0.0	2.0
84387 A	GS-BS#8	Main Zone	oxide	0.132	98.5	91.9	83.1	79.8	0.87	0.0	4.0
84388 A	GS-BS#9	Main Zone	oxide	3.29	101.1	94.9	93.8	92.9	0.67	0.0	4.0
84389 A	GS-BS#10	Main Zone	oxide	0.031	145.2	N/A - Too Low Grade - Test Terminated					
84390 A	GS-BS#11	Main Zone	oxide	0.127	106.3	91.9	84.8	88.8	0.6	0.0	4.0

Column-leach testing parameters for the bulk samples are summarized in Table 13-12.

Table 13-12: Bulk Sample Column Leach Crush Size and Charge Weight Data

KCA Sample	Composite ID	Resource Area	Crush Size (100% Passing)	Columns Size (mm)		Charge Weight (kg)
				Diameter	Height	
84380 A	GS-BS#1	Moosehead	100 mm	0.30	3.16	330.3
84381 A	GS-BS#2	Moosehead	100 mm	0.30	3.12	326.7
84382 A	GS-BS#3	Beavertail	100 mm	0.30	3.29	324.2
84383 A	GS-BS#4	Beavertail	100 mm	0.30	3.01	323.3
84384 A	GS-BS#5	Peg Leg-Cov	100 mm	0.30	2.97	327.9
84385 A	GS-BS#6	Peg Leg-Cov	100 mm	0.30	3.45	332.3
84386 A	GS-BS#7	Main Zone	100 mm	0.30	2.95	325.5

KCA Sample	Composite ID	Resource Area	Crush Size (100% Passing)	Columns Size (mm)		Charge Weight (kg)
				Diameter	Height	
84387 A	GS-BS#8	Main Zone	100 mm	0.30	3.08	314.8
84388 A	GS-BS#9	Main Zone	100 mm	0.30	2.94	311.3
84389 A	GS-BS#10	Main Zone	N/A - Too Low-Grade - Test Terminated			
84390 A	GS-BS#11	Main Zone	100 mm	0.30	3.20	308.1

The main objective of bulk sample testing was to evaluate the commercial scale leachability character of these materials in terms of gold extraction, extraction rate, reagent consumption, and sensitivity to particle size.

The bottle-roll testing used standard procedures that are described in the final laboratory report (KCA 2023a), using 144 hours of retention time for 1.7 mm tests, and 72 hours for 75 µm tests.

Column-leach tests were conducted utilizing material crushed to 100% passing 100 mm and placed in 250 mm diameter columns. During testing these composites were leached between 79 to 126 days with a dilute NaCN solution. After leaching, each column was washed/rinsed with water. A portion of the leached and washed residues from each column was assayed for "tail screen" analyses by size fraction and subjected to LPT. LPT parameters and results are reported in Table 13-13. Note: 2 kg/t to 6 kg/t of cement was agglomerated into the bulk samples, assisting in their passing LPT up to 100 m.

Table 13-13: Summary of Load Permeability Test Results for Sonic Drill Composites

KCA Sample No.	Resource Area	Crush Size (100% Passing)	Column Feed Fines	LPT Results	
			%-200M	Pass/Fail	Height
Bulk Samples					
84380 A	Moosehead	100 mm	21.2	Pass	100m
84381 A	Moosehead	100 mm	9.2	Pass	100m
84382 A	Beavertail	100 mm	10.2	Pass	100m
84383 A	Beavertail	100 mm	3.6	Pass	100m
84384 A	Peg Leg-Cov	100 mm	4.8	Pass	100m
84385 A	Peg Leg-Cov	100 mm	25.7	Pass	100m
84386 A	Main Zone	100 mm	1.8	Pass	100m
84387 A	Main Zone	100 mm	1.7	Pass	100m
84388 A	Main Zone	100 mm	1.2	Pass	100m
84389 A	Main Zone				
84390 A	Main Zone	100 mm	5.8	Pass	100m

The following is offered as a summary of the bottle-roll and column-leach test results, of the bulk samples, from the KCA 2023a report:

- Laboratory-scale bottle-roll and column-leach cyanidation testing was conducted on 10 of the 11 bulk samples. Composite GS-BS#10 testing was terminated once it was evident that it was below gold cut-off grade. The main objective for the bulk sample test program was to evaluate commercial scale crush/agglomeration flowsheet on resources in and around historical existing pits. Direct agitated cyanidation (bottle roll) tests were conducted on all bulk sample composites at a target particle size of P_{80} 75 µm and 1.7 mm. Column-leach testing was conducted on all 10 composites, targeting P_{80} feed size of 75 mm, to evaluate heap-leach amenability.
- All composites are considered oxide, with AuCN >80%.
- Fine grind (75 µm) bottle roll gold extractions ranged from 86.1% to 94.9%, with a weighted average of 93.4%.
- Coarse bottle roll (1.7 mm) gold extractions ranged from 79.1% to 93.8%, with a weighted average of 88.2%.
- Column leach gold extractions at target P_{80}'s of 75 mm ranged from 61.8% to 92.9%, with a weighted average of 84.4%.
- The average head grade for the bottle roll and column leach testing was 0.82 ppm Au.
- Column test gold extraction rates were rapid, with greater than 80% of the total extractable gold recovered in the first 20 days of leaching.
- Column test cyanide (NaCN) consumptions ranged from 0.33 kg/t to 0.87 kg/t and averaged 0.55 kg/t. KCA and industry experience related to commercial heap-leach NaCN consumption rates indicate that consumption will be considerably lower. *"Based upon KCA's experience with mostly clean non-reactive ores, cyanide consumption in production heaps would be only 25 to 33 percent of the laboratory column test consumptions."*
- Column test cement consumption ranged from 2.0 kg/t to 6.0 kg/t and averaged 3.8 kg/t.
- Column test lime consumptions were 0.0 kg/t, as the cement agglomeration provided adequate alkalinity during column leaching.
- All bulk sample column residues passed LPT, at 100 m heap height with the laboratory cement addition levels (see Table 13-10).

13.5 Phase 4 – Head Assays and Bottle Roll Leach Testing (KCA)

A Phase 4 bottle roll and column leach metallurgical program was commissioned by Liberty Gold in early 2023 with work being conducted by KCA (KCA 2023b). The scope of work covered 22 variability composites selected from large diameter PQ metallurgical core from the Hamburg, Basin, and Padre areas.

After initiating the SOW at KCA, a few weeks into the program Liberty Gold requested that the program be modified to exclude the column leach testing, LPT, tails screen analysis, and environmental characterization (highlighted in purple below). KCA was asked to complete the remainder of the program and issued and interim report (KCA 2023b) in November 2023.

Column leach feed screen analysis was completed, and the column charges are being held at KCA to complete the testing once a new budget is approved.

The SOW conducted by KCA included:

- Sample preparation
- Head assays and geochemical analysis
- 10 mesh and 200 mesh bottle roll tests
- Comminution testing
- Column leach testing at P_{80} of 12.5 mm and 25.0 mm
- LPT
- Tails screen analysis and assay by size fraction
- Environmental characterization

13.5.1 Phase 4 Sample Selection

Metallurgical core samples were selected from eight large diameter PQ diamond core holes drilled in 2022 from the Hamburg, Basin, and Padre areas in the northwest and west portions of the historical mine trend (Figure 13-1, Phase-4 orange dots).

A total of 22 variability composites were selected based upon the following geo-metallurgy criteria, filling gaps in significant resource areas:

- Gold/silver head grade
- Cyanide solubility (AuCN %)
- Lithology
- Alteration assemblages
- Rock geochemistry

Information related to Formation, Subunit, Au Final, AuCN %, and Ag Final assay was extracted from the Goldstrike Project geology database and these were the primary geo-metallurgical parameters used for composite selection and makeup.

13.5.2 Phase 4 - Head Assays

Gold and silver head assays were conducted by KCA (KCA 2023b). Cyanide solubility (AuCN), preg-robbing assays, carbon and sulphur speciation, and ICP analysis were conducted by KCA and ALS Chemex.

- Gold grade ranged from 0.295 ppm to 1.815 ppm Au and averaged 0.752 ppm Au.
- Silver grade ranged from 0.04 ppm to 4.23 ppm Ag and averaged 1.77 ppm Ag.
- Copper values were very low, ranging from 8 ppm to 71 ppm.
- Cyanide soluble gold content ranged from 28.7% to 96.1%, with a weighted average of 77.9%. There was one low cyanide soluble gold composite (GS-74 MC). Removing this composite from the list provides the following summary: Cyanide soluble Au ranged from 74.1% to 96.1%, with a weighted average of 84.0%.
- Cyanide soluble silver content ranged from 2.8% to 86.5%, with a weighted average of 36.7%.

- Organic carbon values were low and ranged from 0.05% to 0.20% and averaged 0.10%.
- Preg-robbing analysis ranged from 0.0 to 8.0% and averaged 0.90%, indicating that the composites are not-preg-robbing.
- Sulphide sulphur ranged from <0.01% to 0.85 % and averaged 0.09%. All composites are considered oxide, except for composite GS-74 MC.

From multi-element ICP geochemical analysis:

- As levels were low, ranging from 77 ppm to 1436 ppm and averaged 255 ppm. There was one high As assay in composite (GS-74 MC). Removing this sulphide composite from the list provides the following summary: Arsenic levels ranged from 77 ppm to 327 ppm and averaged 199 ppm.
- Hg levels were low, ranging from 0.09 ppm to 5.0 ppm and averaged 1.6 ppm.
- Concentrations of primary cyanide consumers (Cu, Ni, and Zn) were low, suggesting minimal potential to effect cyanide consumption rates.

Whole rock/QXRD analysis was conducted on all composites:

- Whole rock SiO_2 levels were high, ranging from 36.8% to 93.0%, averaging 82.5%.
- QXRD clay levels were moderate to high:
- Muscovite ranged from 1.5% to 25.3% and averaged 8.5%.
- Swelling Clay (CEC) ranged from 1.1% to 16.4% and averaged 4.9%.
- Kaolinite – only one composite (GS-73 PC) contained kaolinite at 1.7%.
- Calcium levels were moderate ranging from 0.17% to 25.5%, averaging 3.6%.

13.5.3 Phase 4 - Bottle Roll Testing (KCA)

Bottle roll characterization test work was performed by KCA in Reno, Nevada (KCA 2023b). A summary of gold and silver extractions and reagent consumption is provided in Table 13-14, below.

Coarse and fine milled bottle-roll leach tests were completed on each of the 22 variability composites. Splits of head samples for each composite were subjected to bottle-roll leach testing at target P_{80} sizes of 75 µm and 1.7 mm.

The bottle-roll testing used standard procedures that are described in the final laboratory report (KCA 2025), using 144 hours of retention time for 1.7 mm tests, and 72 hours for 75 µm tests.

Table 13-14: Phase 4 Bottle Roll Test Results

PHASE 4 - Goldstrike BR Testing				Material Type	Head Assay Au (g/t)	Cyanide Solubility AuCN (%)	Bottle Roll Au Ext %	
KCA Sample No.	Composite ID	Resource Area	Historical Mine Area				200 mesh (75µm)	10 mesh (1.70mm)
PHASE 4 - Goldstrike Met Core BR Testing								
97017A	GS-55, FZ(MSW)	Main	Hamburg	oxide	0.509	82.5	89.0	81.5
97018A	GS-56, PC,FZ	Main	Hamburg	oxide	0.560	85.7	89.5	86.5
97019A	GS-57, PC,FZ	Main	Hamburg	oxide	1.140	93.0	95.9	94.0
97020A	GS-58, MSW,FZ	Main	Hamburg	oxide	0.563	95.9	94.4	88.5
97021A	GS-59, MSW	Main	Hamburg	oxide	0.588	91.8	96.6	89.0
97022A	GS-60, PC	Main	Hamburg	oxide	0.324	80.2	92.8	78.8
97023A	GS-61, PC	Main	Hamburg	oxide	0.189	74.1	94.9	87.8
97024A	GS-62, PC	Main	Hamburg	oxide	1.710	81.3	93.0	83.4
97025A	GS-63, PC	Main	Hamburg	oxide	0.980	87.8	92.7	85.5
97026A	GS-64, PC	Main	Basin	oxide	0.600	85.0	89.5	85.3
97027A	GS-65, TC	Main	Basin	oxide	0.304	75.7	86.6	85.4
97028A	GS-66, TC	Main	Basin	oxide	1.605	82.9	77.6	73.4
97029A	GS-67, PC	Main	Basin	oxide	1.360	77.9	81.7	72.1
97030A	GS-68, PC	Main	Basin	oxide	0.655	80.9	91.7	74.5
97031A	GS-69, PC	Main	Basin	oxide	0.295	84.7	94.4	85.5
97032A	GS-70, TC	Main	Basin	oxide	0.700	72.9	72.7	61.7
97033A	GS-71, TC	Main	Basin	oxide	0.310	87.1	89.7	79.6
97034A	GS-72, PC	Main	Basin	oxide	0.781	83.2	88.7	82.8
97035A	GS-73, PC	Main	Basin	oxide	0.424	82.5	83.9	86.1
97036B	GS-74, MC	Main	Padre	sulphide	1.815	28.7	26.0	23.9
97037A	GS-75, MC	Main	Padre	oxide	0.539	77.9	76.3	67.7
97038A	GS-76, MR	Main	Padre	oxide	0.583	96.1	95.7	92.7
Phase 4 - Column leach testing has been delayed. Column charges are at KCA and will be tested at a future date.								

The following is offered as a summary of the bottle roll test results from the KCA 2023b report:

- Laboratory scale bottle roll cyanidation testing was conducted on 22 drill core composites. Direct leach agitated cyanidation (bottle roll) tests were conducted on all composites at a target particle size of P_{80} 1.7 mm and 75 µm, to determine gold extraction as a function of feed particle size.
- All 30 composites are considered oxide, with AuCN >70%, except for composite GS-74 MC, which is sulphide.
- Fine grind (75 µm) bottle roll test gold extractions ranged from 26.0% to 95.9%, with a weighted average of 81.3%. Removing the one sulphide composite (GS-74 MC) results in gold extraction ranging from 74.1% to 96.1%, with a weight average of 88.1%.

- Coarse bottle roll (1.7 mm) test gold extractions ranged from 23.9% to 94.0%, with a weighted average of 74.9%. Removing the one sulphide composite (GS-74 MC) results in gold extraction ranging from 64.7% to 94.0%, with a weight average of 81.1%.

13.6 Comments on Metallurgical Sampling and Testing

1 The extent of metallurgical testing and analytical procedures used are considered standard practice for the industry and the summaries provided are representative of the resources tested.

2 Gold and silver recovery predictions are based upon a significant number of bulk samples and variability composites designed to test the various material types and gold and silver grades of the Goldstrike resources.

3 Based upon the scope of the Goldstrike mineralized resources that have been sampled and tested to date, the leach sonic drill samples, bulk samples and metallurgical core samples are deemed to be representative of the various types and styles of mineralization in the known deposits and historical leach pads.

4 The extent of testing has shown that there are no deleterious elements present that would have a detrimental effect on potential economic extraction of gold and silver from the known resources.

13.7 Gold and Silver Recovery Models

13.7.1 Goldstrike Material Type Descriptions and Discussion

Gold and silver mineralization are largely hosted at the unconformity between the Claron Formation (TC) and the underlying Mississippian through Permian formations. The most extensive mineralization occurs in jasperoids and breccias at the Claron (TC) - Callville (PC) unconformity. Mineralization also occurs at the unconformity between the Claron (TC) and the Pakoon Dolomite (PP), Scotty Wash (MSW), or Redwall stratigraphic units (Figure 7-3). Other source of mineralization occurs in the middle sandstone unit of the Pakoon (Pps) and decalcified silty beds within the Callville.

To facilitate gold and silver recovery modelling of the various lithologic units, the following material type categories have been characterized, based upon gold cyanide solubility ranges. Gold and silver recovery equations are based upon lithology and AuCN % solubility ranges.

- Oxide: Mineralized oxide material with gold cyanide solubility >75%.
- Transitional: Mineralized transition material with gold cyanide solubility between 50% and 75%. There is very minimal sampling of this material type; insufficient to develop separate gold and silver recovery models.
- Waste: Mineralized sulphide/waste material with gold cyanide solubility <50%.

It should be noted that at the time of writing transitional material has not been modeled in the Goldstrike 3D model used for resource estimation, and any transition material in the deposit is currently assigned as oxide material and treated as oxide in application of metallurgical recovery equations.

- Geological Model: The Goldstrike geological model shown in Figure 13-4 was used to assign recovery equation to the various formations.

- Units such as Tcpyclay, Chainman Shale (MC), and all volcanic units (TC1) were assigned a 0.001% recovery due to the sulphidic or carbonaceous nature of these units.
- A sulphide model to capture any other poor to non-leach areas that are not captured into the Tcpyclay, MC or TC1 units was built based on cyanide solubility to fire assay ratio (AuCN) of <40%; these volumes were assigned 0.001% recovery.
- Currently no 3D cyanide solubility model has been developed for the transitional material with AuCN between 50% and 75%. The current resource transitional material is designated as oxide gold and silver recovery equations and may be overstating the gold recovery in whatever transition material tonnage exists at Goldstrike.
- It is recommended that additional 3D metallurgical gold cyanide solubility domain models be developed to match the metallurgical recovery models developed by GL Simmons.

Figure 13-4: Cross-Section Through the Main Zone Looking East



Source: Liberty Gold 2025.

Historical heap-leach process operations at Goldstrike started as a ROM project that quickly converted to a coarse crush/belt agglomeration flowsheet, using cement agglomeration, due to elevated clay content resulting in significant Pad 1 solution flow issues. The current resource uses a similar coarse crush/agglomeration flowsheet concept.

There may be significant tonnages of ROM compatible material for heap leaching, but the lack of a detailed clay model limits any consideration for ROM heap leaching in the current plan.

Mineralized resource cyanide solubility is affected by several deposit characteristics:

- Sulphide sulphur content is related to pyrite, arsenian pyrite, and arsenopyrite. Solid solution gold in these sulphides is not recoverable at any feed particle size.
- Organic carbon exists in isolated (3D modelled) parts of the deposits. Black organic carbon has a very low cyanide solubility and is considered waste in all circumstances.
- There is a blanket of clay-rich/sulphide-rich material (Tcpyclay) in a few areas at Goldstrike and they have been 3D modelled and designated as waste.
- Clay is distributed throughout the resource and may be somewhat preg-borrowing but has not proven to be significant.

Heap-leach particle feed size versus gold recovery curves at Goldstrike are very flat, mainly due to gold being deposited in fractures and fines, demonstrating very little benefit to fine crushing to increase gold recovery. Feed size versus gold extraction models have been developed for heap-leach feed P_{80} size ranging up to 250 mm (10 in.).

13.7.2 Gold and Silver Recovery Methodology

The following is a brief description of the methodology used to derive the Goldstrike gold-recovery models. Five steps are used in developing final commercial-scale gold recovery models:

- Step 1: Determine the gold extraction for each variability or bulk composite, using a combination of fine grind/crush bottle-rolls and medium/coarse crush column tests.
- Step 2: Develop head grade versus tails grade models to use in final development of the gold recovery equations.
- Step 3: Estimate solution losses at the end of economic gold recovery operations/closure.
- Step 4: Determine operational scale-up inefficiencies for the heap-leach flowsheet selected.
- Step 5: Incorporate steps 1-4 into final recovery models that reflect modelled test data metallurgical balances, commercial scale inefficiencies, and deductions for solution losses.

Details of the gold and silver recovery modelling technique is in internal and confidential files maintained by GL Simmons and in the Heliostar data room.

13.7.2.1 Gold Recovery Equations for Coarse Crush/Agglomeration Flowsheet

Gold recovery equations for oxide material types (AuCN >75%) are shown in Table 13-15. There are two equations for each material type, one for gold head grades <0.40 g/t Au and one for head grades >0.40 g/t Au.

Table 13-15: Goldstrike – Coarse Crush/Agglomeration Gold Recovery Equations

Geo Met Recovery Zone	Gold Rec (%)	Gold Grade Range	Max Gold Rec (%)
PC – Callville Limestone	=4.175*ln(HG) + 84.076	Au HG < 0.40 g/t	N/A
	=0.803*ln(HG) + 80.928	Au HG ≥ 0.40 g/t	82
PC – Callville Limestone (Beavertail)	=8.667*ln(HG) + 72.360	Au HG < 0.40 g/t	N/A
	=4.653*ln(HG) + 68.750	Au HG ≥ 0.40 g/t	74
PP – Pakoon Dolomite	=19.191*ln(HG) + 94.325	Au HG < 0.40 g/t	N/A
	=7.053*ln(HG) + 83.576	Au HG ≥ 0.40 g/t	91
TC – Claron Formation	=4.668*ln(HG) + 82.267	Au HG < 0.40 g/t	N/A
	=1.662*ln(HG) + 79.475	Au HG ≥ 0.40 g/t	82
MSW – Scotty Wash	=15.772*ln(HG) + 81.516	Au HG < 0.40 g/t	N/A
	=3.035*ln(HG) + 69.625	Au HG ≥ 0.40 g/t	73

Maximum gold recoveries are provided to prevent overestimating gold recovery on high-grade gold blocks.

There is not sufficient information to estimate transitional material gold recoveries, and there is no transitional AuCN 3D model and only one transitional composite that was tested. Oxide gold recovery equations have been adopted to estimate transitional gold recoveries in the resource model. This is a gap that needs to be filled in future testing.

13.7.2.2 Silver Recovery Equations for Coarse Crush/Agglomeration Flowsheet

Silver recovery equations for oxide material types are shown in Table 13-16. There are two equations for each material type, one for silver head grades <8.0 g/t Ag and one for silver head grades >8.0 g/t Ag.

Table 13-16: Goldstrike – Coarse Crush/Agglomeration Silver Recovery Equations

Geo Met Recovery Zone	Silver Rec (%)	Silver Grade Range	Max Silver Rec (%)
PC – Callville Limestone	=4.010*ln(HG) + 6.728	Ag HG < 8.0 g/t	N/A
	=2.197*ln(HG) + 10.437	Ag HG ≥ 8.0 g/t	18
PC – Callville Limestone (Beavertail)	=2.318*LN(HG) + 1.166	Ag HG < 8.0 g/t	N/A
	=0.478*ln(HG) + 4.924	Ag HG ≥ 8.0 g/t	7
PP – Pakoon Dolomite	=7.295*ln(HG) + 3.842	Ag HG > 8.0 g/t	N/A
	=1.504*ln(HG) + 15.672	Ag HG ≥ 8.0 g/t	22
TC – Claron Formation	=4.837*ln(HG) + 9.305	Ag HG < 8.0 g/t	N/A
	=2.948*ln(HG) + 13.182	Ag HG ≥ 8.0 g/t	24
MSW – Scotty Wash	=6.605*ln(HG) + 6.074	Ag HG < 8.0 g/t	N/A
	=4.472*ln(HG) + 10.473	Ag HG ≥ 8.0 g/t	27

Maximum silver recoveries are provided to prevent overestimating silver recovery on high-grade silver.

Although there are no silver equations for transitional silver mineralization, it is anticipated that they will be similar to the oxide silver recovery equations presented above.

13.7.2.3 Gold Recovery Equations for Leach Pad 1 and 2, Low-grade and High-grade Composites

Gold recovery equations for Pad 1 and Pad 2 heap-leach residues (Au head grades >0.20 ppm Au) are presented in Table 13-17. There are two equations for each material type, one for gold head grades <0.40 g/t Au and one for head grades >0.40 g/t Au.

Table 13-17: Goldstrike Leach Pad 1 and 2, Agglomeration Gold Recovery Equations

Geo Met Recovery Zone	Gold Rec (%)	Gold Grade Range	Max Gold Rec (%)
Leach Pad 1	=64.733*(HG) + 18.341	Au HG < 0.40 g/t	N/A
	=24.808*ln(HG) + 67.874	Au HG ≥ 0.40 g/t	68
Leach Pad 2	=66.681*(HG) – 1.777	Au HG < 0.40 g/t	N/A
	=29.286*ln(HG) + 51.474	Au HG ≥ 0.40 g/t	60

13.7.2.4 Silver Recovery Equations for Leach Pad 1 and 2, Low-grade and High-Grade Composites

Silver recovery equations for Pad 1 and Pad 2 heap-leach residues are in Table 13-18. A single equation is provided that covers all silver grade ranges. Minimum and maximum silver recoveries are provided to prevent silver recoveries from going below 0.0% and above 30.0%.

Table 13-18: Goldstrike Leach Pad 1 and 2, Agglomeration Silver Recovery Equations

Geo Met Recovery Zone	Silver Rec (%)	Silver Grade Range	Min/Max Silver Rec (%)
Leach Pad 1	=2.579*(HG) – 6.324	N/A	0.0/30.0
Leach Pad 2	=0.899*(HG) – 2.840	N/A	0.0/7.0

14.0 Mineral Resource Estimates

14.1 Summary

Mineral Resources for the Goldstrike Project are reported in accordance with NI 43-101 guidelines. The modelling and estimation of the Mineral Resources was completed between October and November 2024 under the supervision of the SLR QP. The Mineral Resource estimate presented here supersedes any previous Mineral Resources for the Goldstrike Project.

Canadian Institute of Mining, Metallurgy and Petroleum (CIM) Definition Standards for Mineral Resources and Mineral Reserves (CIM (2014) definitions) were used for Mineral Resource classification.

A total of 75 estimation domains representing gold mineralization were generated using Leapfrog Geo software and estimation was done using a multi-pass inverse distance cubed (ID^3) interpolation approach using Leapfrog Edge software. Classification was based on drill hole spacing and wireframes representing the classification boundaries were generated using Leapfrog Geo software. Estimation and classification were completed on a sub-block model, which was re-blocked in Vulcan software for pit optimization using Whittle software.

Validation procedures included comparison of wireframe volume to block volume, statistical comparisons between composite grades, nearest neighbour (NN) estimates, and ID^3 estimates, validation using swath plots, and visual validation in three dimensions, longitudinal sections, cross-sections, and plan sections.

The Goldstrike Project Mineral Resource estimate is presented in Table 14-1.

The QP is not aware of any environmental, permitting, legal, title, taxation, socio-economic, marketing, political, or other relevant factors that could materially affect the Mineral Resource estimate.

Table 14-1: Summary of Mineral Resources – March 23, 2026

Classification	Tonnage (000 t)	Grade (g/t Au)	Contained Metal (000 oz Au)
Indicated	65,804	0.46	975
Inferred	8,860	0.31	90

Notes:

1. CIM (2014) definitions were followed for Mineral Resources.
2. Mineral Resources are estimated at a gold cut-off grade of 0.10 g/t and using a long-term gold price of US$2,000 per ounce.
3. Mineral Resources are estimated using a variable recovery derived from metallurgical studies.
4. Bulk density is variable by rock type.
5. There are no Mineral Reserves currently estimated at the Goldstrike Project.
6. Mineral Resources that are not Mineral Reserves do not have demonstrated economic viability.
7. Mineral Resources are reported within conceptual open-pit shells.
8. Rounding as required by reporting guidelines may result in apparent discrepancies between tonnes, grades, and contained gold content.
9. The effective date of the Mineral Resource estimate is March 23, 2026.

14.2 Comparison to Previous Resources

The previous Mineral Resource estimate for the Goldstrike Project was prepared by SRK Consulting (Canada) Inc. (SRK) in 2018. The estimate was completed in Geovia GEMS software using concentric grade shells as estimation domains and an ID^2 interpolation method. Since the effective date of the 2018 Mineral Resource estimate, there has been an additional 55,502 m of RC, core, and sonic drilling over 507 drill holes.

Other key changes are:

- A revised geological model and improved understanding of the controls on gold mineralization were the framework for creation of new estimation domain wireframes.
- Increase in gold price from US$1,500/oz to US$2,000/oz.
- Decrease in the gold cut-off grade from 0.2 g/t to 0.1 g/t.
- Change in recovery equations from equations based on ROM to coarse crush/agglomeration flowsheet due to additional metallurgical testing.
- Use of more specific metallurgical equations relating to the geological model, rather than average equations by area.
- Increase in mining processing costs due to change from ROM to coarse crush/agglomeration flowsheet.

A comparison with the current Mineral Resource estimate is presented in Table 14-2.

Table 14-2: Comparison of Previous and Current Mineral Resource Estimates

Class	SRK - February 8, 2018			SLR – March 23, 2026			Difference		
	Tonnage (000 t)	Grade (g/t Au)	Contained Metal (koz Au)	Tonnage (000 t)	Grade (g/t Au)	Contained Metal (koz Au)	% Difference Tonnage	% Difference Grade	% Difference Contained Metal
Indicated	57,846	0.5	925	65,804	0.46	975	14%	-8%	5%
Inferred	19,603	0.47	296	8,860	0.31	90	-55%	-34%	-70%

Notes:
1. SRK Mineral Resource estimate used $1,500/oz Au price and 0.20 g/t Au cut-off grade.
2. SLR Mineral Resource estimate used $2,000/oz Au price and 0.10 g/t Au cut-off grade.

14.3 Mineral Resource Cut-off Grades

A gold cut-off grade of 0.10 g/t was developed for the Goldstrike deposit and reflects assumed mining costs of a conventional open-pit mine with typical heap-leach processing costs. The full operating cost, including mining, processing, and general and administrative (G&A) costs have been used in the calculations. Capital costs, including sustaining capital, have been excluded. Table 14-3 lists the parameters used in the calculation of the cut-off grade.

Table 14-3: Goldstrike Resource Cut-off Grade Summary

Parameter	Units	Value
Gold Price	US$/oz	2,000
Dore Freight, Security & Insurance	$/oz produced	5.50
Royalties	$/oz	20.00
Total Selling Cost	$/oz	25.50
Processing Gold Recovery	%	varies
Process Cost	$/t leached	1.97
Crushing Cost	$/t leached	2.00
Site General Cost	$/t leached	0.62
Total Process and Site Cost	$/t leached	4.59
Mining Cost	$/t mined	2.10

Notes:
1. The metallurgical recoveries vary based on the rock type and Au grade. The average recovery is 76.7%.
2. For all reporting purposes, a marginal cut-off grade of 0.10 g/t Au is used.

14.4 Resource Database

Within the Goldstrike property, Heliostar and its predecessors have completed 2,369 RC, sonic, and core holes totalling 216,869 m. The database was provided by Liberty Gold upon Heliostar's acquisition of the project. It consists of CSV files exported from Seequent's MX Deposit drill hole and data management application with location information stored in NAD 83, UTM Zone 12 N coordinates. The drill hole collar, survey, and interval tables were imported to Seequent's Leapfrog Geo and Edge software (version 2024.1.0) for visual validation, statistical analysis, wireframe building, block modelling, resource estimation, and block model validation.

The Project consists of four deposit areas (Figure 14-1) that are the focus of this Mineral Resource estimate. Listed from northeast to southeast, they are named Main Zone, Peg Leg-Cov, Moosehead, and Beavertail. Drilling within these deposit areas totals 199,828 m. Drill hole spacing averages 30 m to 35 m across Main, Moosehead, and Beavertail, and is slightly wider at 40 m within Peg Leg-Cov. The majority of the historical drill holes are oriented vertically, while the majority of the Liberty Gold holes were drilled at an angle in a fan arrangement.

14.4.1 Gold Mineral Resource Database

The database for the Mineral Resource estimate consists of 2,157 domain intersecting drill holes with a total assay length of 38,183 m within the estimation domain wireframes. Table 14-4 lists the amount of drilling used for the gold resource estimate.

Table 14-4: Summary of Drill Holes Supporting the Block Model Estimation

Company	Metres of Core Drilling	Metres of RC Drilling	Metres of Sonic Drilling
Bull Valley		2,707	
Cadillac		1,647	
Goldsil		2,487	
Houston International		1,963	
Inspiration	160	8,600	
North		664	
Occidental Minerals		556	
Occidental Minerals		73	
Permian		1,670	
Tenneco		47,691	
USMX Utah		7,644	
Historical Total	**160**	**75,703**	**0**
Liberty Gold (2015 – 2022)	4,364	119,153	802
Project Total	**4,524**	**194,856**	**802**

14.4.2 Silver

Silver mineralization is present at the Goldstrike Project in low concentrations and it has been produced in historical mining operations. The main trend of silver is correlated with the stratigraphically controlled gold surrounding the unconformity between the Claron Formation and the Permian units below; however, there is at least one additional silver mineralizing event and the controls on it are less understood.

Of the 133,930 gold assays within the Project, only 121,906 were assayed for silver. To help understand the potential for silver, silver was estimated using the gold estimation domains but is not included in the Mineral Resource estimate.

Figure 14-1: Goldstrike Project Areas Included in the Mineral Resource Estimate



Source: SLR 2025.

14.5 Geological Interpretation

14.5.1 Geological Model

Gold mineralization at Goldstrike is primarily stratigraphically controlled, with mineralization occurring both above and below the base of the unconformity between the Permian silty limestone units and the lower Cenozoic conglomerates, sandstones, and siltstones of the Claron Formation (Tcbc, Trbs, TC1). These units are cut by high-angle faults that are also mineralized, but only where they intersect favourable lithological units within the Claron Formation and the underlying Permian strata. The mineralization is associated with silica alteration (jasperoid) and these zones have been defined by separate wireframes within the geological model with the names Tcbjasp, PPjasp, Pcjasp, and Mswjasp. The example cross-section (Figure 14-2) through the Main Zone shows the mineralized zones modelled within the stratigraphic units adjacent to the unconformity, and the offset by the graben-bounding faults.

Liberty Gold generated wireframes representing the interpreted geology using Leapfrog Geo software. The SLR QP reviewed these wireframes and found them to be a good representation of the geological setting and the controls on the mineralization. This geological model was used to provide a context for the mineralization domains used for estimation. The estimation domains are described in Section 14.5.2. Because there was significant historical mining activity on the Property, both pre-mining and post-mining (current) versions of the geological model were created. The current version includes wireframes for “backfill” and “waste dumps” (Section 14.5.2), which represent material that was remobilized during historical mining activities, as well as Quaternary “Qal”, which represents other remobilized surficial material, such as that used during road building or pad creation. Qal was not included in the resource estimate.

Figure 14-2: Example Cross-Section Through the Main Zone Geological Model (Section 244,450E)



Source: SLR 2025.

14.5.2 Mineralization Domains

The mineralization domains were generated by Liberty Gold using Leapfrog Geo software. Drill hole lithology and assay data, combined with the interpreted geological model, were used in the creation of the wireframes. The wireframes were then reviewed and approved for use in the Mineral Resource estimate by the SLR QP.

Low-grade wireframes were built at a gold cut-off grade of 0.1 g/t. High-grade wireframes were built within the low-grade zones at a gold cut-off grade of 0.5 g/t to 0.6 g/t to target continuous high-grade mineralization. All zones were modelled at a minimum width of two metres. Domains were extended to a distance of 50% to an excluded barren drill hole, or 50% of the local drill hole spacing.

A total of 75 mineralization domains were created (Table 14-5). A plan view of the domains is shown in Figure 14-3 and an example cross-section view through the Main Zone is shown in Figure 14-4. Due to the presence of remobilized material, wireframes representing the backfill, waste dumps, and heap-leach pads from historical mining operations were also used as domains in the estimation process (Section14.5.3).

Table 14-5: Goldstrike Mineralization Domain Wireframes

Area	Number of Low-Grade Wireframes	Number of High-Grade Wireframes
Main	10	22
Peg Leg-Cov	12	7
Moosehead	3	3
Beavertail	6	12
Total Mineralization Wireframes		**75**

Figure 14-3: Plan View of Goldstrike Gold Mineralization Domains



Source: SLR 2025.

Figure 14-4: Cross-Section View of Goldstrike Gold Mineralization Domains in the Main Zone



Source: SLR 2025.

14.5.3 Backfill, Waste Dumps, and Heap-Leap Pads

To account for the historical mining activities over the Project area, three separate topography surfaces were used to generate the geological model and estimation domain wireframes. A pre-mining topography representing the surface prior to any mining activity, an “as mined” topography, and a present-day topography. The topographies were used to code the block model so that the Mineral Resources were limited to in-situ material, or remobilized material within the backfill dumps, waste dumps, or historical heap-leach pads.

The 2022 sonic drilling program had holes targeting the heap-leach pads, the backfill dumps, and the waste dumps. Testing has suggested that the gold in the heap-leach pads was incompletely leached and there remains additional gold that could be extracted through re-leaching. To create wireframes for the backfill dumps, waste dumps, and any remobilized surficial material used for road-building, the as mined topography was used in combination with the present-day topography to create volumes.

Two of the waste dumps in relation to the pre-mining topography are shown along with the geological model in Figure 14-4. Figure 14-5 shows a plan view of the backfill dumps, the waste dumps (wastefill), and the heap-leach pads, along with the locations of the 2022 sonic drill holes.

Figure 14-5: Plan View Showing Locations of Backfill, Waste Dumps, and Heap-Leach Pads



Source: SLR 2025.

14.5.4 Sulphide Model

Gold cyanide solubility is affected by several deposit characteristics including sulphide content related to pyrite, arsenian pyrite, and arsenopyrite. Solid solution gold in these sulphides is not recoverable by leaching at any feed particle size. To characterize the material types and the potential for recovery of gold and silver, recovery equations were assigned based on the lithology types in the geological model.

Units such as Tcpyclay, Chainman Shale (MC), and all volcanic units (TC1) were assigned a 0.001% recovery due to the sulphidic or carbonaceous nature of these units.

In addition to the geological model, wireframes representing the cyanide solubility to fire assay ratio (AuCN) of less than 40% were built using Seequent's Leapfrog Geo software. This model was evaluated to the block model and volumes within those wireframes were assigned a 0.0001% recovery.

A cross-section through the sulphide model is shown in Figure 14-6.

Figure 14-6: Vertical-Section Through Main Zone Sulphide Model Showing Zones of AuCN < 40%



Source: SLR 2025.

14.6 Resource Assays

14.6.1 Gold Capping Levels

Where the assay distribution is positively skewed or approaches log-normal, erratic high-grade assay values can have a disproportionate effect on the average grade of a deposit. One method of treating these outliers to reduce their influence on the average grade is to cut or cap them to a specific grade level. As a general rule of thumb, a Coefficient of Variation (CV) over two indicates possible outlier values that may need to be capped.

Table 14-6 compares the gold raw assay statistics with the capped statistics. Due to the low overall CV of the samples across the Project area, a single capping value of 15 g/t Au was applied to all domains. Several statistical methods were employed to determine appropriate capping levels. These included looking at the descriptive statistics for the raw assay data, plotting the raw assay data on histograms, log probability plots, and use of decile analysis. Examples of the statistical plots used for capping analysis are shown in Figure 14-7 and Figure 14-8.

In the SLR QP's opinion, the capping levels are reasonable to control the influence of high-grade outliers and have been applied correctly to the raw assay data.

Table 14-6: Gold Capped and Uncapped Assay Statistics

Area	Min Group	Descriptive Statistics - Au							
		Assay Value	Number of Samples	Mean (g/t Au)	CV	Min (g/t Au)	Median (g/t Au)	Max (g/t Au)	Number of Samples Capped
Beavertail	HG	Au	1,177	0.87	1.01	0.01	0.67	7.99	0
		Au Cap	1,177	0.87	1.01	0.01	0.67	7.99	
	LG	Au	3,219	0.21	1.43	0.00	0.14	5.55	0
		Au Cap	3,219	0.21	1.43	0.00	0.14	5.55	
	Wastefill	Au	16	0.13	0.93	0.02	0.07	0.47	0
		Au Cap	16	0.13	0.93	0.02	0.07	0.47	
Main	HG	Au	10,445	1.01	4.30	0.00	0.65	406.90	11
		Au Cap	10,445	0.96	1.24	0.00	0.65	15.00	
	LG	Au	17,744	0.19	1.44	0.00	0.14	9.17	0
		Au Cap	17,744	0.19	1.44	0.00	0.14	9.17	
	Backfill	Au	1,253	0.23	1.17	0.00	0.17	4.26	0
		Au Cap	1,253	0.23	1.17	0.00	0.17	4.26	
	Wastefill	Au	354	0.20	1.52	0.00	0.11	3.45	0
		Au Cap	354	0.20	1.52	0.00	0.11	3.45	
	Leachpads	Au	1,047	0.34	1.13	0.01	0.23	4.60	0
		Au Cap	1,047	0.34	1.13	0.01	0.23	4.60	

Area	Min Group	Descriptive Statistics - Au							
		Assay Value	Number of Samples	Mean (g/t Au)	CV	Min (g/t Au)	Median (g/t Au)	Max (g/t Au)	Number of Samples Capped
Moosehead	HG	Au	3,096	0.82	1.15	0.00	0.55	12.41	0
		Au Cap	3,096	0.82	1.15	0.00	0.55	12.41	
	LG	Au	3,300	0.21	1.39	0.00	0.14	5.90	0
		Au Cap	3,300	0.21	1.39	0.00	0.14	5.90	
	Backfill	Au	77	0.23	0.63	0.01	0.22	0.87	0
		Au Cap	77	0.23	0.63	0.01	0.22	0.87	
	Wastefill	Au	136	0.22	0.82	0.00	0.19	0.94	0
		Au Cap	136	0.22	0.82	0.00	0.19	0.94	
Peg Leg-Cov	HG	Au	1,414	1.05	1.18	0.00	0.75	18.25	1
		Au Cap	1,414	1.05	1.15	0.00	0.75	15.00	
	LG	Au	2,838	0.21	1.66	0.00	0.14	8.85	0
		Au Cap	2,838	0.21	1.66	0.00	0.14	8.85	
	Backfill	Au	32	0.20	1.11	0.00	0.15	1.06	0
		Au Cap	32	0.20	1.11	0.00	0.15	1.06	

Note: Statistics for Backfill, Wastefill, and Leachpads are based on 2015-2022 Pilot Gold drilling only in order to exclude the assay results from areas that are now mined out.

Figure 14-7: Histogram for Main Zone Raw Assays (Zoomed in on the axes)



Figure 14-8: Log Probability Plot for Main Zone Raw Assays



14.6.2 Silver Capping Levels

To help understand the potential for silver, silver was estimated using the gold estimation domains but is not included in the Mineral Resource estimate. The samples were left uncapped. The assay statistics for the silver samples are shown in Table 14-7.

The SLR QP notes that the CV for the majority of the zones is high and indicates that capping should be applied to the raw silver assay values. However, the high CVs can also be attributed to other factors including:

- Historical silver assay values that were below detection limits were assigned a value of 0.001, irrespective of the actual detection limit.
- Silver assays include samples that were analyzed using four-acid digestion with fire assay, as well as others that used aqua regia (two-acid) digestion with AA finish. Aqua regia with AA finish is not considered a total digestion for silver.
- The silver values show correlation with gold within the dominant trend in the Main Zone, but there is at least one other silver mineralizing event that is not correlated with the gold. This can be observed within the raw assay data where seven of the highest 15 silver assay values are outside of the modelled gold mineralization domains, and therefore not included in the estimate.

The QP recommends that further work, including additional drilling and sampling with appropriate analytical method (four-acid digestion), be completed to understand the silver mineralization controls. Once the controls on the mineralization are better understood, the silver that is not correlated with the gold should be modelled in separate mineralization wireframes for estimation purposes. Capping analysis should be completed on the silver samples within these domains and appropriate capping values applied prior to composting and estimation.

Table 14-7: Silver Uncapped Assay Statistics

Area	Min Group	Descriptive Statistics - Ag					
		Number of Samples	Mean (g/t Ag)	CV	Min (g/t Ag)	Median (g/t Ag)	Max (g/t Ag)
Beavertail	HG	1,177	1.83	2.64	0.00	0.17	61.27
	LG	3,218	0.42	6.49	0.00	0.00	61.27
	Wastefill	16	0.23	0.58	0.09	0.19	0.59
Main	HG	9,715	4.53	2.93	0.00	1.60	933.10
	LG	16,736	1.11	4.93	0.00	0.17	529.00
	Backfill	1,253	1.15	1.49	0.01	0.58	21.20
	Wastefill	354	0.95	1.65	0.01	0.49	12.35
	Leachpads	1,047	3.77	0.91	0.08	2.71	37.00
Moosehead	HG	2,671	1.22	2.24	0.00	0.00	30.17
	LG	2,714	0.33	3.35	0.00	0.00	18.97
	Backfill	77	0.30	0.66	0.04	0.27	1.45
	Wastefill	136	0.29	0.87	0.01	0.20	1.71

Area	Min Group	Descriptive Statistics - Ag					
		Number of Samples	Mean (g/t Ag)	CV	Min (g/t Ag)	Median (g/t Ag)	Max (g/t Ag)
Peg Leg-Cov	HG	1,412	1.72	1.97	0.00	0.09	23.33
	LG	2,820	0.84	17.82	0.00	0.08	453.58
	Backfill	32	0.30	0.78	0.02	0.21	0.75
Note: Statistics for Backfill, Wastefill, and Leachpads are based on 2015-2022 Pilot Gold drilling only in order to exclude the assay results from areas that are now mined out.							

14.7 Compositing

Composites were created from the capped, raw assay values using the downhole compositing function of Leapfrog's modelling software package. The composite lengths used during interpolation were chosen considering the predominant sampling length, block height, style of mineralization, and continuity of grade.

The capped assays were composited at 3.048 m (10 ft) downhole intervals, respecting the mineral domain boundaries. The composite length is equal to twice the average sample length of the assays and is approximately two thirds of the parent block height (5 m). A small number of unsampled and missing sample intervals were ignored.

Residual composites were maintained in the dataset. The gold composite statistics by domain group are shown in Table 14-8 and the silver composite statistics are in Table 14-9.

Table 14-8: Gold Composite Statistics

Area	Min Group	Count	Mean (g/t Au)	CV	Min (g/t Au)	Median (g/t Au)	Max (g/t Au)
Beavertail	HG	601	0.87	0.87	0.01	0.70	5.50
	LG	1,630	0.21	1.21	0.00	0.16	3.38
	Wastefill	4	0.16	0.79	0.03	0.14	0.31
Main	HG	5,298	0.96	1.10	0.00	0.69	15.00
	LG	9,077	0.19	1.22	0.00	0.15	5.97
	Backfill	536	0.23	0.93	0.00	0.18	2.23
	Wastefill	140	0.22	1.13	0.00	0.15	1.74
	Leachpads	499	0.34	1.00	0.06	0.24	3.78
Moosehead	HG	1,534	0.82	1.02	0.00	0.60	8.57
	LG	1,664	0.21	1.23	0.00	0.15	4.24
	Backfill	33	0.23	0.50	0.01	0.23	0.61
	Wastefill	61	0.23	0.67	0.00	0.21	0.67
Peg Leg-Cov	HG	725	1.05	0.98	0.00	0.81	12.47
	LG	1,470	0.21	1.40	0.00	0.15	7.36
	Backfill	14	0.19	0.75	0.00	0.17	0.43
Note: Statistics for Backfill, Wastefill, and Leachpads are based on 2015-2022 Pilot Gold drilling only in order to exclude the assay results from areas that are now mined out.							

Table 14-9: Silver Composite Statistics

Area	Min Group	Count	Mean (g/t Ag)	CV	Min (g/t Ag)	Median (g/t Ag)	Max (g/t Ag)
Beavertail	HG	601	1.83	2.51	0.00	0.52	60.50
	LG	1,630	0.42	6.11	0.00	0.00	59.25
	Wastefill	4	0.25	0.31	0.17	0.23	0.36
Main	HG	4,928	4.53	2.31	0.00	2.06	471.68
	LG	8,525	1.11	3.35	0.00	0.24	173.90
	Backfill	536	1.14	1.33	0.02	0.63	12.45
	Wastefill	140	1.05	1.31	0.03	0.58	8.69
	Leachpads	499	3.78	0.80	0.41	2.84	21.05
Moosehead	HG	1,318	1.22	1.95	0.00	0.00	18.96
	LG	1,366	0.33	2.92	0.00	0.00	14.46
	Backfill	33	0.30	0.49	0.05	0.26	0.70
	Wastefill	61	0.29	0.73	0.06	0.23	1.14
Peg Leg-Cov	HG	725	1.73	1.74	0.00	0.27	20.37
	LG	1,460	0.84	16.34	0.00	0.09	453.58
	Backfill	14	0.27	0.67	0.02	0.23	0.62

Note: Statistics for Backfill, Wastefill, and Leachpads are based on 2015-2022 Pilot Gold drilling only in order to exclude the assay results from areas that are now mined out.

14.8 Trend Analysis

14.8.1 Grade Contouring

3D grade contour wireframes were generated using the radial basis function (RBF) interpolation in Seequent's Leapfrog Geo software. These wireframes were created using the assay data without any anisotropy in order to assess the overall trends within the deposit. To reduce the influence of high-grade values on the volume of the grade shell, the contours were created as indicator interpolants with a probability value of 0.5The cut-off used for the gold trend analysis was 0.5 g/t Au and for the silver trend analysis, 5 g/t Ag was used (Figure 14-9).

Figure 14-9: Grade Contours Showing the Mineralized Trends in the Main Zone



Source: SLR 2025.

14.8.2 Variography

SLR generated experimental semi-variograms using the 3.048 m gold composited values located within selected individual mineralized domains. The variography was completed using Leapfrog Geo and Edge software. The grade contours described in the previous section were used to define the main plane of mineralization. Downhole variograms were used to model the nugget effect and to fit the across-strike variogram models. To better fit the data, the composites were transformed using a normal score transformation, and then back transformed to obtain the major, semi-major, and minor ellipsoid ranges. The variograms were used to support search ellipsoid distances, trend analysis, and Mineral Resource classification decisions.

An example variogram for domain 206 in the Main Zone is shown in Figure 14-10.

Figure 14-10: Variogram Model – Main Area Domain 206



14.9 Search Strategy and Grade Interpolation Parameters

The grade interpolation used a four-pass ID^3 approach. Each of the subsequent search passes had increased search ellipsoid dimensions and relaxed composite restrictions. Hard boundaries were used for all domains. The Qal unit was not included as an estimation domain. An NN estimate using 5 m composites as well as an inverse distance squared (ID^2) estimate using the 3.048 m composites were prepared using the same search parameters for validation purposes.

The search parameters are shown in Table 14-10.

Table 14-10: Search and Grade Interpolation Parameters

Search Pass	Minimum Samples	Maximum Samples	Max Samples per Hole	Ellipsoid Range 1 (m)	Ellipsoid Range 2 (m)	Ellipsoid Range 3 (m)
1	3	12	2	40	40	10
2	3	12	2	80	80	15
3	1	12	2	120	120	20
4	1	12	2	200	200	50

14.9.1 Dynamic Anisotropy

The search ellipsoids were rotated to follow the orientations of the domain wireframes using Leapfrog's Variable Orientation methodology. This approach uses the wireframes as inputs and calculates the rotation based on the normals on the wireframe faces.

An example cross-section showing the Variable Orientation directions in domain 206 is shown in Figure 14-11.

Figure 14-11: Section Through Main Zone Domain 206 Showing Variable Orientation Directions



Source: SLR 2025.

14.10 Bulk Density

Bulk density measurements were performed on a total of 698 core samples taken over the four Project areas. The density measurements were conducted by ALS laboratory in Elko, Nevada, using ALS's OA-GRA08a methodology, "Specific Gravity with Wax Coat". One measurement was duplicated with the same value in drill hole GS12-05, therefore a total of 697 measurements were used to inform the block model. Density measurements were taken from waste and mineralized intervals including both historical and Liberty Gold core. The measurements were flagged by lithology type and an average value for each lithology was calculated. The lithology geological model wireframes were flagged to the block model and the average density based on lithology was assigned to each block.

The assigned density values used in the block model are presented in Table 14-11.

Table 14-11: Block Model Densities by Lithology

Lithology Type	Assigned Density (t/m^3)
Backfill	1.72
Wastefill	1.72
Leach Pad 1	1.66
Leach Pad 2	1.58
Mc	2.55
Mmr	2.60
Msw	2.48
Mswjasp	2.44
Pc	2.51
Pcjasp	2.49
Pcq	2.44
Ppjasp	2.52
Ppl	2.46
Pps	2.44
Ppu	2.52
TC1	2.47
Tcbc	2.41
Tcbjasp2	2.47
Tcpyclay	2.44
Tig	2.40
Trbs	2.54
Tv	2.45
Qal	1.80
All Others	2.49

14.11 Block Models

The four deposit areas within the Goldstrike Project are contiguous and were estimated within a single sub-blocked model using Leapfrog Geo software. The sub-blocked model was regularized to the parent block size using Maptek Vulcan software. The regularized block model was imported to Geovia's Whittle software for pit optimization, and then back into Leapfrog Geo software for reporting. Table 14-12 describes the model dimensions. SLR considers the block model sizes to be appropriate for the mining method and dip of the mineralized zones.

Table 14-12: Goldstrike Block Model Parameters

	X	Y	Z
Parent Size (m)	10	10	5
Minimum Sub-Block Size (m)	5	5	1.25
Minimum Corner (m)	241,000	4,138,550	1,800
Boundary Size (m)	5,370	2,040	665
Rotation	330 degrees clockwise around Z-axis		

14.12 Cut-off Grade and Whittle Parameters

To fulfill the CIM requirement of "reasonable prospects for eventual economic extraction", or RPEEE, SLR prepared conceptual open-pit shells for the Project to constrain the block model for Mineral Resource reporting purposes.

Pit optimization was conducted in Geovia Whittle software utilizing the Lerchs-Grossmann (LG) algorithm to generate a pit shell based on a regular block model (10 m by 10 m by 5 m in size) and a set of input economic and technical parameters summarized in Table 14-13. An overall slope angle (OSA) of 45° was used.

The results of the pit optimization partially form the basis of the Mineral Resource statement and are used to constrain the Mineral Resource with respect to the CIM standards. Pit optimization does not constitute an attempt to estimate reserves.

Table 14-13: Goldstrike Whittle Pit Optimization Parameters

Goldstrike Whittle Pit Optimization Parameters	Units	Value
Gold Price	US$/oz	2,000
Base Mining Cost	$/t	2.10
Process Cost		
Process Cost	$/t	3.97
Site General Cost	$/t	0.62
Recoveries		

Goldstrike Whittle Pit Optimization Parameters	Units	Value
Processing Gold Recovery	%	Variable: average 76.7%
Other Costs		
Doré Freight, Security & Insurance	$/oz	5.50
Royalties	$/oz	20.00

14.13 Classification

Definitions for resource categories used in this Technical Report are consistent with those defined by CIM (2014) and adopted by NI 43-101. In the CIM classification, a Mineral Resource is defined as “a concentration or occurrence of solid material of economic interest in or on the Earth’s crust in such form, grade or quality and quantity that there are reasonable prospects for eventual economic extraction”. Mineral Resources are classified into Measured, Indicated, and Inferred categories. A Mineral Reserve is defined as the “economically mineable part of a Measured and/or Indicated Mineral Resource” demonstrated by studies at Pre-Feasibility or Feasibility level as appropriate. Mineral Reserves are classified into Proven and Probable categories.

The classification workflow was based upon drill hole spacing from the drill hole intervals using a Python-based calculation. This approach was validated using drill hole spacing calculated on each parent block within the sub-blocked model. The calculation was performed in Leapfrog software and used the average Euclidean distance to three closest samples in separate drill holes, then multiplied by 1.41. The classification boundaries were generated based on the drill hole intervals using Leapfrog software and were manually edited to produce continuous wireframes. In addition to drill hole spacing, the geological interpretation, type of the material (in-situ or remobilized), and the apparent continuity of the grade were considered when assigning classification.

There are no Measured Mineral Resources within the Goldstrike Project. Indicated Mineral Resources were defined for drill hole spacing up to 50 m. Inferred Mineral Resources were defined for spacing between 50 m and 100 m. There are no unclassified blocks within the mineralized zones. Material within the wastefill and backfill wireframes were downgraded to Inferred classification regardless of drill hole spacing due to the remobilized nature of the material.

A plan view of the classification model for all Project areas is shown in Figure 14-12. A cross-section through the classified resource blocks within the Main Zone is shown in Figure 14-13. Both figures show the classified in-pit resource blocks that are above the 0.1 g/t Au cut-off grade.

Figure 14-12: Plan View of the Classified Open Pit Resource – All Deposit Areas



Source: SLR 2025.

Figure 14-13: Cross-Section Through the Classified Open-Pit Resource Blocks in the Main Zone



Source: SLR 2025.

14.14 Block Model Validation

The SLR QP validated the block model using the following methods:

- Visual validation of the block grades within the domains with the estimation composites and the 5 m composites.
- Statistical comparison of the inverse distance estimation block grades, the nearest neighbour estimation block grades, and the estimation composite grades.
- Comparison of the inverse distance, nearest neighbour, and composite mean grades using swath plots.

14.14.1 Visual Validation

The QP completed visual validation of the block model estimates in three dimensions, as well as in plan section, vertical section, and long section views. The estimated block grades show good reproduction of the composites and do not appear to smear significantly.

Example plan and cross-section views of high-grade domain 206 in the Main Zone is shown in Figure 14-14. Cross-section and plan section views through the Beavertail low-grade domain 4100 and domain 4208, one of the high-grade zones within it, are shown in Figure 14-15.

Figure 14-14: Plan and Cross-Section Views Through Main Zone Domain 206



Source: SLR 2025.

Figure 14-15: Section and Planar Views Through Beavertail Domains 4100 and 4208





Note: 5 m composites shown

SLR

Heliostar Metals Ltd.

Goldstrike Project

Utah, USA

Section and Planar Views Through Beavertail Domains 4100 and 4208

Source: SLR 2025.

14.14.2 Statistical Validation

A comparison of the inverse distance block model statistics, the nearest neighbour block model statistics, and the composite gold grades for each of the Project areas is shown in Table 14-14.

The QP is of the opinion that there is good agreement between the ID^3 estimate, the NN estimate, and the estimation composites. The backfill and wastefill were estimated as separate domains, but are grouped in the comparison table below to distinguish between in-situ and remobilized material.

Table 14-14: Block Model Validation Statistical Checks

Area	Domain Group	Volume (m^3)	ID3 Estimate				NN Estimate				3.048 m Composites			
			Mean (g/t Au)	CV	Min (g/t Au)	Max (g/t Au)	Mean (g/t Au)	CV	Min (g/t Au)	Max (g/t Au)	Mean (g/t Au)	CV	Min (g/t Au)	Max (g/t Au)
Beavertail	HG	934,469	0.81	0.58	0.00	4.53	0.89	0.74	0.01	3.97	0.87	0.87	0.01	5.50
	LG	3,793,250	0.21	0.84	0.00	2.98	0.22	0.98	0.00	2.40	0.21	1.21	0.00	3.38
	Bkfl, wstfl	144,656	0.05	1.44	0.00	0.23	0.12	0.65	0.03	0.31	0.13	0.80	0.03	0.31
Main	HG	11,358,813	0.79	0.77	0.00	9.28	0.94	0.85	0.00	12.01	0.96	1.10	0.00	15.00
	LG	35,681,156	0.23	0.99	0.00	3.62	0.23	1.07	0.00	4.63	0.19	1.22	0.00	5.97
	Bkfl, wstfl	5,869,500	0.18	0.71	0.00	1.12	0.21	0.91	0.00	2.23	0.22	1.02	0.00	2.52
	Leachpads	3,580,156	0.33	0.65	0.00	2.60	0.34	0.91	0.06	2.72	0.34	1.00	0.06	3.78
Moosehead	HG	2,098,688	0.76	0.67	0.00	7.27	0.89	0.85	0.00	6.41	0.82	1.02	0.00	8.57
	LG	5,497,250	0.21	0.69	0.00	2.77	0.24	0.88	0.00	3.63	0.21	1.23	0.00	4.24
	Bkfl, wstfl	1,287,000	0.19	0.63	0.00	0.58	0.23	0.67	0.00	0.67	0.23	0.62	0.00	0.67
Peg Leg-Cov	HG	1,091,875	0.97	0.82	0.00	6.65	1.02	0.87	0.00	6.67	1.05	0.98	0.00	12.47
	LG	5,218,969	0.22	1.04	0.00	7.07	0.23	0.93	0.00	2.76	0.21	1.40	0.00	7.36
	Bkfl, wstfl	149,781	0.17	0.54	0.00	0.28	0.16	0.85	0.00	0.35	0.20	0.71	0.00	0.43

Note. Bkfl = Backfill, wstfl = Wastefill, LG = Low Grade, HG = High Grade, CV = Coefficient of Variation

14.14.3 Swath Plots

As part of the model validation process, swath plots were generated comparing the ID^3 estimate, the NN estimate, and the estimation composites. In general, these show very good agreement. The discrepancies are limited to areas with a low volume of blocks.

An example of the swath plots used for validation of the Main Zone are shown in Figure 14-16.

Figure 14-16: Main Zone Swath Plots



14.15 Grade Tonnage Sensitivity

Figure 14-17 shows the sensitivity of the pit constrained Indicated and Inferred Mineral Resources for the Goldstrike Mineral Resource model to various cut-off grades. The total tonnes (above 0 g/t Au) within the conceptual resource pit are 88 Mt.

Figure 14-17: Indicated and Inferred Gold Mineral Resource Grade Tonnage Curves



14.16 Mineral Resource Reporting

CIM (2014) definitions were used for Mineral Resource classification.

In the SLR QP's opinion the assumptions, parameters, and methodology used for the Project Mineral Resource estimate are appropriate for the style of mineralization. The effective date of the Mineral Resource estimate is March 10, 2025. Mineral Resources that are not Mineral Reserves do not have demonstrated economic viability.

For the purposes of open-pit optimization, the sub-blocked model was re-blocked to 10 m by 10 m by 5 m and Mineral Resources are reported from the regularized model. The Project resource estimate is summarized by area at a cut-off grade of 0.1 g/t Au in Table 14-15.

The QP is not aware of any environmental, permitting, legal, title, taxation, socio-economic, marketing, political, or other relevant factors that could materially affect the Mineral Resource estimate.

Table 14-15: Summary of Mineral Resources by Area – Effective Date March 23, 2026

Classification	Area	Tonnage (000 t)	Grade (g/t Au)	Contained Metal (000 oz Au)
Indicated	Beavertail	6,833	0.42	93
	Moosehead	8,624	0.46	128
	Main	46,441	0.46	686
	Peg Leg-Cov	3,906	0.54	67
	Total	**65,804**	**0.46**	**975**
Inferred	Beavertail	111	0.22	1
	Moosehead	1,483	0.3	15
	Main	6,980	0.32	72
	Peg Leg-Cov	286	0.25	2
	Total	**8,860**	**0.31**	**90**

Notes:

1. CIM (2014) definitions were followed for Mineral Resources.
2. Mineral Resources are estimated at a gold cut-off grade of 0.10 g/t and using a long-term gold price of US$2,000 per ounce.
3. Mineral Resources are estimated using a variable recovery derived from metallurgical studies.
4. Bulk density is variable by rock type.
5. There are no Mineral Reserves currently estimated at the Goldstrike Project.
6. Mineral Resources that are not Mineral Reserves do not have demonstrated economic viability.
7. Mineral Resources are reported within conceptual open-pit shells.
8. Rounding as required by reporting guidelines may result in apparent discrepancies between tonnes, grades, and contained gold content.
9. The effective date of the Mineral Resource estimate is March 23, 2026

15.0 Mineral Reserve Estimates

There are no current Mineral Reserve estimates for the Goldstrike Project.

16.0 Mining Methods

This section is not applicable.

17.0 Recovery Methods

This section is not applicable.

18.0 Project Infrastructure

This section is not applicable.

19.0 Market Studies and Contracts

This section is not applicable.

20.0 Environmental Studies, Permitting, and Social or Community Impact

This section is not applicable.

21.0 Capital and Operating Costs

This section is not applicable.

22.0 Economic Analysis

This section is not applicable.

23.0 Adjacent Properties

There are no properties of any significance adjacent to the Goldstrike Project.

24.0 Other Relevant Data and Information

No additional information or explanation is necessary to make this Technical Report understandable and not misleading.

25.0 Interpretation and Conclusions

SLR has reviewed the Goldstrike 2015–2024 project data, examined the drill data in the context of the property geology and mineralization, provided an updated resource estimate, and visited the Project site. SLR is unaware of any significant risks or uncertainties that could be expected to affect the reliability of the exploration information presented in this report, and the data provided to SLR by Heliostar are believed to be reasonably representative of the Goldstrike project geology and gold mineralization.

The Goldstrike property includes a past-producing heap-leach gold mine that was operated by Tenneco Mineral Co., a subsidiary of Tenneco Inc. (Tenneco) and United States Mineral Company (USMX) from late 1988 to 1996. A total of approximately 209,000 ounces of gold and 198,000 ounces of silver were produced during these operations from approximately 8 million tons (7.26 million tonnes) of ore mined from 12 open pits. The average grade was approximately 1.2 g/t Au (0.035 oz/ton Au). A total of 19 million short tons (17.24 million tonnes) of waste was also mined.

Liberty Gold acquired the Project in August 2014. Heliostar acquired the property in March 2026 through its wholly owned subsidiary, Helio Five Resources Ltd. In an agreement dated March 20, 2026, it agreed to purchase Specialty American Metals Inc., a wholly owned British Columbia subsidiary of Liberty Gold, which is the sole owner of Pilot Goldstrike Inc., a Nevada company that holds the Goldstrike Project. Based on a letter from the Utah Division of Oil, Gas, and Mining (UDOGM), dated August 12, 2012, Heliostar believes that there are no outstanding reclamation liabilities.

The Goldstrike mineralization shares many of the characteristics of Carlin-type gold deposits. The mineralization is hosted primarily in conglomerate and limestone of the basal Claron Formation of Tertiary age, as well as with underlying Paleozoic units. The principal controls on mineralization include the generally shallow-dipping unconformity at the base of the Claron Formation, which is extensively mineralized, and high-angle structures of various orientations that appear to be the conduits through which mineralizing fluids circulated. These structural zones can also lead to significant mineralization in the Paleozoic silty limestone of the Pennsylvanian Callville Limestone and Mississippian Redwall Limestone, important hosts of mineralization.

The Project drill hole database includes 1,391 holes (87,175 m) drilled by historical operators and 984 holes for 130,218 m drilled by Liberty Gold in late 2015 through 2022. The data includes 39 core holes and 23 sonic holes, with the remainder being RC holes. Heliostar has not completed any drilling or exploration activities as of the effective date of this report.

SLR reviewed the Project database, and the QP is of the opinion that the data are acceptable as used in this report, although the locations of many of the historical drill holes are uncertain. During its time as operator, Liberty Gold completed work to validate drill hole locations by using historical data (e.g., drill logs and surface location maps and aerial imagery), as well as by surveying the relatively small percentage of historical drill collars that can still be identified in the field.

While a large number of historical holes have been drilled at the Goldstrike property, most are shallow (the average of the downhole drill lengths is 64 m) and were drilled within and immediately adjacent to areas that were subsequently mined. Historical holes drilled outside of the limits of the open pits suggest that the mined mineralization extends beyond pit limits and remains open along the seven-kilometre-long mine trend, and this has been confirmed by Liberty Gold's drilling program and Heliostar's resource estimate.

The Goldstrike oxide resources appear to be readily amenable to crush and/or ROM conventional heap leaching practice. Cyanide and lime consumptions are low to moderate. Deleterious elements such as copper, zinc, mercury, nickel, etc., are low and will have minimum impact upon cyanide consumption. Power required for crushing and abrasion wear characteristics are low to moderate and represent minimal risk. Oxide gold recoveries are considered to be good to excellent, depending upon resource location, cyanide solubility, and particle size.

26.0 Recommendations

In the SLR QP's opinion, this property has merit, warranting additional exploration expenditures. Finding additional mineralization of economic interest within the Goldstrike property is possible through drill testing of prioritized targets, both known and conceptual. Work to advance engineering, economic, and hydrological modelling and studies is also justified.

Heliostar has outlined an approximately US$7,550,400 2026 work program of 22,500 m of RC and core drilling in the resource area and Antimony Ridge. The program includes a district-wide field exploration program that includes geophysics, remote sensing, and surface work. The SLR QP supports this work program.

It is recommended that additional transition metallurgical samples be obtained for testing and that the 3D geology/mine block model be updated to cover the oxide, transition, and waste gold cyanide solubility ranges proposed by GL Simmons.

If silver is to be included in future Mineral Resource estimation, the SLR QP recommends that samples be analyzed using four-acid digestion instead of two-acid aqua regia, which is not a total digestion for silver. Remodelling of the silver domains should follow once the controls on the silver mineralization are better understood.

Engineering work, including site evaluation and economic modelling, is recommended, culminating in a revised Technical Report and update to the 2018 PEA, which is no longer current. An application for a Notice of Intent (NOI) to address drilling in the Antimony Ridge was submitted in June 2025 and approved. Additional work to find a viable water source suitable for a mining operation should be progressed.

Details of the costs of the recommended program are tabulated in Table 1-2.

Table 26-1: Estimated Cost for the Advanced Exploration Program Proposed for the Goldstrike Project

Category	US$	Comments
Drilling	4,923,000	Goldstrike Main & Antimony Ridge & water 15,000 m RC averaging ~$90/m, 7,500 m core averaging ~$400/m, assays @ $60/sample
Technical Report Update	750,000	PEA and mineral resource update
District Field Exploration	785,000	Mapping, prospecting, IP geophysics, soil and rock sampling, assays, remote sensing, field support and compilation
Metallurgy	150,000	Final work on remaining and proposed composites
Re-assaying	101,600	Re-assaying (gold assay verification and silver using four acid digestion)
Geotechnical Consulting	200,000	Work separate from the PEA including engineering, reporting, etc.
Hydrological Consulting	150,000	Work separate from the PEA including water exploration and water rights
Environmental	80,000	Monitoring and surveys
Property	529,051	Claim fees and lease holding costs
5% Contingency	359,353	
Total	**7,546,404**	

The QPs are unaware of any significant factors and risks that may affect access, title, or the right or ability to perform the exploration work recommended for the Goldstrike Project.

27.0 References

Adair, D.H. 1986. Structural setting of the Goldstrike district, Washington County, Utah. In: Griffin, D.T., and Phillips, W.R., eds. Thrusting and extensional structures and mineralization in the beaver Dam Mountains, southwestern Utah. Utah Geological Association Publication 15, pp. 137-148.

Adair, D.H. 1988. Geologic map of the Goldstrike Mine area: unpublished map prepared for Tenneco Minerals Co.

Best, M.G. and Grand, K. 1987. Stratigraphy of the volcanic Oligocene Needles Range Group in southwestern Utah and eastern Nevada: U.S. Geological Survey Professional Paper 1433 A-B, 52 p.

Best, M. G., Christiansen, E. H., Deino, A. L., Grommé, C. S., McKee, E. H., and Noble, D. C. 1989. Excursion 3A: Eocene through Miocene volcanism in the Great Basin of the western United States, *in* Chapin, C. E., and Zidek, J., eds., Field excursions to volcanic terranes in the western United States, Volume II: Cascades and Intermountain West: New Mexico Bureau of Mines and Mineral Resources, Memoir 47, pp. 91-133.

Best, M.G., Christiansen, E.H., and Blank, H.R., Jr. 1989. Oligocene caldera complex and calcalkaline tuffs and lavas of the Indian Peak volcanic field, Nevada and Utah: Geological Society of America Bulletin, v. 101, pp. 1076 – 1090.

Callaway, R.Q. and Gates, E.E. 1981. Goldstrike Project including geological evaluation of Beaver Claims: Unpublished internal report for HIMCO, 96 p.

Cameron, J.W. 1986a. Gold Strike mineralogy: Unpublished Inspiration Consolidated Copper Company Interoffice Memorandum, 3 p.

Cameron, J.W. 1986b. Eleven Gold Strike, UT, feed and tailings samples, including 7 screen fractions: Unpublished Inspiration Consolidated Copper Company Interoffice Memorandum, 3 p.

CIM. 2014. Canadian Institute of Mining, Metallurgy and Petroleum (CIM) Definition Standards for Mineral Resources and Mineral Reserves, adopted by the CIM Council on May 10, 2014.

CIM. 2019. CIM Estimation of Mineral Resources & Mineral Reserves Best Practice Guidelines, adopted by the CIM Council on November 29, 2019.

Cline, J.S., Hofstra, A.H., Muntean, J.L., Tosdal, R.M. and Hickey, K.A. 2005. Carlin-Type Gold Deposits in Nevada: Critical Geologic Characteristics and Viable Models: Economic Geology 100th Anniversary Volume, pp. 451-484.

De Witt, H.C. 2015. Geology and mineralization of the Goldstrike District, Washington County, Utah: M.Sc. thesis, University of Arizona, 63 p.

Effner, S.A. 1992. The geology, hydrothermal alteration and minor element geochemistry of the Goldstrike Mine, Washington County, Utah: M.S. Thesis, University of Idaho, 110 p.

Environmental Resources Management Inc., 2014, Phase I Environmental Site Assessment, Goldstrike Mine and Surrounding Area, Washington County, Utah, 126 p.

Erwin, T. 2014. Goldstrike Project: Mineral Status Report prepared for Cadillac Mining Corporation, dated Aug. 26, 2014, 48 p.

Erwin, T. 2016. Goldstrike Project: Mineral Status Report prepared for Pilot Gold Inc., dated Nov.16, 2016, 103 p.

Erwin, T. 2017. First Supplement to mineral Status Report; Goldstrike Project; Washington County, Utah; prepared for Liberty Gold Corp., Dated Dec. 11, 2017, 116 p.

Erwin, T. 2018a. Second Supplement to mineral Status Report; Goldstrike Project; Washington County, Utah; prepared for Liberty Gold Corp., Dated Jan. 26, 2018, 120 p.

Erwin, T. 2018b. Third Supplement to Mineral Status Report; Goldstrike Project; Washington County, Utah; prepared for Liberty Gold Corp., Dated Oct. 2, 2018, 157 p.

Erwin, T. 2019. Fourth Supplement to Mineral Status Report; Goldstrike Project; Washington County, Utah; prepared for Liberty Gold Corp., Dated Sep. 10, 2019, 161 p.

Enns, J. 2017. Logistics report prepared for Pilot Gold, Inc., Volterra 2DIP on the Goldstrike Property: unpublished report for Pilot Gold, prepared by SJ Geophysics Ltd. 29 p.

Goldstrand, P.M. 1991. Tectonostratigraphy, petrology and paleogeography of Upper Cretaceous to Eocene rocks of southwest Utah: Ph.D. Thesis, University of Nevada, Reno, 205 p.

Goldstrand, P.M. 1994. Tectonic development of Upper Cretaceous to Eocene strata of southwestern Utah: Geological Society of America Bulletin, v. 106, p. 145-154.

Greenan, D.M. 1985. Geology and remote sensing of the Goldstrike District, Washington County, Utah: An integrated study: Bachelor's thesis, University of Maryland, 171 p.

Gustin, M.M., and Smith, M.T. 2016. Technical report on the Goldstrike Project: Canadian National Instrument 43-101 technical report, 106 p.

Hazen Laboratories Inc. 2016. Comminution Testing, Hazen Project 12319, November 18, 2016. Unpublished report for Pilot Gold USA.

Hebert, J.P. 1988. Geologic ore reserves, Hassayampa Zone, Goldstrike Project: unpublished Tenneco Minerals Co. Interoffice Communication, 4 p.

Hebert, J.P. 1990. Sulfide/carbon ore: unpublished Tenneco Minerals Co. Interoffice Communication, 2 p.

Heliostar Metals Ltd. 2026. Heliostar to Acquire Goldstrike Gold Project in Utah, press release dated March 23, 2026. Available at: https://www.heliostarmetals.com/news-media/news-releases/heliostar-to-acquire-goldstrike-gold-project-in-utah. Acessed April 23, 2026.

Hintze, L.F. 1980. Geologic map of Utah: Utah Geological and Mineral Survey Map, scale 1:500,000.

Hintze L.F., Anderson, R.E., and Embree, G.F. 1994. Geologic map of the Motoqua and Gunlock quadrangles: US Geological Survey Miscellaneous Investigations Series, Map I-2427.

KCA. 2017. Kappes, Cassiday & Associates (KCA), Goldstrike Project Report of Metallurgical Test Work, April 2017. Project No. 9059C, Report I.D. KCA060096_02. Unpublished report for Pilot Gold USA, Inc.

KCA. 2018. Goldstrike Project Phase II Test Work, June 2018. Project No. 9059C, Report I.D. KCA0180062_GSU02_01. File: 9059. Unpublished report for Pilot Gold USA, Inc.

KCA. 2023a. Goldstrike Utah Project, Bulk and Pad Samples, Report of Metallurgical Test Work, September2023. Project No. 9059C, Report I.D. KCA022077_GSU03. File: 9059. Unpublished report for Pilot Gold USA, Inc.

KCA. 2023b. Goldstrike Utah Project, Variability Met Core, Report of Metallurgical Test Work, November 2023. Project No. 9059C, Report I.D. KCA0230040_GSU04_02. File:9059. Unpublished report for Pilot Gold USA, Inc.

KCA. 2025. Goldstrike, Utah Project: Antimony Ridge Report on Metallurgical Test Work Project No. 9059 C File: 9059 Report I.D.: KCA0240044_GSU05_01, Unpublished report for Pilot Goldstrike, 56 p.

Knudsen, T.R. and Biek, R.F. 2014. Interim geologic map of the Cedar City NW Quadrangle, Iron County, Utah: Utah Geological Survey Open-File Report 627, 20 p.

LaRocque, A. 1960. Molluscan faunas of the Flagstaff Formation of central Utah: Geological Society of America Memoir 78, 100 p.

MEG MineSearch. 2012. Goldstrike Project Profile Report, 8 p.

Moorhead, R. 2014. Title Report, Patented Mining Claim Groups, Goldstrike Project, Washington County, Utah: Title Memorandum prepared for Pilot Gold, 2 p.

Muntean, J.L. 2018. The Carlin gold system: Applications to exploration in Nevada and Beyond: Society of Economic Geologists, Inc., Reviews in Economic Geology, v. 20, p. 39-88.

Muntean, J.L., and Cline, J.S. 2018. Diversity of Carlin-style gold deposits: Society of Economic Geologists, Inc., Reviews in Economic Geology, v. 20, p. 1-5.

Parsley, G.P. 1994. Exploration work summary, lease year 1993-1994, Jedediah (GS) Claims, Goldstrike Mining District, Washington County, Utah: Unpublished internal company report, 362 p.

Parsons, Behle, and Latimer. 2022. Limited Due Diligence Update Report - Goldstrike Project, Dated March 22, 2022, 48 p.

Puchlik, K.P. 2010. Technical Report, Mineral Mountain Project, Washington County, Utah, USA: Canadian National Instrument 43-101 Technical Report prepared for Tonogold Resources Inc., by Puchski GeoConsultants, 69 p.

Robert, F., Brommecker, R., Bourne, B.T., Doback, P.J., McEwan, C.J., Rowe, R.R. and Zhou, X. 2007. Models and exploration methods for major gold deposit types: *in* Milkereit, B., ed., Ore Deposits and Exploration Technology, Paper 48, Proceedings of Exploration 07: Fifth Decennial International conference on Mineral Exploration, p. 691-711.

Rowley, P.D., Steven, T.A., Anderson, J.J., and Cunningham, C.G. 1979. Cenozoic stratigraphy and structural framework of southwestern Utah: U.S. Geological Survey Professional Paper 1149, 27 p.

Rowley, P.D., Anderson, R.E., Hacker, D.B., Boswell, J.T., Maxwell, D.J., Cox, D.P., Willden, R. and Adair, D.H. 2007. Interim geologic map of the Goldstrike Quadrangle and the east part of the Docs Pass Quadrangle, Washington County, Utah: Utah Geological Survey, Open-File Report 510, 34 p.

Schaubs, M. 1981. Goldstrike Project, Annual Report 1980: Unpublished report for HIMCO, 120 p.

Schultz, L.M. and Schultz, J.S. 1987. Flora of western Utah – early Cenozoic to the present: *in* Cenozoic geology of western Utah; sites for precious metal and hydrocarbon accumulations, Utah Geological Association, Publication 16, p. 65-74.

Schurman, S.R. 1987. Goldstrike Project, Washington County, Utah: Unpublished report for Goldsil Resources, 19 p.

Shabestari, P. and Smith, M. 2020. The history, geology and gold mineralization at the Goldstrike deposit, southwestern Utah: an unusual, off-trend, Carlin-type gold deposit: Great Basin Symposium.

SRK. 2018A. Independent Technical Report and Resource Estimate for the Goldstrike Project, Washington County, Utah USA: SRK Consulting (Canada) Inc., Canadian National Instrument 43-101 Technical Report, 248 p.

SRK. 2018B. Preliminary Economic Assessment and Independent Technical Report for the Goldstrike Project, Washington County, Utah, USA: SRK Consulting (Canada) Inc., Canadian National Instrument 43-101 Technical Report, 244 p.

UDOGM. 2012. Letter from the State of Utah Department of Natural Resources Division of Oil, Gas and Mining to Cadillac Mining Corporation regarding the reclamation status of the Property, dated August 12, 2012.

USMX. 1993. Goldstrike Project Final Report on Column Leach Tests on MOS and BEV Bulk Samples. Kappes, Cassiday & Associates - December 8, 1993.

Willden, R. 2006. Goldstrike Mining District, Washington County, Utah: Utah Geological Association Publication 32, pp. 458 – 477.

Willden, R., and Adair, D.H. 1986. Gold deposits at Goldstrike, Utah: Utah Geological Association Publication 15, pp. 137 – 147.

Williams, P. L. 1967. Stratigraphy and petrography of the Quichapa Group, southwestern Utah and southeastern Nevada: Seattle, Washington Univ. Ph. D. thesis, 139 p.

Wright, J.L. 2017. Goldstrike Property Airborne Magnetic/Radiometric Survey, Gradient Array Resistivity Survey, GIS Database: Internal Report prepared for Liberty Gold, April, 2017, 28 p and digital data files.

28.0 Date and Signature Date

This report titled “NI 43-101 Technical Report, Goldstrike Project, Utah, USA” with an effective date of March 23, 2026, was prepared and signed by the following authors:

(Signed & Sealed) ***Lorraine Tam***

Dated at Vancouver, BC
May 6, 2026

Lorraine Tam, P.Geo.

(Signed & Sealed) ***Gary L. Simmons***

Dated at Larkspur, CO
May 6, 2026

Gary L. Simmons, MMSA

29.0 Certificate of Qualified Person

29.1 Lorraine Tam

I, Lorraine Tam, P.Geo., as an author of this report entitled “NI 43-101 Technical Report, Goldstrike Project, Utah, USA” with an effective date of March 23, 2026, prepared for Heliostar Metals Ltd., do hereby certify that:

1 I am a Principal Resource Geologist with SLR Consulting (Canada) Ltd, of Suite 200 – 887 Great Northern Way, Vancouver, BC V5T 4T5.

2 I am a graduate of University of British Columbia, Vancouver, British Columbia, Canada in 2005 with a Bachelor of Science (Honours) in Geological Sciences.

3 I am registered as a Professional Geologist in the Province of British Columbia (Reg.# 41054). I have worked as a geologist for a total of 19 years since my graduation. My relevant experience for the purpose of the Technical Report is:

- Lithology and mineralization modelling.
- Data analysis and validation.
- Exploration Geologist on precious and base metal projects in Canada and Mexico.
- Mineral estimation work and reporting on precious and base metal projects around the world.
- Expert user of Leapfrog software.

4 I have read the definition of "qualified person" set out in National Instrument 43-101 (NI 43-101) and certify that by reason of my education, affiliation with a professional association (as defined in NI 43-101) and past relevant work experience, I fulfill the requirements to be a "qualified person" for the purposes of NI 43-101.

5 I visited the Goldstrike Project on March 5, 2025.

6 I am responsible for the overall preparation of the Technical Report, including Section 1 (with the exception of portions of Section 1.1 pertaining to metallurgy and Section 1.2.10), Sections 2 to 12, 14 to 24, Sections 25 and 26 (with the exception of portions pertaining to metallurgy), and Section 27.

7 I am independent of the Issuer, Heliostar, and the Goldstrike Project, applying the test set out in Section 1.5 of NI 43-101.

8 I have had no prior involvement with the property that is the subject of the Technical Report.

9 I have read NI 43-101, and the Technical Report has been prepared in compliance with NI 43-101 and Form 43-101F1.

10 At the effective date of the Technical Report, to the best of my knowledge, information, and belief, Sections 1 to 12 and 14 to 27 in the Technical Report for which I am responsible, contain all scientific and technical information that is required to be disclosed to make the Technical Report not misleading.

Dated this 6th day of May, 2026

(Signed & Sealed) ***Lorraine Tam***

Lorraine Tam, P.Geo.

29.2 Gary L. Simmons

I, Gary L. Simmons, QP MMSA, as an author of this report entitled “NI 43-101 Technical Report, Goldstrike Project, Utah, USA” with an effective date of March 23, 2026, prepared for Heliostar Metals Ltd., do hereby certify that:

1 I am the Owner of GL Simmons Consulting, LLC, 15293 Shadow Mountain Ranch Road, Larkspur, CO 80118.

2 I am a graduate of the Colorado School of Mines in Golden, Colorado, USA in 1972 with a bachelor’s degree in metallurgical engineering.

3 I am registered as a Qualified Professional (QP) with the Mining & Metallurgical Society of America (MMSA) in Colorado, USA, QP Number: 01013QP. I have worked as a metallurgical engineer for a total of 52 since my graduation. My relevant experience for the purpose of the Technical Report is:

- 10 years of operational experience in base/precious metals for The New Jersey Zinc Company, Noranda Mining and Meridian Minerals Company.
- 30 years in corporate level management in the gold/copper/silver business working on metallurgical studies, pilot plants, process flowsheet development and all levels of design and engineering studies for: 1. Meridian Minerals Co (Mill Supt & Director of Metallurgy), 2. Santa Fe Pacific Gold Corp (Director of Metallurgy) and Newmont Mining Corp (Director of Metallurgy & Technology).
- 12 years as metallurgical consultant working on global oxide and refractory gold/silver/copper projects.

4 I have read the definition of "qualified person" set out in National Instrument 43-101 (NI 43-101) and certify that by reason of my education, affiliation with a professional association (as defined in NI 43-101) and past relevant work experience, I fulfill the requirements to be a "qualified person" for the purposes of NI 43-101.

5 I visited the Goldstrike Project on March 22, 2018, May 16, 2018 and May 16, 2022.

6 I am responsible for portions of Section 1.1 pertaining to metallurgy, Section 1.2.10, 13, and portions of Sections 25 and 26 pertaining to metallurgy of the Technical Report.

7 I am independent of the Issuer, Heliostar and the Goldstrike Project and have participate in previous studies on the project: 1. Independent Technical Report and Resource Estimate for the Goldstrike Project, Washington County, Utah, USA, prepared by SRL Consulting (Canada) Inc., Effective date 08 February, 2018; and 2. Preliminary Economic Assessment and Independent Technical Report for the Goldstrike Project, Washington County, Utah, USA, prepared by SRK Consulting (Canada) Inc., Effective Date 08 February 2018, applying the test set out in Section 1.5 of NI 43-101.

8 I have had no prior involvement with the property that is the subject of the Technical Report other than that which is stated above.

9 I have read NI 43-101, and the Technical Report has been prepared in compliance with NI 43-101 and Form 43-101F1.

10 At the effective date of the Technical Report, to the best of my knowledge, information, and belief, Sections 13 and 1.1 in the Technical Report for which I am responsible contain all scientific and technical information that is required to be disclosed to make the Technical Report not misleading.

Dated 6th day of May, 2026

(Signed & Sealed) ***Gary L. Simmons***

Gary L. Simmons, QP MMSA

30.0 Appendix 1

30.1 Land Tenure

Table 30-1: List of Unpatented Mining Claims, Goldstrike Property, Washington Country, Utah

Claim Name	Location Date	BLM Serial Number	Legacy BLM Serial Number	County Document Number	Case Type
GAP 43	19-Jan-2004	UT101621231	UMC370953	864771	Lode
GAP 44 *Amendment*	19-Jan-2004	UT101621232	UMC370954	864772 *20240030908*	Lode
GAP 45 *Amendment*	19-Jan-2004	UT101621233	UMC370955	864773 *20240030909*	Lode
GAP 46	19-Jan-2004	UT101621234	UMC370956	864774	Lode
GAP 47	19-Jan-2004	UT101621235	UMC370957	864775	Lode
GAP 48	19-Jan-2004	UT101621236	UMC370958	864776	Lode
GAP 49	19-Jan-2004	UT101621237	UMC370959	864777	Lode
GAP 50	19-Jan-2004	UT101621238	UMC370960	864778	Lode
GAP 51	19-Jan-2004	UT101621239	UMC370961	864779	Lode
GAP 52	19-Jan-2004	UT101621822	UMC370962	864780	Lode
GAP 53	19-Jan-2004	UT101621823	UMC370963	864781	Lode
GAP 54	19-Jan-2004	UT101621824	UMC370964	864782	Lode
GAP 55A	7-Nov-2022	UT105804343		20220050602	Lode
GAP 56A	7-Nov-2022	UT105804344		20220050603	Lode
GAP 57A	7-Nov-2022	UT105804345		20220050604	Lode
GAP 58	20-Jan-2004	UT101622223	UMC370968	864786	Lode
GAP 59	19-Jan-2004	UT101622224	UMC370969	864787	Lode
GAP 60	19-Jan-2004	UT101622225	UMC370970	864788	Lode
GAP 61	19-Jan-2004	UT101622226	UMC370971	864789	Lode
GAP 62	19-Jan-2004	UT101622227	UMC370972	864790	Lode
GAP 63	19-Jan-2004	UT101622228	UMC370973	864791	Lode
GAP 64	19-Jan-2004	UT101622229	UMC370974	864792	Lode
GAP 65	19-Jan-2004	UT101622230	UMC370975	864793	Lode
GAP 66	19-Jan-2004	UT101622231	UMC370976	864794	Lode
GAP 67	19-Jan-2004	UT101622232	UMC370977	864795	Lode
GAP 68	19-Jan-2004	UT101622233	UMC370978	864796	Lode

Claim Name	Location Date	BLM Serial Number	Legacy BLM Serial Number	County Document Number	Case Type
GAP 69	19-Jan-2004	UT101622234	UMC370979	864797	Lode
GAP 70	19-Jan-2004	UT101622235	UMC370980	864798	Lode
GAP 71	19-Jan-2004	UT101622236	UMC370981	864799	Lode
GAP 72	19-Jan-2004	UT101622237	UMC370982	864800	Lode
GAP 73	19-Jan-2004	UT101622238	UMC370983	864801	Lode
GAP 74	19-Jan-2004	UT101622239	UMC370984	864802	Lode
GAP 75	19-Jan-2004	UT101622240	UMC370985	864803	Lode
GAP 76	19-Jan-2004	UT101622241	UMC370986	864804	Lode
GAP 77A	7-Nov-2022	UT105804346		20220050605	Lode
GAP 78A	7-Nov-2022	UT105804347		20220050606	Lode
GAP 79A	7-Nov-2022	UT105804348		20220050607	Lode
GAP 80A	7-Nov-2022	UT105804349		20220050608	Lode
GAP 81	20-Jan-2004	UT101622667	UMC370991	864809	Lode
GAP 82	19-Jan-2004	UT101622668	UMC370992	864810	Lode
GAP 83	19-Jan-2004	UT101622669	UMC370993	864811	Lode
GAP 84	19-Jan-2004	UT101622670	UMC370994	864812	Lode
GAP 85	19-Jan-2004	UT101622671	UMC370995	864813	Lode
GAP 86	19-Jan-2004	UT101622672	UMC370996	864814	Lode
GAP 87	20-Jan-2004	UT101622673	UMC370997	864815	Lode
GAP 88	20-Jan-2004	UT101622674	UMC370998	864816	Lode
GAP 89	20-Jan-2004	UT101622675	UMC370999	864817	Lode
GAP 90	20-Jan-2004	UT101622676	UMC371000	864818	Lode
GAP 91	20-Jan-2004	UT101622677	UMC371001	864819	Lode
GAP 92	20-Jan-2004	UT101622678	UMC371002	864820	Lode
GAP 93	20-Jan-2004	UT101622679	UMC371003	864821	Lode
GAP 94	20-Jan-2004	UT101622680	UMC371004	864822	Lode
GAP 95	18-Jan-2004	UT101622681	UMC371005	864823	Lode
GAP 96	18-Jan-2004	UT101622682	UMC371006	864824	Lode
GAP 97	18-Jan-2004	UT101622683	UMC371007	864825	Lode
GAP 98	18-Jan-2004	UT101622684	UMC371008	864826	Lode
GAP 99	18-Jan-2004	UT101624085	UMC371009	864827	Lode
GAP 100	18-Jan-2004	UT101624086	UMC371010	864828	Lode
GAP 101	18-Jan-2004	UT101624087	UMC371011	864829	Lode

Claim Name	Location Date	BLM Serial Number	Legacy BLM Serial Number	County Document Number	Case Type
GAP 102	20-Jan-2004	UT101624088	UMC371012	864830	Lode
GAP 103	20-Jan-2004	UT101624089	UMC371013	864831	Lode
GAP 104	20-Jan-2004	UT101624090	UMC371014	864832	Lode
GAP 105	20-Jan-2004	UT101624091	UMC371015	864833	Lode
GAP 106	20-Jan-2004	UT101624092	UMC371016	864834	Lode
GAP 107	18-Jan-2004	UT101624093	UMC371017	864835	Lode
GAP 108	18-Jan-2004	UT101624094	UMC371018	864836	Lode
GAP 109	18-Jan-2004	UT101624095	UMC371019	864837	Lode
GAP 110	18-Jan-2004	UT101624096	UMC371020	864838	Lode
GAP 111	18-Jan-2004	UT101624097	UMC371021	864839	Lode
GAP 112	18-Jan-2004	UT101624098	UMC371022	864840	Lode
GAP 113	18-Jan-2004	UT101624099	UMC371023	864841	Lode
GAP 114	20-Jan-2004	UT101624100	UMC371024	864842	Lode
GAP 115	20-Jan-2004	UT101624101	UMC371025	864843	Lode
GAP 116	20-Jan-2004	UT101624102	UMC371026	864844	Lode
GAP 117	20-Jan-2004	UT101624103	UMC371027	864845	Lode
GAP 118	20-Jan-2004	UT101624104	UMC371028	864846	Lode
GS 1	29-Oct-2010	UT101651365	UMC410981	20100038964	Lode
GS 2	29-Oct-2010	UT101651366	UMC410982	20100038965	Lode
GS 3	29-Oct-2010	UT101651367	UMC410983	20100038966	Lode
GS 4	29-Oct-2010	UT101651368	UMC410984	20100038967	Lode
GS 5	29-Oct-2010	UT101651369	UMC410985	20100038968	Lode
GS 6	29-Oct-2010	UT101651370	UMC410986	20100038969	Lode
GS 8	29-Oct-2010	UT101651372	UMC410988	20100038971	Lode
GS 9	29-Oct-2010	UT101651373	UMC410989	20100038972	Lode
GS 10	29-Oct-2010	UT101651374	UMC410990	20100038973	Lode
GS 11	29-Oct-2010	UT101651375	UMC410991	20100038974	Lode
GS 12	29-Oct-2010	UT101651376	UMC410992	20100038975	Lode
GS 13	29-Oct-2010	UT101651377	UMC410993	20100038976	Lode
GS 14	29-Oct-2010	UT101652355	UMC410994	20100038977	Lode
GS 15	29-Oct-2010	UT101652356	UMC410995	20100038978	Lode
GS 16	29-Oct-2010	UT101652357	UMC410996	20100038979	Lode
GS 17	29-Oct-2010	UT101652358	UMC410997	20100038980	Lode

Claim Name	Location Date	BLM Serial Number	Legacy BLM Serial Number	County Document Number	Case Type
GS 18	29-Oct-2010	UT101652359	UMC410998	20100038981	Lode
GS 19	29-Oct-2010	UT101652360	UMC410999	20100038982	Lode
GS 20	29-Oct-2010	UT101652361	UMC411000	20100038983	Lode
GS 21	25-Oct-2010	UT101652362	UMC411001	20100038984	Lode
GS 22	25-Oct-2010	UT101652363	UMC411002	20100038985	Lode
GS 23	25-Oct-2010	UT101652364	UMC411003	20100038986	Lode
GS 24	25-Oct-2010	UT101652365	UMC411004	20100038987	Lode
GS 25	25-Oct-2010	UT101652366	UMC411005	20100038988	Lode
GS 26	25-Oct-2010	UT101652367	UMC411006	20100038989	Lode
GS 27	25-Oct-2010	UT101652368	UMC411007	20100038990	Lode
GS 28	25-Oct-2010	UT101652369	UMC411008	20100038991	Lode
GS 29	25-Oct-2010	UT101652370	UMC411009	20100038992	Lode
GS 30	25-Oct-2010	UT101652371	UMC411010	20100038993	Lode
GS 31	25-Oct-2010	UT101652372	UMC411011	20100038994	Lode
GS 32	25-Oct-2010	UT101652373	UMC411012	20100038995	Lode
GS 33	25-Oct-2010	UT101652374	UMC411013	20100038996	Lode
GS 34	25-Oct-2010	UT101652375	UMC411014	20100038997	Lode
GS 35	25-Oct-2010	UT101652376	UMC411015	20100038998	Lode
GS 36	25-Oct-2010	UT101653254	UMC411016	20100038999	Lode
GS 37	25-Oct-2010	UT101653255	UMC411017	20100039000	Lode
GS 38	25-Oct-2010	UT101653256	UMC411018	20100039001	Lode
GS 39	25-Oct-2010	UT101653257	UMC411019	20100039002	Lode
GS 40	25-Oct-2010	UT101653258	UMC411020	20100039003	Lode
GS 41	25-Oct-2010	UT101653259	UMC411021	20100039004	Lode
GS 43	25-Oct-2010	UT101653261	UMC411023	20100039006	Lode
GS 45	25-Oct-2010	UT101653263	UMC411025	20100039008	Lode
GS 47	25-Oct-2010	UT101653265	UMC411027	20100039010	Lode
GS 48	30-Oct-2010	UT101653266	UMC411028	20100039011	Lode
GS 49	30-Oct-2010	UT101653267	UMC411029	20100039012	Lode
GS 50	30-Oct-2010	UT101653268	UMC411030	20100039013	Lode
GS 51	30-Oct-2010	UT101653269	UMC411031	20100039014	Lode
GS 52	30-Oct-2010	UT101653270	UMC411032	20100039015	Lode
GS 53	30-Oct-2010	UT101653271	UMC411033	20100039016	Lode

Claim Name	Location Date	BLM Serial Number	Legacy BLM Serial Number	County Document Number	Case Type
GS 54	29-Oct-2010	UT101653272	UMC411034	20100039017	Lode
GS 55	28-Oct-2010	UT101653273	UMC411035	20100039018	Lode
GS 56	29-Oct-2010	UT101653274	UMC411036	20100039019	Lode
GS 57	28-Oct-2010	UT101628754	UMC411037	20100039020	Lode
GS 58	29-Oct-2010	UT101628755	UMC411038	20100039021	Lode
GS 59	30-Oct-2010	UT101628756	UMC411039	20100039022	Lode
GS 60	29-Oct-2010	UT101628757	UMC411040	20100039023	Lode
GS 61	30-Oct-2010	UT101628758	UMC411041	20100039024	Lode
GS 62	29-Oct-2010	UT101628759	UMC411042	20100039025	Lode
GS 63	30-Oct-2010	UT101628760	UMC411043	20100039026	Lode
GS 64	29-Oct-2010	UT101628761	UMC411044	20100039027	Lode
GS 65	29-Oct-2010	UT101628762	UMC411045	20100039028	Lode
GS 66	29-Oct-2010	UT101628763	UMC411046	20100039029	Lode
GS 67	24-Oct-2010	UT101628764	UMC411047	20100039030	Lode
GS 68	24-Oct-2010	UT101628765	UMC411048	20100039031	Lode
GS 69	24-Oct-2010	UT101628766	UMC411049	20100039032	Lode
GS 70	24-Oct-2010	UT101628767	UMC411050	20100039033	Lode
GS 71	24-Oct-2010	UT101628768	UMC411051	20100039034	Lode
GS 72	24-Oct-2010	UT101628769	UMC411052	20100039035	Lode
GS 73	24-Oct-2010	UT101628770	UMC411053	20100039036	Lode
GS 74	24-Oct-2010	UT101628771	UMC411054	20100039037	Lode
GS 75	24-Oct-2010	UT101628772	UMC411055	20100039038	Lode
GS 76	24-Oct-2010	UT101628773	UMC411056	20100039039	Lode
GS 77	24-Oct-2010	UT101628774	UMC411057	20100039040	Lode
GS 78	24-Oct-2010	UT101628775	UMC411058	20100039041	Lode
GS 79	24-Oct-2010	UT101629755	UMC411059	20100039042	Lode
GS 80	24-Oct-2010	UT101629756	UMC411060	20100039043	Lode
GS 81	24-Oct-2010	UT101629757	UMC411061	20100039044	Lode
GS 82	24-Oct-2010	UT101629758	UMC411062	20100039045	Lode
GS 83	24-Oct-2010	UT101629759	UMC411063	20100039046	Lode
GS 84	24-Oct-2010	UT101629760	UMC411064	20100039047	Lode
GS 85	24-Oct-2010	UT101629761	UMC411065	20100039048	Lode
GS 86	24-Oct-2010	UT101629762	UMC411066	20100039049	Lode

Claim Name	Location Date	BLM Serial Number	Legacy BLM Serial Number	County Document Number	Case Type
GS 87	24-Oct-2010	UT101629763	UMC411067	20100039050	Lode
GS 88	24-Oct-2010	UT101629764	UMC411068	20100039051	Lode
GS 89	24-Oct-2010	UT101629765	UMC411069	20100039052	Lode
GS 90	24-Oct-2010	UT101629766	UMC411070	20100039053	Lode
GS 91	24-Oct-2010	UT101629767	UMC411071	20100039054	Lode
GS 92	24-Oct-2010	UT101629768	UMC411072	20100039055	Lode
GS 93	24-Oct-2010	UT101629769	UMC411073	20100039056	Lode
GS 94	24-Oct-2010	UT101629770	UMC411074	20100039057	Lode
GS 95	24-Oct-2010	UT101629771	UMC411075	20100039058	Lode
GS 96	1-Jun-2014	UT101354953	UMC423123	20140019231	Lode
GS 97	1-Jun-2014	UT101354954	UMC423124	20140019232	Lode
GS 98	1-Jun-2014	UT101354955	UMC423125	20140019233	Lode
GS 99	30-Oct-2010	UT101629772	UMC411079	20100039062	Lode
GS 100	30-Oct-2010	UT101629773	UMC411080	20100039063	Lode
GS 101	30-Oct-2010	UT101629774	UMC411081	20100039064	Lode
GS 102	30-Oct-2010	UT101629775	UMC411082	20100039065	Lode
GS 103	30-Oct-2010	UT101670749	UMC411083	20100039066	Lode
GS 104	30-Oct-2010	UT101670750	UMC411084	20100039067	Lode
GS 105	30-Oct-2010	UT101670751	UMC411085	20100039068	Lode
GS 106	30-Oct-2010	UT101670752	UMC411086	20100039069	Lode
GS 107	28-Oct-2010	UT101670753	UMC411087	20100039070	Lode
GS 108	27-Oct-2010	UT101670754	UMC411088	20100039071	Lode
GS 109	28-Oct-2010	UT101670755	UMC411089	20100039072	Lode
GS 110	27-Oct-2010	UT101670756	UMC411090	20100039073	Lode
GS 111	27-Oct-2010	UT101670757	UMC411091	20100039074	Lode
GS 112	27-Oct-2010	UT101670758	UMC411092	20100039075	Lode
GS 113	27-Oct-2010	UT101670759	UMC411093	20100039076	Lode
GS 114	27-Oct-2010	UT101670760	UMC411094	20100039077	Lode
GS 115	27-Oct-2010	UT101670761	UMC411095	20100039078	Lode
GS 116	27-Oct-2010	UT101670762	UMC411096	20100039079	Lode
GS 117	27-Oct-2010	UT101670763	UMC411097	20100039080	Lode
GS 118	27-Oct-2010	UT101670764	UMC411098	20100039081	Lode
GS 119	27-Oct-2010	UT101670765	UMC411099	20100039082	Lode

Claim Name	Location Date	BLM Serial Number	Legacy BLM Serial Number	County Document Number	Case Type
GS 120	27-Oct-2010	UT101670766	UMC411100	20100039083	Lode
GS 121	26-Oct-2010	UT101670767	UMC411101	20100039084	Lode
GS 122	26-Oct-2010	UT101670768	UMC411102	20100039085	Lode
GS 123	20-Mar-2015	UT101758566	UMC425542	20150012468	Lode
GS 124	26-Oct-2010	UT101670769	UMC411104	20100039087	Lode
GS 125	26-Oct-2010	UT101671716	UMC411105	20100039088	Lode
GS 126	26-Oct-2010	UT101671717	UMC411106	20100039089	Lode
GS 127	26-Oct-2010	UT101671718	UMC411107	20100039090	Lode
GS 128	26-Oct-2010	UT101671719	UMC411108	20100039091	Lode
GS 129	26-Oct-2010	UT101671720	UMC411109	20100039092	Lode
GS 130	26-Oct-2010	UT101671721	UMC411110	20100039093	Lode
GS 131	26-Oct-2010	UT101671722	UMC411111	20100039094	Lode
GS 132	26-Oct-2010	UT101671723	UMC411112	20100039095	Lode
GS 133	26-Oct-2010	UT101671724	UMC411113	20100039096	Lode
GS 134	26-Oct-2010	UT101671725	UMC411114	20100039097	Lode
GS 135	26-Oct-2010	UT101671726	UMC411115	20100039098	Lode
GS 136	26-Oct-2010	UT101671727	UMC411116	20100039099	Lode
GS 137	26-Oct-2010	UT101671728	UMC411117	20100039100	Lode
GS 138	26-Oct-2010	UT101671729	UMC411118	20100039101	Lode
GS 139	26-Oct-2010	UT101671730	UMC411119	20100039102	Lode
GS 140	26-Oct-2010	UT101671731	UMC411120	20100039103	Lode
GS 141	28-Oct-2010	UT101671732	UMC411121	20100039104	Lode
GS 142	28-Oct-2010	UT101671733	UMC411122	20100039105	Lode
GS 143	28-Oct-2010	UT101671734	UMC411123	20100039106	Lode
GS 144	28-Oct-2010	UT101671735	UMC411124	20100039107	Lode
GS 145	28-Oct-2010	UT101671736	UMC411125	20100039108	Lode
GS 146	28-Oct-2010	UT101672625	UMC411126	20100039109	Lode
GS 147	28-Oct-2010	UT101672626	UMC411127	20100039110	Lode
GS 148	28-Oct-2010	UT101672627	UMC411128	20100039111	Lode
GS 149	28-Oct-2010	UT101672628	UMC411129	20100039112	Lode
GS 150	28-Oct-2010	UT101672629	UMC411130	20100039113	Lode
GS 151	28-Oct-2010	UT101672630	UMC411131	20100039114	Lode
GS 152	28-Oct-2010	UT101672631	UMC411132	20100039115	Lode

Claim Name	Location Date	BLM Serial Number	Legacy BLM Serial Number	County Document Number	Case Type
GS 153	28-Oct-2010	UT101672632	UMC411133	20100039116	Lode
GS 154	28-Oct-2010	UT101672633	UMC411134	20100039117	Lode
GS 155	28-Oct-2010	UT101672634	UMC411135	20100039118	Lode
GS 156	28-Oct-2010	UT101672635	UMC411136	20100039119	Lode
GS 157	28-Oct-2010	UT101672636	UMC411137	20100039120	Lode
GS 158	28-Oct-2010	UT101672637	UMC411138	20100039121	Lode
GS 159	28-Oct-2010	UT101672638	UMC411139	20100039122	Lode
GS 160	28-Oct-2010	UT101672639	UMC411140	20100039123	Lode
GS 161	28-Oct-2010	UT101672640	UMC411141	20100039124	Lode
GS 162	28-Oct-2010	UT101672641	UMC411142	20100039125	Lode
GS 163	28-Oct-2010	UT101672642	UMC411143	20100039126	Lode
GS 164	6-May-2011	UT101426900	UMC413524	20110016713	Lode
GS 165	6-May-2011	UT101426901	UMC413525	20110016714	Lode
GS 166	6-May-2011	UT101426902	UMC413526	20110016715	Lode
GS 167	7-May-2011	UT101426903	UMC413527	20110016716	Lode
GS 168	7-May-2011	UT101426904	UMC413528	20110016717	Lode
GS 169	7-May-2011	UT101426905	UMC413529	20110016718	Lode
GS 170	7-May-2011	UT101426906	UMC413530	20110016719	Lode
GS 171	7-May-2011	UT101426907	UMC413531	20110016720	Lode
GS 172	7-May-2011	UT101426908	UMC413532	20110016721	Lode
GS 173	7-May-2011	UT101426909	UMC413533	20110016722	Lode
GS 174	7-May-2011	UT101426910	UMC413534	20110016723	Lode
GS 175	7-May-2011	UT101426911	UMC413535	20110016724	Lode
GS 176	7-May-2011	UT101426912	UMC413536	20110016725	Lode
GS 177	7-May-2011	UT101426913	UMC413537	20110016726	Lode
GS 178	7-May-2011	UT101426914	UMC413538	20110016727	Lode
GS 179	7-May-2011	UT101427042	UMC413539	20110016728	Lode
GS 180	7-May-2011	UT101427043	UMC413540	20110016729	Lode
GS 181A	27-Mar-2018	UT101831648	UMC440070	20180016001	Lode
GS 182A	27-Mar-2018	UT101831649	UMC440071	20180016002	Lode
GS 183A	27-Mar-2018	UT101831650	UMC440072	20180016003	Lode
GS 184A	27-Mar-2018	UT101831651	UMC440073	20180016004	Lode
GS 185A	27-Mar-2018	UT101831652	UMC440074	20180016005	Lode

Claim Name	Location Date	BLM Serial Number	Legacy BLM Serial Number	County Document Number	Case Type
GS 186	10-May-2011	UT101427044	UMC413546	20110016735	Lode
GS 187	10-May-2011	UT101427045	UMC413547	20110016736	Lode
GS 188	10-May-2011	UT101427046	UMC413548	20110016737	Lode
GS 189	10-May-2011	UT101427047	UMC413549	20110016738	Lode
GS 190	10-May-2011	UT101427048	UMC413550	20110016739	Lode
GS 191	10-May-2011	UT101427049	UMC413551	20110016740	Lode
GS 192	10-May-2011	UT101427050	UMC413552	20110016741	Lode
GS 193	10-May-2011	UT101427051	UMC413553	20110016742	Lode
GS 194	10-May-2011	UT101427052	UMC413554	20110016743	Lode
GS 195	10-May-2011	UT101427053	UMC413555	20110016744	Lode
GS 196	10-May-2011	UT101427054	UMC413556	20110016745	Lode
GS 197	9-May-2011	UT101427055	UMC413557	20110016746	Lode
GS 198	9-May-2011	UT101427056	UMC413558	20110016747	Lode
GS 199	9-May-2011	UT101427057	UMC413559	20110016748	Lode
GS 200	9-May-2011	UT101427058	UMC413560	20110016749	Lode
GS 201	9-May-2011	UT101427059	UMC413561	20110016750	Lode
GS 202	8-May-2011	UT101427060	UMC413562	20110016751	Lode
GS 203	8-May-2011	UT101427061	UMC413563	20110016752	Lode
GS 204	8-May-2011	UT101427062	UMC413564	20110016753	Lode
GS 205	8-May-2011	UT101427243	UMC413565	20110016754	Lode
GS 206	8-May-2011	UT101427244	UMC413566	20110016755	Lode
GS 207	7-May-2011	UT101427245	UMC413567	20110016756	Lode
GS 208	7-May-2011	UT101427246	UMC413568	20110016757	Lode
GS 209	3-Jun-2014	UT101354956	UMC423126	20140019234	Lode
GS 210	3-Jun-2014	UT101354957	UMC423127	20140019235	Lode
GS 211	3-Jun-2014	UT101354958	UMC423128	20140019236	Lode
GS 212	3-Jun-2014	UT101355912	UMC423129	20140019237	Lode
GS 213	3-Jun-2014	UT101355913	UMC423130	20140019238	Lode
GS 214	3-Jun-2014	UT101355914	UMC423131	20140019239	Lode
GS 215	3-Jun-2014	UT101355915	UMC423132	20140019240	Lode
GS 216	3-Jun-2014	UT101355916	UMC423133	20140019241	Lode
GS 217A	3-Apr-2018	UT101831653	UMC440075	20180016006	Lode
GS 218	3-Jun-2014	UT101355917	UMC423135	20140019243	Lode

Claim Name	Location Date	BLM Serial Number	Legacy BLM Serial Number	County Document Number	Case Type
GS 219A	10-Oct-2016	UT101569228	UMC428738	20160042212	Lode
GS 220A	10-Oct-2016	UT101569229	UMC428739	20160042213	Lode
GS 221B	2-Apr-2018	UT101831654	UMC440076	20180016007	Lode
GS 222B	31-Mar-2018	UT101831655	UMC440077	20180016008	Lode
GS 223B	31-Mar-2018	UT101832167	UMC440078	20180016009	Lode
GS 224B	31-Mar-2018	UT101832168	UMC440079	20180016010	Lode
GS 225A	10-Oct-2016	UT101569230	UMC428744	20160042218	Lode
GS 226A	10-Oct-2016	UT101569231	UMC428745	20160042219	Lode
GS 227A	10-Oct-2016	UT101569232	UMC428746	20160042220	Lode
GS 228A	10-Oct-2016	UT101569233	UMC428747	20160042221	Lode
GS 229A	10-Oct-2016	UT101569234	UMC428748	20160042222	Lode
GS 230A	10-Oct-2016	UT101569235	UMC428749	20160042223	Lode
GS 231A	10-Oct-2016	UT101569236	UMC428750	20160042224	Lode
GS 232A	10-Oct-2016	UT101569237	UMC428751	20160042225	Lode
GS 233A	10-Oct-2016	UT101569238	UMC428752	20160042226	Lode
GS 234A	10-Oct-2016	UT101569239	UMC428753	20160042227	Lode
GS 235A	10-Oct-2016	UT101569240	UMC428754	20160042228	Lode
GS 236A	10-Oct-2016	UT101569241	UMC428755	20160042229	Lode
GS 237A	10-Oct-2016	UT101569242	UMC428756	20160042230	Lode
GS 238A	10-Oct-2016	UT101890635	UMC428757	20160042231	Lode
GS 239A	16-Oct-2016	UT101890636	UMC428758	20160042232	Lode
GS 240A	10-Oct-2016	UT101890637	UMC428759	20160042233	Lode
GS 241A	16-Oct-2016	UT101890638	UMC428760	20160042234	Lode
GS 242A	16-Oct-2016	UT101890639	UMC428761	20160042235	Lode
GS 243A	16-Oct-2016	UT101890640	UMC428762	20160042236	Lode
GS 244A	16-Oct-2016	UT101890641	UMC428763	20160042237	Lode
GS 245A	7-Nov-2022	UT105804350		20220050609	Lode
GS 246A	7-Nov-2022	UT105804351		20220050610	Lode
GS 247A	7-Nov-2022	UT105804352		20220050611	Lode
GS 248A	7-Nov-2022	UT105804353		20220050612	Lode
GS 249A	7-Nov-2022	UT105804354		20220050613	Lode
GS 250	31-May-2014	UT101355923	UMC423167	20140019275	Lode
GS 251	31-May-2014	UT101355924	UMC423168	20140019276	Lode

Claim Name	Location Date	BLM Serial Number	Legacy BLM Serial Number	County Document Number	Case Type
GS 252	31-May-2014	UT101355925	UMC423169	20140019277	Lode
GS 253	31-May-2014	UT101355926	UMC423170	20140019278	Lode
GS 254	31-May-2014	UT101355927	UMC423171	20140019279	Lode
GS 255	31-May-2014	UT101355928	UMC423172	20140019280	Lode
GS 256	31-May-2014	UT101355929	UMC423173	20140019281	Lode
GS 257A	23-Jun-2016	UT101644542	UMC426736	20160026083	Lode
GS 258A	23-Jun-2016	UT101644543	UMC426737	20160026084	Lode
GS 259B	7-Nov-2022	UT105804355		20220050614	Lode
GS 260	1-Jun-2014	UT101355930	UMC423177	20140019285	Lode
GS 261A	7-Nov-2022	UT105804356		20220050615	Lode
GS 262	1-Jun-2014	UT101355932	UMC423179	20140019287	Lode
GS 263	1-Jun-2014	UT101356904	UMC423180	20140019288	Lode
GS 264	1-Jun-2014	UT101356905	UMC423181	20140019289	Lode
GS 265	1-Jun-2014	UT101356906	UMC423182	20140019290	Lode
GS 266	1-Jun-2014	UT101356907	UMC423183	20140019291	Lode
GS 267	1-Jun-2014	UT101356908	UMC423184	20140019292	Lode
GS 268	1-Jun-2014	UT101356909	UMC423185	20140019293	Lode
GS 269	1-Jun-2014	UT101356910	UMC423186	20140019294	Lode
GS 270	1-Jun-2014	UT101356911	UMC423187	20140019295	Lode
GS 271	1-Jun-2014	UT101356912	UMC423188	20140019296	Lode
GS 272	1-Jun-2014	UT101356913	UMC423189	20140019297	Lode
GS 273	1-Jun-2014	UT101356914	UMC423190	20140019298	Lode
GS 274	1-Jun-2014	UT101356915	UMC423191	20140019299	Lode
GS 275	1-Jun-2014	UT101356916	UMC423192	20140019300	Lode
GS 276	1-Jun-2014	UT101356917	UMC423193	20140019301	Lode
GS 277A	23-Jun-2016	UT101644545	UMC426739	20160026086	Lode
GS 278	1-Jun-2014	UT101356918	UMC423195	20140019303	Lode
GS 279	1-Jun-2014	UT101356919	UMC423196	20140019304	Lode
GS 280	1-Jun-2014	UT101356920	UMC423197	20140019305	Lode
GS 281	1-Jun-2014	UT101356921	UMC423198	20140019306	Lode
GS 282	1-Jun-2014	UT101356922	UMC423199	20140019307	Lode
GS 283	1-Jun-2014	UT101356923	UMC423200	20140019308	Lode
GS 284	1-Jun-2014	UT101356924	UMC423201	20140019309	Lode

Claim Name	Location Date	BLM Serial Number	Legacy BLM Serial Number	County Document Number	Case Type
GS 285	1-Jun-2014	UT101357900	UMC423202	20140019310	Lode
GS 286	1-Jun-2014	UT101357901	UMC423203	20140019311	Lode
GS 287	1-Jun-2014	UT101357902	UMC423204	20140019312	Lode
GS 288	1-Jun-2014	UT101357903	UMC423205	20140019313	Lode
GS 289	1-Jun-2014	UT101357904	UMC423206	20140019314	Lode
GS 290	1-Jun-2014	UT101357905	UMC423207	20140019315	Lode
GS 291	1-Jun-2014	UT101357906	UMC423208	20140019316	Lode
GS 292	1-Jun-2014	UT101357907	UMC423209	20140019317	Lode
GS 293	1-Jun-2014	UT101357908	UMC423210	20140019318	Lode
GS 294	1-Jun-2014	UT101357909	UMC423211	20140019319	Lode
GS 295	1-Jun-2014	UT101357910	UMC423212	20140019320	Lode
GS 296	1-Jun-2014	UT101357911	UMC423213	20140019321	Lode
GS 297	1-Jun-2014	UT101357912	UMC423214	20140019322	Lode
GS 298	1-Jun-2014	UT101357913	UMC423215	20140019323	Lode
GS 299	1-Jun-2014	UT101357914	UMC423216	20140019324	Lode
GS 300	1-Jun-2014	UT101357915	UMC423217	20140019325	Lode
GS 301	1-Jun-2014	UT101357916	UMC423218	20140019326	Lode
GS 302	1-Jun-2014	UT101357917	UMC423219	20140019327	Lode
GS 303	1-Jun-2014	UT101357918	UMC423220	20140019328	Lode
GS 304	1-Jun-2014	UT101357919	UMC423221	20140019329	Lode
GS 305	1-Jun-2014	UT101357920	UMC423222	20140019330	Lode
GS 306	1-Jun-2014	UT101358903	UMC423223	20140019331	Lode
GS 307	1-Jun-2014	UT101358904	UMC423224	20140019332	Lode
GS 308	1-Jun-2014	UT101358905	UMC423225	20140019333	Lode
GS 309	1-Jun-2014	UT101358906	UMC423226	20140019334	Lode
GS 310	1-Jun-2014	UT101358907	UMC423227	20140019335	Lode
GS 311	1-Jun-2014	UT101358908	UMC423228	20140019336	Lode
GS 312	1-Jun-2014	UT101358909	UMC423229	20140019337	Lode
GS 313	1-Jun-2014	UT101358910	UMC423230	20140019338	Lode
GS 314	1-Jun-2014	UT101358911	UMC423231	20140019339	Lode
GS 315	1-Jun-2014	UT101358912	UMC423232	20140019340	Lode
GS 316	1-Jun-2014	UT101358913	UMC423233	20140019341	Lode
GS 317	1-Jun-2014	UT101358914	UMC423234	20140019342	Lode

Claim Name	Location Date	BLM Serial Number	Legacy BLM Serial Number	County Document Number	Case Type
GS 318	1-Jun-2014	UT101358915	UMC423235	20140019343	Lode
GS 319	1-Jun-2014	UT101358916	UMC423236	20140019344	Lode
GS 320A	7-Nov-2022	UT105804357		20220050616	Lode
GS 321	1-Jun-2014	UT101358918	UMC423238	20140019346	Lode
GS 322A	7-Nov-2022	UT105804358		20220050617	Lode
GS 323	1-Jun-2014	UT101358920	UMC423240	20140019348	Lode
GS 324A	7-Nov-2022	UT105804359		20220050618	Lode
GS 325A	7-Nov-2022	UT105804360		20220050619	Lode
GS 326A	7-Nov-2022	UT105804361		20220050620	Lode
GS 327	2-Jun-2014	UT101359921	UMC423244	20140019352	Lode
GS 329	2-Jun-2014	UT101359923	UMC423246	20140019354	Lode
GS 331	2-Jun-2014	UT101359925	UMC423248	20140019356	Lode
GS 339	2-Jun-2014	UT101359933	UMC423256	20140019364	Lode
GS 340	2-Jun-2014	UT101359934	UMC423257	20140019365	Lode
GS 341	2-Jun-2014	UT101359935	UMC423258	20140019366	Lode
GS 342	2-Jun-2014	UT101359936	UMC423259	20140019367	Lode
GS 343	2-Jun-2014	UT101359937	UMC423260	20140019368	Lode
GS 344	2-Jun-2014	UT101359938	UMC423261	20140019369	Lode
GS 345	2-Jun-2014	UT101359939	UMC423262	20140019370	Lode
GS 346	2-Jun-2014	UT101359940	UMC423263	20140019371	Lode
GS 347	2-Jun-2014	UT101359941	UMC423264	20140019372	Lode
GS 348	2-Jun-2014	UT101450929	UMC423265	20140019373	Lode
GS 349	2-Jun-2014	UT101450930	UMC423266	20140019374	Lode
GS 350	2-Jun-2014	UT101450931	UMC423267	20140019375	Lode
GS 351	2-Jun-2014	UT101450932	UMC423268	20140019376	Lode
GS 352	2-Jun-2014	UT101450933	UMC423269	20140019377	Lode
GS 353	2-Jun-2014	UT101450934	UMC423270	20140019378	Lode
GS 354	2-Jun-2014	UT101450935	UMC423271	20140019379	Lode
GS 377	2-Jun-2014	UT101486079	UMC423294	20140019402	Lode
GS 378	2-Jun-2014	UT101486080	UMC423295	20140019403	Lode
GS 379	2-Jun-2014	UT101486081	UMC423296	20140019404	Lode
GS 381	2-Jun-2014	UT101486083	UMC423298	20140019406	Lode
GS 383	2-Jun-2014	UT101486085	UMC423300	20140019408	Lode

Claim Name	Location Date	BLM Serial Number	Legacy BLM Serial Number	County Document Number	Case Type
GS 385	2-Jun-2014	UT101486087	UMC423302	20140019410	Lode
GS 386	2-Jun-2014	UT101486088	UMC423303	20140019411	Lode
GS 387	2-Jun-2014	UT101486089	UMC423304	20140019412	Lode
GS 388	2-Jun-2014	UT101486090	UMC423305	20140019413	Lode
GS 389	2-Jun-2014	UT101486091	UMC423306	20140019414	Lode
GS 390	2-Jun-2014	UT101487075	UMC423307	20140019415	Lode
GS 401	2-Jun-2014	UT101487085	UMC423318	20140019426	Lode
GS 402	2-Jun-2014	UT101487086	UMC423319	20140019427	Lode
GS 469	25-Sep-2014	UT101351325	UMC424119	20140032451	Lode
GS 470	25-Sep-2014	UT101351326	UMC424120	20140032452	Lode
GS 472	25-Sep-2014	UT101351327	UMC424121	20140032453	Lode
GS 474	25-Sep-2014	UT101351328	UMC424122	20140032454	Lode
GS 476	25-Sep-2014	UT101351329	UMC424123	20140032455	Lode
GS 478	25-Sep-2014	UT101351330	UMC424124	20140032456	Lode
GS 480	25-Sep-2014	UT101351331	UMC424125	20140032457	Lode
GS 482	25-Sep-2014	UT101351332	UMC424126	20140032458	Lode
GS 484	25-Sep-2014	UT101351333	UMC424127	20140032459	Lode
GS 486	25-Sep-2014	UT101351334	UMC424128	20140032460	Lode
GS 489 *amendment*	7-Sep-2014	UT101351336	UMC424130	20140030274 *20150024312*	Lode
GS 490 *amendment*	7-Sep-2014	UT101352317	UMC424131	20140030275 *20150020389*	Lode
GS 491 *amendment*	7-Sep-2014	UT101352318	UMC424132	20140030276 *20150020390*	Lode
GS 492 *amendment*	7-Sep-2014	UT101352319	UMC424133	20140030277 *20150020391*	Lode
GS 493 *amendment*	7-Sep-2014	UT101352320	UMC424134	20140030278 *20150020392*	Lode
GS 494 *amendment*	7-Sep-2014	UT101352321	UMC424135	20140030279 *20150020393*	Lode
GS 495 *amendment*	7-Sep-2014	UT101352322	UMC424136	20140030280 *20150020394*	Lode
GS 496 *amendment*	7-Sep-2014	UT101352323	UMC424137	20140030281 *20150020395*	Lode

Claim Name	Location Date	BLM Serial Number	Legacy BLM Serial Number	County Document Number	Case Type
GS 497 *amendment*	7-Sep-2014	UT101352324	UMC424138	20140030282 *20150020396*	Lode
GS 498 *amendment*	7-Sep-2014	UT101352325	UMC424139	20140030283 *20150020397*	Lode
GS 499 *amendment*	7-Sep-2014	UT101352326	UMC424140	20140030284 *20150020398*	Lode
GS 500 *amendment*	7-Sep-2014	UT101352327	UMC424141	20140030285 *20150020399*	Lode
GS 501 *amendment*	7-Sep-2014	UT101352328	UMC424142	20140030286 *20150020400*	Lode
GS 502 *amendment*	7-Sep-2014	UT101352329	UMC424143	20140030287 *20150020401*	Lode
GS 503 *amendment*	7-Sep-2014	UT101352330	UMC424144	20140030288 *20150020402*	Lode
GS 504 *amendment*	7-Sep-2014	UT101352331	UMC424145	20140030289 *20150020403*	Lode
GS 505 *amendment*	7-Sep-2014	UT101352332	UMC424146	20140030290 *20150020404*	Lode
GS 506 *amendment*	7-Sep-2014	UT101352333	UMC424147	20140030291 *20150020405*	Lode
GS 507 *amendment*	7-Sep-2014	UT101352334	UMC424148	20140030292 *20150020406*	Lode
GS 508 *amendment*	7-Sep-2014	UT101352335	UMC424149	20140030293 *20150020407*	Lode
GS 510A	4-Sep-2024	UT106696276		20240030910	Lode
GS 512	25-Sep-2014	UT101353317	UMC424152	20140032464	Lode
GS 514	25-Sep-2014	UT101353318	UMC424153	20140032465	Lode
GS 516	25-Sep-2014	UT101353319	UMC424154	20140032466	Lode
GS 518	25-Sep-2014	UT101353320	UMC424155	20140032467	Lode
GS 520	25-Sep-2014	UT101353321	UMC424156	20140032468	Lode
GS 522	25-Sep-2014	UT101353322	UMC424157	20140032469	Lode
GS 524	25-Sep-2014	UT101353323	UMC424158	20140032470	Lode
GS 526	25-Sep-2014	UT101353324	UMC424159	20140032471	Lode
GS 528	25-Sep-2014	UT101353325	UMC424160	20140032472	Lode
GS 530	25-Sep-2014	UT101353326	UMC424161	20140032473	Lode

Claim Name	Location Date	BLM Serial Number	Legacy BLM Serial Number	County Document Number	Case Type
GS 532	25-Sep-2014	UT101353327	UMC424162	20140032474	Lode
GS 534	25-Sep-2014	UT101353328	UMC424163	20140032475	Lode
GS 536	25-Sep-2014	UT101353329	UMC424164	20140032476	Lode
GS 538	25-Sep-2014	UT101353330	UMC424165	20140032477	Lode
GS 567 *amendment*	7-Sep-2014	UT101353331	UMC424166	20140030294 *20150020408*	Lode
GS 568 *amendment*	7-Sep-2014	UT101353332	UMC424167	20140030295 *20150020409*	Lode
GS 569	25-Sep-2014	UT101353333	UMC424168	20140032478	Lode
GS 570	25-Sep-2014	UT101353334	UMC424169	20140032479	Lode
GS 571	25-Sep-2014	UT101353335	UMC424170	20140032480	Lode
GS 572	18-Mar-2015	UT101758567	UMC425543	20150012469	Lode
GS 573	18-Mar-2015	UT101758568	UMC425544	20150012470	Lode
GS 575	19-Mar-2015	UT101758569	UMC425545	20150012471	Lode
GS 576A	27-Mar-2018	UT101832169	UMC440080	20180016011	Lode
GS 580	23-Feb-2016	UT101334683	UMC426324	20160008536	Lode
GS 581	23-Feb-2016	UT101334684	UMC426325	20160008537	Lode
GS 582	23-Feb-2016	UT101334685	UMC426326	20160008538	Lode
GS 583	23-Feb-2016	UT101334686	UMC426327	20160008539	Lode
GS 584	23-Feb-2016	UT101334687	UMC426328	20160008540	Lode
GS 585	23-Feb-2016	UT101334688	UMC426329	20160008541	Lode
GS 586	24-Feb-2016	UT101334689	UMC426330	20160008542	Lode
GS 590A	7-Nov-2022	UT105804362		20220050621	Lode
GS 591A	7-Nov-2022	UT105804363		20220050622	Lode
GS 592A	7-Nov-2022	UT105804364		20220050623	Lode
GS 593A	7-Nov-2022	UT105804365		20220050624	Lode
GS 594A	7-Nov-2022	UT105804366		20220050625	Lode
GS 595A	7-Nov-2022	UT105804367		20220050626	Lode
GS 596	23-Jun-2016	UT101644552	UMC426746	20160026093	Lode
GS 597	23-Jun-2016	UT101644553	UMC426747	20160026094	Lode
GS 598	23-Jun-2016	UT101644554	UMC426748	20160026095	Lode
GS 599	23-Jun-2016	UT101644555	UMC426749	20160026096	Lode
GS 600	23-Jun-2016	UT101644556	UMC426750	20160026097	Lode

Claim Name	Location Date	BLM Serial Number	Legacy BLM Serial Number	County Document Number	Case Type
GS 601	31-Jul-2016	UT101644557	UMC426751	20160028283	Lode
GS 602	31-Jul-2016	UT101645730	UMC426752	20160028284	Lode
GS 603	31-Jul-2016	UT101645731	UMC426753	20160028285	Lode
GS 604	31-Jul-2016	UT101645732	UMC426754	20160028286	Lode
GS 605	31-Jul-2016	UT101645733	UMC426755	20160028287	Lode
GS 606	31-Jul-2016	UT101645734	UMC426756	20160028288	Lode
GS 607	31-Jul-2016	UT101645735	UMC426757	20160028289	Lode
GS 608	31-Jul-2016	UT101645736	UMC426758	20160028290	Lode
GS 609	31-Jul-2016	UT101645737	UMC426759	20160028374	Lode
GS 610	31-Jul-2016	UT101645738	UMC426760	20160028375	Lode
GS 611	31-Jul-2016	UT101645739	UMC426761	20160028376	Lode
GS 612	31-Jul-2016	UT101645740	UMC426762	20160028377	Lode
GS 613	31-Jul-2016	UT101645741	UMC426763	20160028378	Lode
GS 614	31-Jul-2016	UT101645742	UMC426764	20160028362	Lode
GS 615	31-Jul-2016	UT101645743	UMC426765	20160028363	Lode
GS 616	31-Jul-2016	UT101645744	UMC426766	20160028364	Lode
GS 617	31-Jul-2016	UT101645745	UMC426767	20160028365	Lode
GS 618	31-Jul-2016	UT101645746	UMC426768	20160028366	Lode
GS 619	31-Jul-2016	UT101645747	UMC426769	20160028367	Lode
GS 620	31-Jul-2016	UT101645748	UMC426770	20160028368	Lode
GS 718	3-Apr-2018	UT101832170	UMC440081	20180016012	Lode
GS 719	3-Apr-2018	UT101832171	UMC440082	20180016013	Lode
GS 720	2-Apr-2018	UT101832172	UMC440083	20180016014	Lode
GS 721	31-Mar-2018	UT101832173	UMC440084	20180016015	Lode
GS 722	8-Nov-2022	UT105804337		20220050596	Lode
GS 723	8-Nov-2022	UT105804338		20220050597	Lode
GS 724	8-Nov-2022	UT105804339		20220050598	Lode
GS 725	8-Nov-2022	UT105804340		20220050599	Lode
GS 726	8-Nov-2022	UT105804341		20220050600	Lode
GS 727	8-Nov-2022	UT105804342		20220050601	Lode
GS 729	4-Sep-2024	UT106696277		20240030911	Lode
GS 730	4-Sep-2024	UT106696278		20240030912	Lode
GS 731	4-Sep-2024	UT106696279		20240030913	Lode

Claim Name	Location Date	BLM Serial Number	Legacy BLM Serial Number	County Document Number	Case Type
GS 732	4-Sep-2024	UT106696280		20240030914	Lode
GS 733	4-Sep-2024	UT106696281		20240030915	Lode
GS 734	4-Sep-2024	UT106696282		20240030916	Lode
GS 735	4-Sep-2024	UT106696283		20240030917	Lode
GS 736	4-Sep-2024	UT106696284		20240030918	Lode
GS 737	4-Sep-2024	UT106696285		20240030919	Lode
GS 738	4-Sep-2024	UT106696286		20240030920	Lode
GS 739	4-Sep-2024	UT106696287		20240030921	Lode
GS 740	4-Sep-2024	UT106696288		20240030922	Lode
GS 741	4-Sep-2024	UT106696289		20240030923	Lode
GS 742	4-Sep-2024	UT106696290		20240030924	Lode
GS 743	4-Sep-2024	UT106696291		20240030925	Lode
GS 744	4-Sep-2024	UT106696292		20240030926	Lode
GS 745	4-Sep-2024	UT106696293		20240030927	Lode
GS 746	4-Sep-2024	UT106696294		20240030928	Lode
GS 747	3-Sep-2024	UT106696295		20240030929	Lode
GS 748	3-Sep-2024	UT106696296		20240030930	Lode
GS 749	3-Sep-2024	UT106696297		20240030931	Lode
GS 750	3-Sep-2024	UT106696298		20240030932	Lode
GS 751	3-Sep-2024	UT106696299		20240030933	Lode
GS 752	3-Sep-2024	UT106696300		20240030934	Lode
GS 753	3-Sep-2024	UT106696301		20240030935	Lode
GS 754	3-Sep-2024	UT106696302		20240030936	Lode
GS 755	4-Sep-2024	UT106696303		20240030937	Lode
GS 756	4-Sep-2024	UT106696304		20240030938	Lode
GS 757	4-Sep-2024	UT106696305		20240030939	Lode
GS 758	4-Sep-2024	UT106696306		20240030940	Lode
GS 759	3-Sep-2024	UT106696307		20240030941	Lode
GS 760	3-Sep-2024	UT106696308		20240030942	Lode
GS 761	3-Sep-2024	UT106696309		20240030943	Lode
GS 762	3-Sep-2024	UT106696310		20240030944	Lode
GS 763	3-Sep-2024	UT106696311		20240030945	Lode
GS 764	3-Sep-2024	UT106696312		20240030946	Lode

Claim Name	Location Date	BLM Serial Number	Legacy BLM Serial Number	County Document Number	Case Type
GS 765	3-Sep-2024	UT106696313		20240030947	Lode
GS 766	3-Sep-2024	UT106696314		20240030948	Lode
GS 767	3-Feb-2025	UT106721788		20250005308	Lode
GS 768	3-Feb-2025	UT106721789		20250005309	Lode
GS 769	3-Feb-2025	UT106721790		20250005310	Lode
GS 770	3-Feb-2025	UT106721791		20250005311	Lode
GS 771	3-Feb-2025	UT106721792		20250005312	Lode
GS 772	3-Feb-2025	UT106721793		20250005313	Lode
GS 773	3-Feb-2025	UT106721794		20250005314	Lode
GS 774	3-Feb-2025	UT106721795		20250005315	Lode
GS 775	3-Feb-2025	UT106721796		20250005316	Lode
GS 776	3-Feb-2025	UT106721797		20250005317	Lode
GS 777	3-Feb-2025	UT106721798		20250005318	Lode
GS 778	3-Feb-2025	UT106721799		20250005319	Lode
GS 779	3-Feb-2025	UT106721800		20250005320	Lode
GS 780	3-Feb-2025	UT106721801		20250005321	Lode
GS 781	3-Feb-2025	UT106721802		20250005322	Lode
GS 782	4-Feb-2025	UT106721803		20250005323	Lode
GS 783	4-Feb-2025	UT106721804		20250005324	Lode
GS 784	4-Feb-2025	UT106721805		20250005325	Lode
GS 785	4-Feb-2025	UT106721806		20250005326	Lode
GS 786	4-Feb-2025	UT106721807		20250005327	Lode
GS 787	4-Feb-2025	UT106721808		20250005328	Lode
GS 788	4-Feb-2025	UT106721809		20250005329	Lode
GS 789	4-Feb-2025	UT106721810		20250005330	Lode
GS 790	4-Nov-2025	UT106764368		20250041580	Lode
GS 791	4-Nov-2025	UT106764369		20250041581	Lode
GS 792	4-Nov-2025	UT106764370		20250041582	Lode
GS 793	4-Nov-2025	UT106764371		20250041583	Lode
GS 794	4-Nov-2025	UT106764372		20250041584	Lode
GS 795	4-Nov-2025	UT106764373		20250041585	Lode
GS 796	4-Nov-2025	UT106764374		20250041586	Lode
GS 797	4-Nov-2025	UT106764375		20250041587	Lode

Claim Name	Location Date	BLM Serial Number	Legacy BLM Serial Number	County Document Number	Case Type
GS 798	4-Nov-2025	UT106764376		20250041588	Lode
GS 799	4-Nov-2025	UT106764377		20250041589	Lode
GS 800	4-Nov-2025	UT106764378		20250041590	Lode
GS 801	4-Nov-2025	UT106764379		20250041591	Lode
GS 802	4-Nov-2025	UT106764380		20250041592	Lode
GS 803	4-Nov-2025	UT106764381		20250041593	Lode
GS 804	4-Nov-2025	UT106764382		20250041594	Lode
GS 805	4-Nov-2025	UT106764383		20250041595	Lode
GS 806	4-Nov-2025	UT106764384		20250041596	Lode
GS 807	4-Nov-2025	UT106764385		20250041597	Lode
GS 808	4-Nov-2025	UT106764386		20250041598	Lode
GS 809	4-Nov-2025	UT106764387		20250041599	Lode
GS 810	4-Nov-2025	UT106764388		20250041600	Lode
GS 811	4-Nov-2025	UT106764389		20250041601	Lode
GS 812	4-Nov-2025	UT106764390		20250041602	Lode
GS 813	4-Nov-2025	UT106764391		20250041603	Lode
GS 814	4-Nov-2025	UT106764392		20250041604	Lode
GS 815	4-Nov-2025	UT106764393		20250041605	Lode
GS 816	4-Nov-2025	UT106764394		20250041606	Lode
GS 817	4-Nov-2025	UT106764395		20250041607	Lode

Table 30-2: Claims and Lease Payments Effective 23 March 2026

DESCRIPTION	PAYMENTS MADE MAR 2025-FEB 2026			2026 PAYMENT ESTIMATED
	Payment	Last paid	Paid through	
Pilot Goldstrike Inc. BLM Claim maintenance fees	$121,800	6-Aug-2025	1-Sep-2026	$128,800
Pilot Goldstrike Inc. County maintenance fees	$1,238	22-Sep-2025	1-Sep-2026	$1,308
Bauer Trust Lease	$20,000	20-Oct-2025	2-Nov-2026	$20,000
Bauer Trust Property Taxes	$496	20-Feb-2026	30-Nov-2026	$496
Bracken Trust Mining Lease	$4,000	21-May-2025	22-Jun-2026	$4,000
Bracken Trust Property Taxes	$0	30-Nov-2025	30-Nov-2026	$0
Bull Valley III LLC Lease Extension Payment	$20,000	13-Jan-2026	28-Feb-2026	$0
Bull Valley III LLC Lease 2nd Amendment	$300,000	5-Mar-2026	14-Jan-2027	$100,000
Bull Valley III LLC Property Taxes	$851	30-Nov-2025	30-Nov-2026	$851
Fraser Trust Lease	$22,000	20-Feb-2026	18-Feb-2027	$22,000
Fraser Trust Property Taxes	$318	30-Nov-2025	30-Nov-2026	$318
Marvil Investments LLC Lease	$20,000	20-Oct-2025	2-Nov-2026	$20,000
Marvil Investments LLC Property Taxes	$167	30-Nov-2025	30-Nov-2026	$167
Utah SITLA Mineral Lease	$11,112	29-Oct-2025	1-Nov-2026	$11,112
Subtotals:				
BLM Claim maintenance fees	*$121,800*			*$128,800*
County Claim maintenance fees	*$1,238*			*$1,308*
Lease Payments (Patents)	*$386,000*			*$386,000*
Property Taxes (patents)	*$1,832*			*$1,831*

State Mineral Lease	*$11,112*			*$11,112*
Total	**$521,982**			**$529,051**

Table 30-3: List of Unpatented Placer Mining Claims, Goldstrike Property, Washington County, Utah

Claim Name	Location Date	BLM Serial Number	Legacy BLM Serial Number	County Document Number	Case Type
GSP 1	23-Apr-2017	UT101784418	UMC433735	20170016712	Placer
GSP 2	23-Apr-2017	UT101784419	UMC433736	20170016713	Placer
GSP 3	23-Apr-2017	UT101784420	UMC433737	20170016714	Placer
GSP 4	23-Apr-2017	UT101784421	UMC433738	20170016715	Placer
GSP 5	23-Apr-2017	UT101785601	UMC433739	20170016716	Placer
GSP 6	23-Apr-2017	UT101785602	UMC433740	20170016717	Placer
GSP 7	23-Apr-2017	UT101785603	UMC433741	20170016718	Placer
GSP 8 *amendment*	23-Apr-2017	UT101785604	UMC433742	20170016719 *20170019463* *20170042262*	Placer
GSP 9 *amendment*	23-Apr-2017	UT101785605	UMC433743	20170016720 *20170019464* *20170042263*	Placer
GSP 10	23-Apr-2017	UT101785606	UMC433744	20170016721	Placer
GSP 11	23-Apr-2017	UT101785607	UMC433745	20170016722	Placer
GSP 12A	22-Oct-2017	UT101790288	UMC437177	20170046456	Placer
GSP 13A	22-Oct-2017	UT101790289	UMC437178	20170046457	Placer
GSP 14A	22-Oct-2017	UT101790290	UMC437179	20170046458	Placer
GSP 15 *amendment*	23-Apr-2017	UT101785608	UMC433749	20170016726 *20170019466*	Placer
GSP 16 *amendment*	23-Apr-2017	UT101785609	UMC433750	20170016727 *20170019467*	Placer

Table 30-4: List of Patented Mining Claims, Goldstrike Property, Washington County, Utah

Owner Effective Dates	Mineral Survey Number Patent Number Date, Acres (approximate) Parcel Number	Claim Names
Theon “Bud” Bauer and Annette C. Bauer, husband and wife, co-trustees of the Bauer Family Revocable Trust Effective Nov. 2, 2010 Amended Oct. 22, 2013	MS 6422 Patent 867989, Jun. 14, 1922 71.07 Ac. Parcel ZZZ-195	Wildcat Wildcat No. 1 Oro Del Ray Burdette
	MS 6768 Patent 997760, Mar. 18, 1927 127.98 Ac. Parcel ZZZ-195	Blue Jay No. 1 Blue Jay No. 2 Amadore Amadore No. 2 Jay Extension Jewell Wonder Yellow Stone Yellow Stone No. 1
Bull Valley III, LLC Effective Jan. 14, 2011 Amended Dec. 23, 2013	MS 6283 Patent 485363, Aug. 3, 1915 278.948 Ac. Parcel ZZZ-941	White Sultana Hamburg Hamburg No. 1 Hamburg No. 2 Hamburg No. 3 Hamburg No. 4 Hamburg No. 5 Fraction Primer No. 1 Primer No. 2 Septer Spot Spot No. 1 Spot No. 3 Spot No. 4
	MS 6283 Patent 589031, Jun. 23, 1917 8.051 Ac. Parcel ZZZ-941	Spot No. 2 (North Half)
The Sandra Smith Fraser Revocable Living Trust Effective Feb. 18, 2011 Amended Dec. 26, 2016	MS 6283 Patent 589031, Jun. 23, 1917 8.051 Ac. Parcel ZZZ-1209	Spot No. 2 (South Half)
	MS 6454	Search Light

Owner Effective Dates	Mineral Survey Number Patent Number Date, Acres (approximate) Parcel Number	Claim Names
Deeded to Trust Sep. 8, 2020	Patent 698535, Jul. 16, 1919 70.94 Ac. Parcel ZZZ-245	Search Light No. 1 Search Light No. 2 Central Fraction Mecca Lode
	MS 6698 Patent 927075, Dec. 18, 1923 30.63 Ac. Parcel ZZZ-245	White Star White Star No. 1
Marvil Investments LLC Effective Nov. 2, 2010 Amended Oct. 24, 2013	MS 6557 Patent 928969, Jan. 12, 1924 66.83 Ac. Parcel ZZZ-204	Bull Run Mine No. 1 Bull Run Mine No. 2 Bull Run Mine No. 3 Bull Run Mine No. 4

Table 30-5: Jennings and Goldstrike Thiriot, LLC Property Lease

Mining Lease Agreement Bracken Project (“Agreement”) by and between Jeffrey Jennings, Manager of the Claude Bracken Family Living Trust (“Owner”), and Pilot Goldstrike Inc. a Nevada corporation (“Lessee”), effective June 22, 2017.

Township-Range	Section	Lots	Acres	Parcel
T.39S., R.18W.	16	W½NW¼	80	9058
	17	NE¼SE¼; SE¼NE¼ (less 1 acre homesite)	80	9059
Total			160, more or less	

Table 30-6: Utah State Institutional Trust Lands Administration Lease, Washington County, Utah

Amended and Restated Utah State Metalliferous Minerals Lease, ML 52928, dated November 1, 2024, between the School and Institutional Trust Lands Administration on behalf of the State of Utah as trustee for the trust land beneficiaries and Pilot Goldstrike Inc.

(Replaces Mining Lease and Agreement, effective November 1, 2014, by and between the State of Utah, acting by and through the School and Institutional Trust Lands Administration (Lessor) and Cadillac South Explorations Inc.* (Lessee), Mineral Lease No. ML-52928.)

Mineral Lease	Township-Range	Sections	Lots	Acres	Effective Date	Extended Primary Term
ML-52928	T. 39 S., R. 19 W.	36	SW¼, S½SE¼	240	Nov. 1, 2024	Ends Oct. 31, 2034 (10 years)
	T. 40 S., R. 19 W.	2	Lots 1-8, S½N½, S½ [ALL]	685.88		
Total				925.88		



Making Sustainability Happen